

Reservoir Permit No. 3009

Application for a Permit to Construct a Reservoir and to Store for Beneficial Use the Unappropriated Waters of the State of Oregon

I, EDWARD ZACH (Name of Applicant) of R. RT. 1 BOX 75, Mt Angel (Mailing Address)

State of OREGON, do hereby make application for a permit to construct the following described reservoir and to store the unappropriated waters of the State of Oregon, subject to existing rights.

If the applicant is a corporation, give date and place of incorporation

1. The name of the proposed reservoir is Reservoir # 3

2. The name of the stream from which the reservoir is to be filled and the appropriation made is Bocklee Creek tributary of Zollner Creek

3. The amount of water to be stored is 2.66 acre feet.

4. The use to be made of the impounded water is Irrigation (Irrigation, power, domestic supply, etc.)

5. The location of the proposed reservoir will be in Sec. 35 Tp. 5-5, R. 1 W., W. M., in the county of Marion (Give sections or townships to be submerged)

(a) State whether situated in channel of running stream and give character of material at outlet Situated in channel of stream

(b) If not in channel of running stream, state how it is to be filled. If through a feed canal, give name and dimensions

6. The dam will be located in SE 1/4 of NW 1/4, Sec. 35 Tp. 5-5, R. 1 W., W. M. The maximum height will be 9.9 feet above stream bed or ground surface on center line of dam. The length on top will be 120 feet; length on bottom 40 feet; width on top 10 feet; slope of front or water side 3:1; slope on back 2:1; height of dam above water line when full 4.3 feet.

* A different form of application should be used for the appropriation of stored water to beneficial use. Such forms can be secured without charge, together with instructions, by addressing the State Engineer, Salem, Oregon.

7. The construction of dam, the material of which it is to be built, and method of protection from waves are as follows: *Compacted earth fill*
No wave action anticipated

8. The location of wasteway with dimensions are as follows: *Around S. end of dam*
(State whether over or around the dam)
35' bottom width 3.3' depth 1.5' side slopes

9. The location of outlet from the proposed reservoir, with character of construction and dimensions, are as follows: *12" Corrugated metal pipe 57' in length with*
(All dams across natural stream channels must be provided with an outlet conduit of such capacity and location to pass the normal flow of the stream at any time.)
3- metal Anti seep collars. Gate valve at upstream end.
A 5.7' length of 24" dia corrugated metal pipe back of gate valve for TRICKLE TUBE

10. The area submerged by the proposed reservoir, when full, will be *1.5* acres, with a maximum depth of water of *5.6* feet; and approximate mean depth of water *1.66* feet.

11. The estimated cost of the proposed work is \$ *1500*

12. Construction work will begin on or before *Aug 15-62*

13. Construction work will be completed on or before *Sept 15-62*

Edward J. ...
(Signature of applicant)

STATE OF OREGON, }
County of Marion, } ss.

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for

In order to retain its priority, this application must be returned to the State Engineer, with corrections, on or before, 19

WITNESS my hand this day of, 19

STATE ENGINEER

Remarks:

[Dotted lines for handwritten remarks]

STATE OF OREGON, }
County of Marion, } ss.

This is to certify that I have examined the foregoing application and do hereby grant the same, subject to the following limitations and conditions: The right herein granted is limited to the construction of reservoir No. 3 and storage of water from Bocklee Creek to be appropriated under application No. 37967, permit No. 28163 for irrigation.

The right hereunder shall be limited to the storage of 2.6 acre feet.

The priority date of this permit is August 17, 1962

Actual construction work shall begin on or before August 20, 1963 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1964

WITNESS my hand this 20th day of August 1962

John H. ...

STATE ENGINEER

Application No. *R 37966*
Reservoir Permit No. *R-3000*

PERMIT

To construct a reservoir and store for beneficial use the unappropriated waters of the State of Oregon.

This instrument was first received in the office of the State Engineer at Salem, Oregon, on the *17th* day of *August* 19*62*, at *2:12* o'clock *P.* M.

Returned to applicant:

Approved:

..... August 20, 1962 11 of
Recorded in Book No. 11 of
Reservoirs, on Page *3824*.

..... CHAS. L. WHEELER STATE ENGINEER

Drainage Basin No. *2* ... page *3824*