

Application for a Permit to Construct a Reservoir and to Store for Beneficial Use the Unappropriated Waters of the State of Oregon

I, PORTLAND AREA COUNCIL, BOY SCOUTS OF AMERICA, a non-profit corporation,
(Name of Applicant)

of 25 S. W. Grant Street, Portland,
(Mailing Address)

State of Oregon, do hereby make application for a permit to construct the following described reservoir and to store the unappropriated waters of the State of Oregon, subject to existing rights.

If the applicant is a corporation, give date and place of incorporation incorporated under the laws of the State of Oregon, March 26, 1925.

1. The name of the proposed reservoir is Lake Camp Baldwin

2. The name of the stream from which the reservoir is to be filled and the appropriation made is Eight Mile Creek
tributary of Columbia River

3. The amount of water to be stored is ~~40~~ Plans - 375 acre feet.

4. The use to be made of the impounded water is recreation and domestic
(Irrigation, power, domestic supply, etc.)

5. The location of the proposed reservoir will be in Sec. SE 1/4 of SE 1/4 of Section 9
(Give sections or townships to be submerged)
Tp. 2S, R. 11 E, W.M., in the county of Wasco

(a) State whether situated in channel of running stream and give character of material at outlet Natural channel of Tamarack Creek. Material is stream gravel, soil and boulders.

(b) If not in channel of running stream, state how it is to be filled. If through a feed canal, give name and dimensions Feed canal 3/4 mile long from Eight Mile Creek in Section 8, T 2S R 11 E W.M.; runs into natural channel of Tamarack Creek.

6. The dam will be located in SE 1/4 of SE 1/4 of, Sec. 9,
(Smallest legal subdivision)
Tp. 2S, R. 11 E, W.M. The maximum height will be 25 feet above stream bed or ground surface on center line of dam. The length on top will be 500 feet; length on bottom 50 feet, width on top 15 feet; slope on front or water side 2 1/2 on 1; slope on back 3 on 1; height of dam above water line when full 3 feet.
(Feet horizontal to 1 vertical) (Feet horizontal to 1 vertical)

* A different form of application should be used for the appropriation of stored water to beneficial use. Such forms can be secured without charge, together with instructions, by addressing the State Engineer, Salem, Oregon.

7. The construction of dam, the material of which it is to be built, and method of protection from waves are as follows: Rolled earth fill placed in 12" layers and compacted by 3 passes of a D.C. 6 Cat or equal.

8. The location of wasteway with dimensions are as follows: ^{Plans - 12"} 36" pipe under the dam (State whether over or around the dam) and 50 wide emergency spillway around the left abutment. plus 15" conduit by pass.

9. The location of outlet from the proposed reservoir, with character of construction and dimensions, are as follows: ^{Plans 12"} 36" outlet pipe with automatic ^{10"} 48" inflow. (All dams across natural stream channels must be provided with an outlet conduit, of such capacity and location to pass the normal flow of the stream at any time)

10. The area submerged by the proposed reservoir, when full, will be 4.5 Plans 4 35 acres, with a maximum depth of water of 20 feet; and approximate mean depth of water 6 feet.

11. The estimated cost of the proposed work is \$25,000

12. Construction work will begin on or before January 10, 1962

13. Construction work will be completed on or before January 10, 1964

**PORTLAND AREA COUNCIL,
BOY SCOUTS OF AMERICA**
(Signature of applicant)

By _____
Council President

STATE OF OREGON, }
County of Marion. } ss.

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for correction and completion

In order to retain its priority, this application must be returned to the State Engineer, with corrections on or before January 2, 1961

WITNESS my hand this 2nd day of November, 1961

RECORDED
By _____
SIA
SALEM

LEWIS A. STAPLE
STATE ENGINEER

By Walter N. Perry
Walter N. Perry
ASSISTANT

Remarks:

STATE OF OREGON, }
County of Marion, } ss.

This is to certify that I have examined the foregoing application and do hereby grant the same, subject to the following limitations and conditions: The right herein granted is limited to the construction of Lake Camp Baldwin Reservoir and storage of water from Eight Mile Creek to be appropriated under application No. 37125, permit No. 28547 for recreation, and the dam shall be constructed under the supervision of a registered professional engineer.

The right hereunder shall be limited to the storage of 37.5 acre feet
The priority date of this permit is October 11, 1961
Actual construction work shall begin on or before April 29, 1964 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1965
WITNESS my hand this 29th day of April, 1963

[Signature]
STATE ENGINEER

Application No. R-37124
Reservoir Permit No. R-3200

PERMIT

To construct a reservoir and store for beneficial use the unappropriated waters of the State of Oregon.

This instrument was first received in the office of the State Engineer at Salem, Oregon, on the 11 day of April, 1942, at 10 o'clock A.M.

Returned to applicant:

Approved:

April 29 1942

Recorded in Book No. 3200 of
Reservoirs, on Page

Charles L. Stoddard
State Engineer

Drainage Basin No. 4 page 2

Fees