

Application for a Permit to Construct a Reservoir and to Store for Beneficial Use the Unappropriated Waters of the State of Oregon

I, VALLEY MEMORIAL PARK, INC.
(Name of Applicant)

of 25755 S W Tualatin Valley Highway Hillsboro, Oregon.
(Mailing Address)

State of Oregon, do hereby make application for a permit to construct the following described reservoir and to store the unappropriated waters of the State of Oregon, subject to existing rights.

If the applicant is a corporation, give date and place of incorporation 1958
Hillsboro, Oregon

1. The name of the proposed reservoir is _____

2. The name of the stream from which the reservoir is to be filled and the appropriation made is Unnamed intermittent tributary of Rock Creek

tributary of Rock Creek

3. The amount of water to be stored is 240 acre feet

4. The use to be made of the impounded water is See Remarks section
(Irrigation, power, domestic supply, etc.)

5. The location of the proposed reservoir will be in Sec. 9
(Give sections or townships to be surveyed)

Tp. 1S, R. 2W, W.M., in the county of Washington

(a) State whether situated in channel of running stream and give character of material at outlet

The dam will be situated in the channel of an intermittent stream.

(b) If not in channel of running stream, state how it is to be filled. If through a feed canal, give name and dimensions the reservoir is to be maintained during the summer months

by pumping water from Rock Creek

6. The dam will be located in NW₄ of NW₂ Sec. 9
(Smallest legal subdivisions)

Tp. 1S, R. 2W, W.M. The maximum height will be 12 feet above stream bed or ground surface on center line of dam. The length on top will be 310 feet, length on bottom 85 feet; width on top 16 feet; slope on front

or water side 3:1; slope on back 3:1; height of dam above water line when full 3.6 feet.

(Feet horizontal to 1 vertical)

(Feet horizontal to 1 vertical)

* A different form of application should be used for the appropriation of stored water to beneficial use. Such form is available without charge, together with instructions, by addressing the State Engineer, Salem, Oregon.

7. The construction of dam, the material of which it is to be built, and method of protection from waves are as follows: The dam is to be constructed of compacted earth fill. The dam and spillway are to be protected from erosion by seeding to a sod forming grass.

8. The location of wasteway with dimensions are as follows: The spillway will be located around the right end of the north fill. The bottom width of the spillway will be 20'.
(State whether over or around the dam)

9. The location of outlet from the proposed reservoir, with character of construction and dimensions, are as follows: The outlet will consist of a 12" dia CMP cradeled in concrete, located under the north fill.
(All dams across natural stream channels must be provided with an outlet conduit, of such capacity and location to pass the normal flow of the stream at any time)

10. The area submerged by the proposed reservoir, when full, will be 7.815 acres, with a maximum depth of water of 9 feet; and approximate mean depth of water 3.1 feet.

11. The estimated cost of the proposed work is \$ 6800

12. Construction work will begin on or before Nov. 1, 1963

13. Construction work will be completed on or before Nov. 1, 1964

Valley Memorial Park, Inc.
(Signature of Applicant)

[Handwritten Signature]

STATE OF OREGON,)

County of Marion,)

I, _____, County Clerk, have examined the foregoing application, together with the accompanying maps and data, and find them to be true and correct.

In witness whereof, at _____, Oregon, this _____ day of _____, 1963.

_____ and _____ 31 day of May 1963

CHRIS B. WHEELER

STATE ENGINEER

By

[Handwritten Signature]

ASSISTANT

Remarks: This reservoir is being constructed with the twofold purpose of
a) a non consumptive use in landscaping the Valley Memorial park and
b) providing a secondary supply of water to supplement the existing
water rights held by this corporation.

It appears at this time that the reservoir will not be used for
supplemental irrigation for 3 or 4 years during which time a water right
would expire. A water right form will be filled out and sent in prior to
the time when it is anticipated that the supplemental irrigation water
will be needed.

STATE OF OREGON,)
County of Marion,) ss.

This is to certify that I have examined the foregoing application and do hereby grant the same
subject to the following limitations and conditions: The right herein granted is limited to the construction
of a reservoir and storage of water from an unnamed stream to be appropriated under
application No. 38885, permit No. 28954 for landscaping the Valley Memorial
Park, and the dam shall be constructed under the supervision of a registered
professional engineer.

The right hereunder shall be limited to the storage of 24.0 acre feet

The priority date of this permit is July 8, 1963

Actual construction work shall begin on or before September 23, 1964

shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1965

WITNESS my hand this 20th day of September 1963

Robert W. L...
STATE ENGINEER *amp*

Application No. *R-38776*

Reservoir Permit No. *R-3415*

PERMIT

To construct a reservoir and store for beneficial use the unappropriated waters of the State of Oregon.

This instrument was first received in the office of the State Engineer at Salem, Oregon, on the *30th* day of *May*, 196*3*, at *6:45* o'clock *A.* M.

Returned to applicant:

Approved:

September 20, 1963

Recorded in Book No. *12* of

Reservoirs, on Page *3415*

CHRIS L. WHEELER

State Engineer

Drainage Basin No. *R* page *62A20*

Fees