

Reservoir Permit No. 396

APPLICATION NO. 4937

APPLICATION FOR A PERMIT TO CONSTRUCT A RESERVOIR AND TO STORE FOR BENEFICIAL USE THE UNAPPROPRIATED WATERS OF THE STATE OF OREGON

I, Minam Lake Reservoir Co.

(Name of Applicant.)

of Lostine, County of Malheur

(Postoffice)

State of Oregon, do hereby make application for a permit to construct the following described reservoir and to store the unappropriated waters of the State of Oregon, subject to existing rights.

If the applicant is a corporation, give date and place of incorporation April 13, 1916,

Lostine, Ore.

1. The name of the proposed reservoir is MINAM LAKE RESERVOIR CO'S

2. The name of the stream from which the reservoir is to be filled and the appropriation made is

Minam River

3. The amount of water to be stored is 1000 acre feet.

4. The use to be made of the impounded water is Irrigation & Domestic to be appropriated under Application 4936, Permit No. 3271 (Irrigation, power, domestic supply, etc.)

5. The location of the proposed reservoir will be in Sec. 30 Twp. 4 S R 44 E.

(Give sections or townships to be submerged)

Wallowa County

(a) State whether situated in channel of running stream and give character of material at outlet Minam Lake is to be used as Reservoir at the head of the Minam & Middle Fork of the Wallowa River

(b) If not in channel of running stream, state how it is to be filled. If through a feed canal, give name and dimensions To be filled from natural watershed.

6. The dam will be located in Sec. 30

(Smallest legal subdivision)

*A different form of application should be used for the appropriation of stored water to beneficial use. Such forms can be secured without charge, together with instructions, by addressing the State Engineer, Salem, Oregon.

Tp. 4 S R. 44 E W. M. It will be No. 1 will be 14 ft.
(No. N. or S.) (No. E. or W.) No. 2 will be 14 feet in height, having a length
 on top of 225 (No. 1) feet; length on bottom 0 feet; width on top 10 ft. No. 3
65 (No. 2) feet; width on top 10 ft. No. 3
3 (No. 3) feet; width on top 10 ft. No. 3
 slope of front or water side 3 to 1 ft.
 slope on back 2 ft. to 1 ft. (Feet horizontal to 1 vertical); height of dam above water
 line when full 4 ft. No. 1 & 2 (Feet horizontal to 1 vertical)
3 " No. 3 feet.

7. The construction of dam, the material of which it is to be built, and method of protection from waves are as follows: Earth fill with brush and rock riprap

8. The location of wasteway with dimensions are as follows: Around or to one side of the dam. Open ditch (State whether over or around the dam)

9. The location of outlet from the proposed reservoir, with character of construction and dimensions, are as follows: The outlet will be through the center of Dam. No. 1, will be of 24" Wood stave pipe 1 1/2" shell (State whether through or around the proposed dam)

10. The area submerged by the proposed reservoir, when full, will be 115 acres, with a maximum depth of water of 10 feet, and approximate mean depth of water Present area at low water 85 acres, depth not known.

11. The estimated cost of the proposed work is \$ 2,000.00

12. Construction work will begin on or before One year from approval

13. Construction work will be completed on or before Two years from approval

Duplicate maps of the proposed reservoir and storage works, prepared in accordance with the rules of State Water Board of Control, accompany this application.

Minam Lake Reservoir Co.

(Name of applicant)

by Jay Lewis, Pres.

Signed in the presence of us as witnesses:

(1) S P Crow Lostine, Oregon
(Name) (Address of witness)

(2) E O Allen Lostine, Oregon
(Name) (Address of witness)

Remarks:

STATE OF OREGON, }
County of Marion } ss.

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for correction or completion, as follows:
\$8.00 fees= For completion & maps

In order to retain its priority, this application must be returned to the State Engineer, with corrections, on or before.....
Feb. 17 1917
December 7 1916

11th - Jan. - 1917
WITNESS my hand this 7 day of November, 1916

John H Lewis
L.A. State Engineer.

STATE OF OREGON, }
County of Marion } ss.

This is to certify that I have examined the foregoing application and do hereby grant the same, subject to the following limitations and conditions:
The right under this permit shall be limited to the storage of water for irrigation and domestic purposes to be appropriated under Application No. 4936, Permit No. 3271.

The right hereunder shall be limited to the storage of 1000 acre feet.

The priority date of this permit is May 29, 1916.

Actual construction work shall begin on or before February 28, 1918

and shall thereafter be prosecuted with reasonable diligence and be completed on or before June 1, 1919

WITNESS my hand this 28th day of February, 1917, 19

John H Lewis
State Engineer.

EXTENDED TO 6/1/20-6/1/21-6/1/22

8

Application No. 4935

Reservoir Permit No. 396

PERMIT
TO CONSTRUCT A RESERVOIR AND STORE FOR
BENEFICIAL USE THE UNAPPROPRIATED
WATERS OF THE STATE OF OREGON

Division No. 2 District No.

*This instrument was first received in the office
of the State Engineer at Salem, Oregon, on the
29 day of May
1916 at 1:30 o'clock P.M.*

*Returned to applicant for correction
Nov 7, 1916
Jan 12, 1917*

*Corrected application received
Feb 9, 1917
Nov 28, 1916*

*Approved
Feb 28, 1917*

*Recorded in Book No. 21 of Reservoirs on
Page 396*

John H Lewis

State Engineer.

1 map RS

\$8.00