

3975

Reservoir Permit No.

Application for a Permit to Construct a Reservoir and to Store for Beneficial Use the Unappropriated Waters of the State of Oregon

I, Neil W. Rankin (Name of Applicant)

of Route 1, Box 37-A, Gaston (Mailing Address)

State of Oregon, do hereby make application for a permit to construct the following described reservoir and to store the unappropriated waters of the State of Oregon, subject to existing rights.

If the applicant is a corporation, give date and place of incorporation

1. The name of the proposed reservoir is Unnamed

2. The name of the stream from which the reservoir is to be filled and the appropriation made is un-named

tributary of Williams Creek

3. The amount of water to be stored is One (1) acre feet.

4. The use to be made of the impounded water is Wildlife and recreation (Irrigation, power, domestic supply, etc.)

5. The location of the proposed reservoir will be in Sec. 9 (Give sections or townships to be submerged)

Tp. 2 S R. 4 W, W.M., in the county of Yamhill

(a) State whether situated in channel of running stream and give character of material at outlet In channel of running creek. Land adjacent to creek has good top soil, sometimes called shot soil.

(b) If not in channel of running stream, state how it is to be filled. If through a feed canal, give name and dimensions

6. The dam will be located in N.W. Quarter of N.W. Quarter of Sec. 9 (Smallest legal subdivision)

Tp. 2 S R. 4 W, W.M. The maximum height will be 10 feet above stream bed or ground surface on center line of dam. The length on top will be 130 feet; length on bottom 50 feet; width on top 10 feet; slope on front or water side 3 to 1; slope on back 3 to 1; height of dam above water line when full 2 1/2 feet.

\* A different form of application should be used for the appropriation of stored water to beneficial use. Such forms can be obtained together with instructions, by addressing the State Engineer, Salem, Oregon 97310

7. The construction of dam, the material of which it is to be built, and method of protection from waves are as follows: This will be an earthen dam, 10 ft. high and 70 ft. wide at the bottom. Wheel tractors will be used to pack earth during construction. Waste way around N. end of dam to be ~~8~~ 8 ft. wide and 2<sup>1</sup>/<sub>2</sub> ft. deep and 2<sup>1</sup>/<sub>2</sub> ft. below top of dam. Waste way will be of concrete construction.

8. The location of wasteway with dimensions are as follows: Around N. end of dam, ~~6~~ to 8 feet wide by 2<sup>1</sup>/<sub>2</sub> ft. in depth, with ~~approximately~~ 3" lining of concrete. (State whether over or around the dam)

9. The location of outlet from the proposed reservoir, with character of construction and dimensions, are as follows: 8" steel pipe - 70 Ft. long with ~~3~~ <sup>7</sup> or ~~4~~ concrete collars, also has an ~~8~~ <sup>7</sup> ft. vertical stand pipe. (All dams across natural stream channels must be provided with an outlet conduit of such capacity and location to pass the normal flow of the stream at any time)

10. The area submerged by the proposed reservoir, when full, will be .3 acres, with a maximum depth of water of 8 feet; and approximate mean depth of water 3 feet.

11. The estimated cost of the proposed work is \$ 850.00

12. Construction work will begin on or before Sept. 1, 1964

13. Construction work will be completed on or before Oct. 1, 1964

Signature of applicant:

*Robert W. K... ..*

STATE OF OREGON.

County of Marion.

I hereby certify that I have examined the foregoing application, together with the accompanying plans and reports, and find that the same conform to the requirements of the law for the completion of the same.

In testimony whereof, priority, this application must be returned to the State Engineer, with correct fee, on or before

July 3, 1964.

WITNESS my hand this 2th day of May, 1964.

BRUCE L. MEHLER

STATE ENGINEER

By

*Walter Perry*

ASSISTANT

Remarks: MY PURPOSE FOR CONSTRUCTING THIS DAM IS TO STOCK WITH FISH. EITHER TROUT OR BASS. ALSO I THINK THIS POND WILL ADD TO THE APPEARANCE OF THE PLACE. IF THE IDEA OF THE FISH DOES NOT MATERIALIZE THEN IT WILL BE USED AS A DUCK LAKE. AS FOR RECREATION THIS SHOULD BE A NICE FAMILY PICNIC SPOT WITH THE NATURAL TREES IN THE AREA.

STATE OF OREGON, }  
County of Marion, } ss.

This is to certify that I have examined the foregoing application and do hereby grant the same subject to the following limitations and conditions: The right herein granted is limited to the construction of a reservoir and storage of water from an unnamed stream to be appropriated under application No. 39958, permit No. 29679 for fish culture and recreation.

The right hereunder shall be limited to the storage of 1.0 acre feet.  
The priority date of this permit is April 21, 1964  
Actual construction work shall begin on or before July 31, 1965 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1966  
WITNESS my hand this 31st day of July, 1964

*Chris L. Wheeler*  
STATE ENGINEER

Application No. *13-3776-C*

Reservoir Permit No. *R-3975*

### PERMIT

To construct a reservoir and store for beneficial use the unappropriated waters of the State of Oregon.

This instrument was first received in the office of the State Engineer at Salem, Oregon, on the *21<sup>st</sup>* day of *April*, 19*64*, at *Five* o'clock *A.* M.

Returned to applicant:

Approved: *July 27, 1964*

Recorded in Book No. \_\_\_\_\_ of \_\_\_\_\_  
Reservoirs, on Page **3975**

*CHRIS I. WHEELER*  
State Engineer

Drainage Basin No. *R* page *62A21*

Fees .....