

# Application for a Permit to Construct a Reservoir and to Store for Beneficial Use the Unappropriated Waters of the State of Oregon

I, Robert L. Stockhoff  
(Name of Applicant)

of Route 1 Box 32 Dayton  
(Mailing Address)

State of Oregon, do hereby make application for a permit to construct the following described reservoir and to store the unappropriated waters of the State of Oregon, subject to existing rights.

If the applicant is a corporation, give date and place of incorporation

1. The name of the proposed reservoir is Stockhoff Reservoir

2. The name of the stream from which the reservoir is to be filled and the appropriation made is Tributary to west Palmer Creek  
tributary of Yamhill River

3. The amount of water to be stored is 6.5 acre feet.

4. The use to be made of the impounded water is Irrigation  
(Irrigation, power, domestic supply, etc.)

5. The location of the proposed reservoir will be in Sec. 6  
(Give sections or townships to be submerged)  
Tp. 5S, R. 3W, W.M., in the county of Yamhill

(a) State whether situated in channel of running stream and give character of material at outlet  
Intermittent Silt loam

(b) If not in channel of running stream, state how it is to be filled. If through a feed canal, give name and dimensions  
Catch Winter Run off

6. The dam will be located in NE 1/4 SE 1/4 NW 1/4, Sec. 6  
(Smallest legal subdivision)  
Tp. 5S, R. 3W, W.M. The maximum height will be 10 feet above stream bed or ground surface on center line of dam. The length on top will be 270 feet; length on bottom 55 feet; width on top 10 feet; slope on front or water side 3 to 1; slope on back 2 to 1; height of dam above water line when full 2.5 feet.  
(Feet horizontal to 1 vertical) (Feet horizontal to 1 vertical)

\* A different form of application should be used for the appropriation of stored water to beneficial use. Such forms can be secured without charge, together with instructions, by addressing the State Engineer, Salem, Oregon 97310.

7. The construction of dam, the material of which it is to be built, and method of protection from waves are as follows: Earth Rolled in thin layers  
No way protection need

8. The location of wasteway with dimensions are as follows: Around the dam,  
(State whether over or around the dam)  
bottom width 40 ft and min depth 2.5 ft.

9. The location of outlet from the proposed reservoir, with character of construction and dimensions, are as follows: under dam 10 in coated steel pipe  
(All dams across natural stream channels must be provided with an outlet conduit, of such capacity and location to pass the normal flow of the stream at any time)

10. The area submerged by the proposed reservoir, when full, will be 1.8 acres, with a maximum depth of water of 7.5 feet; and approximate mean depth of water 3.6 feet.

11. The estimated cost of the proposed work is \$ 2500<sup>00</sup>

12. Construction work will begin on or before 1 Oct. 1966

13. Construction work will be completed on or before 1 Nov 1966

Robert L. Stockhoff  
(Signature of applicant)

STATE OF OREGON, }  
County of Marion, } ss.

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for .....

In order to retain its priority, this application must be returned to the State Engineer, with corrections on or before ....., 19.....

WITNESS my hand this ..... day of ....., 19.....

STATE ENGINEER  
By ..... ASSISTANT

Remarks: I have permits to irrigate land adjoining  
this reservoir. Permit G-1527 and permit G-2128

STATE OF OREGON, }  
County of Marion, } ss.

This is to certify that I have examined the foregoing application and do hereby grant the same, subject to the following limitations and conditions: The right herein granted is limited to the construction of Stockoff Reservoir and storage of water from an unnamed stream to be appropriated under application No. 42922, permit No. 31859 for irrigation and supplemental irrigation.

The right hereunder shall be limited to the storage of 6.5 acre feet.

The priority date of this permit is October 13, 1966

Actual construction work shall begin on or before April 11, 1968 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1968.

WITNESS my hand this 11th day of April, 1967

*[Signature]*

STATE ENGINEER

A

Application No. R-47921  
Reservoir Permit No. R 4838

**PERMIT**

To construct a reservoir and store for beneficial use the unappropriated waters of the State of Oregon.

This instrument was first received in the office of the State Engineer at Salem, Oregon, on the 13<sup>th</sup> day of October, 1966, at 11:50 o'clock A. M.

Returned to applicant:

Approved:

..... April 11, 1967 .....

Recorded in Book No. .... of

Reservoirs, on Page R 4838

..... CHRIS L. WHEELER  
State Engineer .....

Drainage Basin No. 2 page 9081

Fees \$15.00