

Application for a Permit to Construct a Reservoir and to Store for Beneficial Use the Unappropriated Waters of the State of Oregon

CERTIFICATE NO. 44151

I, Edward J. Wageman (Name of Applicant)

of Rte. 4 Box 950, x Roseburg, Oregon 97470 (Mailing Address)

State of Oregon, do hereby make application for a permit to construct the following described reservoir and to store the unappropriated waters of the State of Oregon, subject to existing rights.

If the applicant is a corporation, give date and place of incorporation

1. The name of the proposed reservoir is Hidden Valley Dam and Reservoir

2. The name of the stream from which the reservoir is to be filled and the appropriation made is

Unnamed intermittent stream tributary of Ten Mile Creek

3. The amount of water to be stored is 50 acre feet.

4. The use to be made of the impounded water is irrigation (Irrigation, power, domestic supply, etc.)

5. The location of the proposed reservoir will be in Sec. 25 (Give sections or townships to be submerged)

Tp. 28 S R. 8, W.M., in the county of Douglas

(a) State whether situated in channel of running stream and give character of material at outlet

Intermittent stream. Gravely clay

(b) If not in channel of running stream, state how it is to be filled. If through a feed canal, give name and dimensions

6. The dam will be located in NW 1/4 SE 1/4, Sec. 25 (Smallest legal subdivision)

Tp. 28 S, R. 8 W, W.M. The maximum height will be 41 feet above stream bed or ground

surface on center line of dam. The length on top will be 500 feet; length on

bottom 5 feet; width on top 19 1/6 feet; slope on front

or water side 3:1; slope on back 2:1; height of dam above water line (Feet horizontal to 1 vertical)

when full 5 feet.

* A different form of application should be used for the appropriation of stored water to beneficial use. Such forms can be secured without charge, together with instructions, by addressing the State Engineer, Salem, Oregon 97310.

R 5427

7. The construction of dam, the material of which it is to be built, and method of protection from waves are as follows: earth fill - gravelly clay - grass face as reservoir is less than 1000 ft long

8. The location of wasteway with dimensions are as follows: around end of dam in rock. (State whether over or around the dam) 10 ft. bottom width with 1 1/2:1 side slopes

9. The location of outlet from the proposed reservoir, with character of construction and dimensions, are as follows: installation of 18 in. asphalt dipped coorugated pipe (All dams across natural stream channels must be provided with an outlet conduit, of such capacity and location to pass the normal flow of the stream at any time) equipped with head gate and seepage collars at 25 ft. intervals

10. The area submerged by the proposed reservoir, when full, will be 4 acres, with a maximum depth of water of 28 feet; and approximate mean depth of water 12 1/2 feet.

11. The estimated cost of the proposed work is \$ 25,000

12. Construction work will begin on or before Oct. 1 1968

13. Construction work will be completed on or before Oct. 1 1969

Edward J. Wogeman (Signature of applicant) Emma J. Wogeman

STATE OF OREGON, ss. County of Marion,

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for Completion

In order to retain its priority, this application must be returned to the State Engineer, with corrections on or before March 25th, 1969 June 16th 69

WITNESS my hand this 14th day of April, 1969

RECEIVED JUL 28 1969 STATE ENGINEER SALEM, OREGON

RECEIVED APR 16 1969 STATE ENGINEER SALEM, OREGON

CHRIS L. WHEELER STATE ENGINEER ASSISTANT

Handwritten signature of Chris L. Wheeler

Remarks: This dam is proposed to furnish a supplemental water supply for Applications Nos. 20016 and 41354. Permits Nos. 15587 and 30891. Owing to permits having priority, Ten Mile Creek during periods of minimum discharge does not furnish sufficient water to irrigate the lands authorized.

STATE OF OREGON, }
County of Marion, } ss.

This is to certify that I have examined the foregoing application and do hereby grant the same, subject to the following limitations and conditions: The right herein granted is limited to the construction of Hidden Valley Reservoir and storage of water from an unnamed stream to be appropriated under application No. 43949, permit No. 34136 for supplemental irrigation and the dam shall be constructed under the supervision of a registered professional engineer

The right hereunder shall be limited to the storage of 50.0 acre feet.

The priority date of this permit is July 28, 1969

Actual construction work shall begin on or before August 25, 1970 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1971

WITNESS my hand this 25th day of August, 1969. Extended to Oct. 1 1972

John K. ...
STATE ENGINEER

Application No. R-43948

Reservoir Permit No. R-5427

PERMIT

To construct a reservoir and store for beneficial use the unappropriated waters of the State of Oregon.

This instrument was first received in the office of the State Engineer at Salem, Oregon, on the 15th day of August, 1967, at 8:00 o'clock A. M.

Returned to applicant:

Approved:

August 25, 1969

Recorded in Book No. _____ of

Reservoirs, on Page R-5427

CHRIS L. WHEELER
State Engineer

Drainage Basin No. 15 page 37H
Fees \$20.00