

RECEIVED
JAN 21 1967
STATE ENGINEER
SALEM, OREGON

CERTIFICATE NO. 51574

ASSIGNED, See Misc. Reg., Vol. 6 Page 1043

* Reservoir Permit No. R 5601

Application for a Permit to Construct a Reservoir and to Store for Beneficial Use the Unappropriated Waters of the State of Oregon

I, John Stringer (Name of Applicant)

of Nyssa, (Mailing Address)

State of Oregon, do hereby make application for a permit to construct the following described reservoir and to store the unappropriated waters of the State of Oregon, subject to existing rights.

If the applicant is a corporation, give date and place of incorporation

1. The name of the proposed reservoir is Stinking Water Creek Reservoir

2. The name of the stream from which the reservoir is to be filled and the appropriation made is

Stinking Water Creek

tributary of Middle Fork of Malheur River

3. The amount of water to be stored is 1,169 acre feet.

4. The use to be made of the impounded water is irrigation
(Irrigation, power, domestic supply, etc.)

5. The location of the proposed reservoir will be in Sec. 20
(Give sections or townships to be submerged)

Tp. 22 S., R. 35 E., W.M., in the county of Harney

(a) State whether situated in channel of running stream and give character of material at outlet

In the channel of Stinking Water Creek. Material at outlet stream sands and gravels.

(b) If not in channel of running stream, state how it is to be filled. If through a feed canal, give name and dimensions

6. The dam will be located in NW¹ NE¹ (Smallest legal subdivision), Sec. 20,

Tp. 22 S., R. 35 E., W.M. The maximum height will be 71 feet above stream bed or ground

surface on center line of dam. The length on top will be 333 feet; length on

bottom 50 feet; width on top 20 feet; slope on front

or water side 3:1; slope on back 2:1; height of dam above water line

(Feet horizontal to 1 vertical) (Feet horizontal to 1 vertical)

when full 5 feet.

* A different form of application should be used for the appropriation of stored water to beneficial use. Such forms can be secured without charge, together with instructions, by addressing the State Engineer, Salem, Oregon 97310.

7. The construction of dam, the material of which it is to be built, and method of protection from waves are as follows: Dam is earth fill with sand and gravel filter drains. Rip rap to the dimensions shown on the plan.

8. The location of wasteway with dimensions are as follows: 900 feet, more or less (State whether over or around the dam) Northwestery of North end of dam. b=70 ft. z=1

9. The location of outlet from the proposed reservoir, with character of construction and dimensions, are as follows: 30" asbestos bonded, asphalt dipped 10 ga. CMP through the dam, (All dams across natural stream channels must be provided with an outlet conduit, of such capacity and location to pass the normal flow of the stream at any time) with Armco Model 50-100 gate.

10. The area submerged by the proposed reservoir, when full, will be 106 acres, with a maximum depth of water of 54 feet; and approximate mean depth of water 22.6 feet.

11. The estimated cost of the proposed work is \$ 15,000

12. Construction work will begin on or before July 1, 1966

13. Construction work will be completed on or before Jan. 5, 1967

X John Stinger (Signature of applicant)

STATE OF OREGON, } ss. County of Marion,

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for Completion

In order to retain its priority, this application must be returned to the State Engineer, with corrections on or before March 27th, 1967.

WITNESS my hand this 25th day of January, 1967

RECEIVED FEB 15 1967

STATE ENGINEER SALEM OREGON

CHRIS L. WHEELER STATE ENGINEER

Handwritten signature of Chris L. Wheeler, Assistant State Engineer

Remarks: This application is for the storage of that amount above Permit R-4609.

[Dotted lines for notes]

STATE OF OREGON, }
County of Marion, } ss.

This is to certify that I have examined the foregoing application and do hereby grant the same, subject to the following limitations and conditions: The right herein granted is limited to the construction of Stinking Water Creek Reservoir and the storage of water from Stinking Water Creek to be appropriated under application No. 43279, permit No. 34957, for supplemental irrigation and is subject to the terms and conditions of an order of the State Engineer entered February 15, 1962.

The right hereunder shall be limited to the storage of 11,690 acre feet.

The priority date of this permit is January 24, 1967.

Actual construction work shall begin on or before January 11, 1972 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1972.

WITNESS my hand this 11th day of January, 1971.

[Signature]
STATE ENGINEER

cc
45

PC

Application No. R-43227
Reservoir Permit No. R 5601

PERMIT

To construct a reservoir and store for beneficial use the unappropriated waters of the State of Oregon.

This instrument was first received in the office of the State Engineer at Salem, Oregon, on the 24th day of January, 1967, at 5:00 o'clock P. M.

Returned to applicant:

Approved:

.....
January 11, 1971

Recorded in Book No. of
Reservoirs, on Page **R 5601**

.....
CHRIS L. WHEELER
State Engineer

Drainage Basin No. 10 page 15D

Fees \$24.85 -