

* Reservoir Permit No. R 6128

Application for a Permit to Construct a Reservoir and to Store for Beneficial Use the Unappropriated Waters of the State of Oregon

I, Oregon Berry Packing Company
(Name of Applicant)

of Route 4, Box 198 A, Hillsboro
(Mailing address) (City)

State of Oregon, 97123, do hereby make application for a permit to construct the
(Zip Code)
 following described reservoir and to store the unappropriated waters of the State of Oregon, subject to existing rights.

If the applicant is a corporation, give date and place of incorporation (Partnership)

1. The name of the proposed reservoir is L.R.M. Pond

2. The name of the stream from which the reservoir is to be filled and the appropriation made is
Unnamed stream.

tributary of Christensen Creek - Tualatin River.

3. The amount of water to be stored is 19.8 acre feet.

4. The use to be made of the impounded water is Irrigation and Supplemental Irrigation.
(Irrigation, power, domestic supply, etc.)

5. The location of the proposed reservoir will be in Sec. 31 (NE 1/4 NW 1/4)
(Give sections or townships to be submerged)

Tp. 1S, R. 2W, W.M., in the county of Washington.

(a) State whether situated in channel of running stream and give character of material at outlet
In channel of an intermittent stream - material at outlet is brown loam
with some clay.

(b) If not in channel of running stream, state how it is to be filled. If through a feed canal, give name and dimensions
Pool level to be maintained during summer months by pumping
from existing well (see attached map for location). The well has water
right certificate GR-459.

6. The dam will be located in NE 1/4 NW 1/4, Sec. 31
(Smallest legal subdivision)

Tp. 1S, R. 2W, W.M. The maximum height will be 12 feet above stream bed or ground surface on center line of dam. The length on top will be 1,700 feet; length on bottom 70 feet; width on top 10 feet; slope on front or water side 3:1; slope on back 2:1; height of dam above water line when full 4.0 feet.
(Feet horizontal to 1 vertical) (Feet horizontal to 1 vertical)

* A different form of application should be used for the appropriation of stored water to beneficial use. Such forms can be secured without charge, together with instructions, by addressing the State Engineer, Salem, Oregon 97310.

7. The construction of dam, the material of which it is to be built, and method of protection from waves are as follows: Compacted homogenous earthfill with grass covered slopes both up and downstream.

8. The location of wasteway with dimensions are as follows: a 30 ft. wide emergency spillway around the east end of the dam.
(State whether over or around the dam)

9. The location of outlet from the proposed reservoir, with character of construction and dimensions, are as follows: An 8" CMP from inlet box to 12" CMP riser. A 12" CMP from riser to downstream toe of dam. Water surface of the pond will be drawn down during winter months 3.0 feet below normal water surface by means of a side inlet in riser.
(All dams across natural stream channels must be provided with an outlet conduit, of such capacity and location to pass the normal flow of the stream at any time)

10. The area submerged by the proposed reservoir, when full, will be 2.7 acres, with a maximum depth of water of 11 feet; and approximate mean depth of water 7.33 feet.

11. The estimated cost of the proposed work is \$ 15,000

12. Construction work will begin on or before August 15, 1975

13. Construction work will be completed on or before October 1, 1975

Ray J. Mikulak
(Signature of applicant)

STATE OF OREGON, }
County of Marion, } ss.

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for

In order to retain its priority, this application must be returned to the State Engineer, with corrections on or before, 19.....

WITNESS my hand this day of, 19.....

STATE ENGINEER

By ASSISTANT

Remarks:

STATE OF OREGON, }
County of Marion, } ss.

This is to certify that I have examined the foregoing application and do hereby grant the same, subject to the following limitations and conditions: The right herein granted is limited to the construction of L.R.M. Pond and storage of water from an unnamed stream to be appropriated under Application No. 53050, Permit No. 37849., for irrigation.

The right hereunder shall be limited to the storage of19.8..... acre feet.

The priority date of this permit isApril 29, 1975.....

Actual construction work shall begin on or beforeJuly 16, 1976..... and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1977...

WITNESS my hand this16th.... day ofJuly....., 1975..

Water Resources Director XXXXXXXXXXXXXXX

ok

Application No. *R-53059*
Reservoir Permit No. **R 6128**

PERMIT

To construct a reservoir and store for beneficial use the unappropriated waters of the State of Oregon.

This instrument was first received in the office of the State Engineer at Salem, Oregon, on the *29th* day of *April*, 19*75*, at *2:45* o'clock *P*. M.

Returned to applicant:

Approved:

July 16, 1975

Recorded in Book No. _____ of Reservoirs, on Page **R 6128**

James E. Sexson
State Engineer

Drainage Basin No. *2* page *62B19*

Fees *25.00*