

### Application for a Permit to Construct a Reservoir and to Store for Beneficial Use the Unappropriated Waters of the State of Oregon

I, W. J. Conrad  
(Name of Applicant)  
of Marshfield, County of Coos  
(Postoffice)  
State of Oregon, do hereby make application for a permit to construct the following described reservoir and to store the unappropriated waters of the State of Oregon, subject to existing rights.

If the applicant is a corporation, give date and place of incorporation

1. The name of the proposed reservoir is Sunset Beach Reservoir

2. The name of the stream from which the reservoir is to be filled and the appropriation made is An Unnamed Creek  
tributary of Big Creek

3. The amount of water to be stored is 0.07 acre feet.

4. The use to be made of the impounded water is Domestic supply  
(Irrigation, power, domestic supply, etc.)

5. The location of the proposed reservoir will be in Sec. 9, Twp. 26 S., R. 14 W. in the SW $\frac{1}{4}$  of SE $\frac{1}{4}$   
(Give sections or townships to be submerged)

(a) State whether situated in channel of running stream and give character of material at outlet  
Situated in the channel of a running stream at a point where a soft shale rock lies within a foot of the surface of the ground.

(b) If not in channel of running stream, state how it is to be filled. If through a feed canal, give name and dimensions

6. The dam will be located in SW $\frac{1}{4}$  of SE $\frac{1}{4}$ , Sec. 9,  
(Smallest legal subdivision)  
Tp. 26 S, R. 14 W, W. M. It will be 10 feet in height,  
(No. N. or S.) (No. E. or W.)

\* A different form of application should be used for the appropriation of stored water to beneficial use. Such forms can be secured without charge, together with instructions, by addressing the State Engineer, Salem, Oregon.

having a length on top of 25 feet; length on bottom 10 feet; width on top 8 feet slope of front or water side 1 to 1 (Feet horizontal to 1 vertical) slope on back 1 to 4 (Feet horizontal to 1 vertical); height of dam above water line when full 1 feet.

7. The construction of dam, the material of which it is to be built, and method of protection from waves are as follows: Timber crib construction filled in with earth and rock, with the upstream face covered with 2 inch tongue and grooved lumber to a height of 1 foot above bottom of spillway.

8. The location of wasteway with dimensions are as follows: Spillway 2 ft. wide and 1 ft. deep over the top of the dam. (State whether over or around the dam)

9. The location of outlet from the proposed reservoir, with character of construction and dimensions, are as follows: 4 " pipe through the proposed dam (State whether through or around the proposed dam)

10. The area submerged by the proposed reservoir, when full, will be 0.02 acres, with a maximum depth of water of 7 feet; and approximate mean depth of water 4 feet.

11. The estimated cost of the proposed work is \$ 400.00

12. Construction work will begin on or before May 1st, 1930

13. Construction work will be completed on or before June 1st, 1930

Duplicate maps of the proposed reservoir and storage works, prepared in accordance with the rules of the State Water Board, accompany this application.

W. J. Conrad (Name of applicant)

Signed in the presence of us as witnesses:

(1) Marshfield, Oregon. (Name) (Address of witness)

(2) (Name) (Address of witness)

Remarks: The purpose of this reservoir is to serve as a settling basin and reserve storage of water for the Sunset Beach Resort water supply, as described in the application to appropriate water.

STATE OF OREGON, }  
County of Marion, } ss.

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for correction or completion as follows:

In order to retain its priority, this application must be returned to the State Engineer, with corrections, on or before \_\_\_\_\_, 19\_\_\_\_\_.

WITNESS my hand this \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_\_.

State Engineer.

STATE OF OREGON, }  
County of Marion, } ss.

This is to certify that I have examined the foregoing application and do hereby grant the same, subject to the following limitations and conditions: The right herein granted is limited to the construction of the Sunset Beach Reservoir for storage of water for domestic purposes, to be appropriated under Application No. 13214, Permit No. 9456.

The right hereunder shall be limited to the storage of 0.07 acre feet.

The priority date of this permit is December 31, 1929

Actual construction work shall begin on or before February 10, 1931

and shall thereafter be prosecuted with reasonable diligence and be completed on or before

October 1, 1932

WITNESS my hand this 10th day of February, 1930.

R H E A L U P E R

State Engineer.

Application No. R-13213

Reservoir Permit No. R-627

**PERMIT**

To construct a reservoir and store for beneficial use the unappropriated waters of the State of Oregon.

District No. ....

This instrument was first received in the office of the State Engineer at Salem, Oregon, on the 31st day of December, 1929, at 8:00 o'clock A. M.

Returned to applicant for correction:

Corrected application received:

Approved:

February 10, 1930

Recorded in Book No. 3 of Reservoirs, on Page 627

R H E A L U P E R

17 p. 397 g.

State Engineer.

\$5.00