

RECEIVED

JUN 2 11 1976

WATER RESOURCES DEPT
SALEM, OREGON

ASSIGNED, See Misc. Res., Vol.

(By Deed)

* Reservoir Permit No. **R 6504**

"CERTIFICATE NO. **56322**

Application for a Permit to Construct a Reservoir and to Store for Beneficial Use the Unappropriated Waters of the State of Oregon

I, Pinnacle Packing Co. Inc. by Merritt Hittle, Treasurer

(Name of Applicant)

of P. O. Box 1068, Medford,

(Mailing address)

(City)

State of Oregon, 97501, do hereby make application for a permit to construct the following described reservoir and to store the unappropriated waters of the State of Oregon, subject to existing rights.

(Zip Code)

If the applicant is a corporation, give date and place of incorporation Medford, Oregon in December, 1928.

1. The name of the proposed reservoir is Pinnacle Packing Reservoir.

2. The name of the stream from which the reservoir is to be filled and the appropriation made is Unnamed Stream, a trib. of S. Fk. Upton Slough, a trib. of Upton Slough, tributary of Rogue River.

3. The amount of water to be stored is 9.2 acre feet.

4. The use to be made of the impounded water is temperature control.

(Irrigation, power, domestic supply, etc.)

5. The location of the proposed reservoir will be in Sec. 9

(Give sections or townships to be submerged)

Tp. 37 S., R. 1 W., W.M., in the county of Jackson.

(a) State whether situated in channel of running stream and give character of material at outlet Dam to be constructed in channel of Unnamed Stream, a trib. of S. Fk. Upton Slough, heavy clay soil at outlet.

(b) If not in channel of running stream, state how it is to be filled. If through a feed canal, give name and dimensions

6. The dam will be located in NW⁴ NW⁴, Sec. 9, Tp. 37 S., R. 1 W., W.M. The maximum height will be 7.0 feet above stream bed or ground surface on center line of dam. The length on top will be 840 feet; length on bottom 225 feet; width on top 10 feet; slope on front or water side 3:1; slope on back 2:1; height of dam above water line when full 2.5 feet.

(Feet horizontal to 1 vertical)

(Feet horizontal to 1 vertical)

* A different form of application should be used for the appropriation of stored water to beneficial use. Such forms can be secured without charge, together with instructions, by addressing the State Engineer, Salem, Oregon 97310.

7. The construction of dam, the material of which it is to be built, and method of protection from waves are as follows: Dam to be constructed of clay material excavated from storage area.

8. The location of wasteway with dimensions are as follows: Around northeast corner of dam; being 10 feet bottom width, 20 feet top width and 2.5 feet in depth.

9. The location of outlet from the proposed reservoir, with character of construction and dimensions, are as follows: will construct a bypass ditch from Unnamed Stream to east side of reservoir to bypass normal flow of stream if necessary. Ditch 2' width top, 1.5' width bottom and 1.0' in depth.

10. The area submerged by the proposed reservoir, when full, will be 1.6 acres, with a maximum depth of water of 10.5 / feet; and approximate mean depth of water 5.75 feet.

11. The estimated cost of the proposed work is \$3,500.00.

12. Construction work will begin on or before one year from date of priority.

13. Construction work will be completed on or before October 1, 1978.

Pinnacle Packing Co, Inc
(Signature of applicant)
by M. L. Lirill, Treasurer

STATE OF OREGON, }
County of Marion, } ss.

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for

In order to retain its priority, this application must be returned to the State Engineer, with corrections on or before, 19

WITNESS my hand this day of, 19

STATE ENGINEER

By ASSISTANT

Remarks: This reservoir capacity to be increased by excavation of approximately 14,000 cubic yards from storage area, to a maximum depth of 5 to 6 feet below natural ground surface. The excavated material is to be used in dam fill and to level the low areas in pear orchard.

STATE OF OREGON, }
County of Marion, } ss.

This is to certify that I have examined the foregoing application and do hereby grant the same, subject to the following limitations and conditions: The right herein granted is limited to the construction of Pinnacle Packing Co. Reservoir and storage of water from an unnamed stream to be appropriated under application No. 54416, permit No. 40781 for temperature control.

The right hereunder shall be limited to the storage of 9.2 acre feet.

The priority date of this permit is June 21, 1976

Actual construction work shall begin on or before November 18, 1977 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1978.

WITNESS my hand this 18th day of November, 1976.


WATER RESOURCES DIRECTOR

Y A

Application No. K-54415

Reservoir Permit No. R 6504

PERMIT

To construct a reservoir and store for beneficial use the unappropriated waters of the State of Oregon.

This instrument was first received in the office of the State Engineer at Salem, Oregon, on the 21 day of June, 1916, at 8:00 o'clock A.M.

Returned to applicant:

Approved:

Recorded in Book No. R 6504 of Reservoirs, on Page

State Engineer

Drainage Basin No. 15 page 78Z17

Fees 36.00

R 6504