

Application for a Permit to Construct a Reservoir and to Store for Beneficial Use the Unappropriated Waters of the State of Oregon

CERTIFICATE NO. 4819

I, Hood River Irrigation District (Name of Applicant) of Hood River (Postoffice), County of Hood River State of Oregon, do hereby make application for a permit to construct the following described reservoir and to store the unappropriated waters of the State of Oregon, subject to existing rights.

If the applicant is a corporation, give date and place of incorporation

1. The name of the proposed reservoir is Green Point Reservoir

2. The name of the stream from which the reservoir is to be filled and the appropriation made is Green Point Creek

tributary of

3. The amount of water to be stored is 1300 acre feet.

4. The use to be made of the impounded water is Irrigation (Irrigation, power, domestic supply, etc.)

5. The location of the proposed reservoir will be in Sec. 22, Township 2 North, Range 9 East, W. M. (Give sections or townships to be submerged)

(a) State whether situated in channel of running stream and give character of material at outlet no

(b) If not in channel of running stream, state how it is to be filled. If through a feed canal, give name and dimensions Thru the old Stanley-Smith ditch from Greenpoint Creek

6. The dam will be located in NW 1/4 and SW 1/4 of NE 1/4, Sec. 22, Tp. 2 N, R. 9 E, W. M. It will be 55 feet in height. (Smallest legal subdivision) (No. N. or S.) (No. E. or W.)

* A different form of application should be used for the appropriation of stored water to beneficial use. Such forms can be secured without charge, together with instructions, by addressing the State Engineer, Salem, Oregon.

having a length on top of 600 feet; length on bottom 200 feet; width on top 15 feet slope of front or water side 3:1 (Feet horizontal to 1 vertical) slope on back 2:1 (Feet horizontal to 1 vertical); height of dam above water line when full 5 feet.

7. The construction of dam, the material of which it is to be built, and method of protection from waves are as follows: Earth fill - 108,000 cu. yds.

8. The location of wasteway with dimensions are as follows: Around west end of dam - (State whether over or around the dam) timber lined

9. The location of outlet from the proposed reservoir, with character of construction and dimensions, are as follows: Under dam - 16" I.D. concrete - 4 concrete cutoff collars (State whether through or around the proposed dam)

10. The area submerged by the proposed reservoir, when full, will be 60 acres, with a maximum depth of water of 50 feet; and approximate mean depth of water 20 feet.

11. The estimated cost of the proposed work is \$ 78,000.00

12. Construction work will begin on or before as soon as funds available

13. Construction work will be completed on or before 18 months

Duplicate maps of the proposed reservoir and storage works, prepared in accordance with the rules of the State Water Board, accompany this application.

Hood River Irrigation District (Name of applicant)

By: F. Fenwick, Secty.

Signed in the presence of us as witnesses:

(1) S. L. Banks (Name), Route 3, Hood River, Ore. (Address of witness)

(2) G. A. McCurdy (Name), " " (Address of witness)

Remarks: Application has been made to the Administrator of Public Works for funds to construct this Dam so that no definite time can be set, either for commencement or completion of the project it depending altogether on the action of the Public Works Administration.

STATE OF OREGON, }
County of Marion, } ss.

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for correction or completion as follows:

In order to retain its priority, this application must be returned to the State Engineer, with corrections, on or before _____, 19_____.

WITNESS my hand this _____ day of _____, 19_____.

State Engineer.

STATE OF OREGON, }
County of Marion, } ss.

This is to certify that I have examined the foregoing application and do hereby grant the same, subject to the following limitations and conditions: The right herein granted is limited to the construction of a reservoir for the storage of water from Green Point Creek, to be appropriated under Application No. 15199, Permit No. 12362.

The right hereunder shall be limited to the storage of 1300 acre feet.

The priority date of this permit is November 22, 1935

Actual construction work shall begin on or before January 8, 1938

and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1938

WITNESS my hand this 8th day of January, 1937.

CHAS. E. STRICKLIN

State Engineer.

Application No. 15198

Reservoir Permit No. R-698

PERMIT

To construct a reservoir and store for beneficial use the unappropriated waters of the State of Oregon.

District No.

This instrument was first received in the office of the State Engineer at Salem, Oregon, on the 22nd day of November, 1933 at 8:00 o'clock A. M.

Returned to applicant for correction:

Corrected application received:

Approved:

January 8, 1937

Recorded in Book No. 3 of Reservoirs, on Page 698

CHAS. E. STRICKLIN

State Engineer.

4 - 86

\$10.75