

RECEIVED  
APR 19 1968  
STATE ENGINEER  
SALEM, OREGON

\* Reservoir Permit No. R 7283

**Application for a Permit to Construct a Reservoir and to Store for Beneficial Use the Unappropriated Waters of the State of Oregon**

I, The Bureau of Land Management  
(Name of Applicant)

of P.O. Box 220 Vale  
(Mailing Address)

State of Oregon do hereby make application for a permit to construct the following described reservoir and to store the unappropriated waters of the State of Oregon, subject to existing rights.

If the applicant is a corporation, give date and place of incorporation

1. The name of the proposed reservoir is Shumway

2. The name of the stream from which the reservoir is to be filled and the appropriation made is Not Named

tributary of Granite Creek

3. The amount of water to be stored is 3.6 acre feet.

4. The use to be made of the impounded water is Stock and wild life  
(Irrigation, power, domestic supply, etc.)

5. The location of the proposed reservoir will be in Sec. 22  
(Give sections or townships to be submerged)

Tp. 23S7, R. 39E, W.M., in the county of Malheur

(a) State whether situated in channel of running stream and give character of material at outlet  
Not a running stream

(b) If not in channel of running stream, state how it is to be filled. If through a feed canal, give name and dimensions  
From spring runoff

6. The dam will be located in SW 1/4 Sec 22  
(Smallest legal subdivision), Sec. 22

Tp. 23S, R. 39E, W.M. The maximum height will be 10.7 feet above stream bed or ground surface on center line of dam. The length on top will be 386.3 feet; length on bottom Triangular feet; width on top 12.0 feet; slope on front or water side 3:1; slope on back 2:1; height of dam above water line when full 4.0 feet.

\* A different form of application should be used for the appropriation of stored water to beneficial use. Such forms can be secured without charge, together with instructions, by addressing the State Engineer, Salem, Oregon.

R 7283

7. The construction of dam, the material of which it is to be built, and method of protection from waves are as follows: A keyway excavated and filled with the best impervious material taken from a borrow area. The dam built in layers not to exceed 6 inches and compacted with a cat and carryall.

8. The location of wasteway with dimensions are as follows: Spillway around the west end of the dam. (State whether over or around the dam)

9. The location of outlet from the proposed reservoir, with character of construction and dimensions, are as follows: None (All dams across natural stream channels must be provided with an outlet conduit, of such capacity and location to pass the normal flow of the stream at any time)

10. The area submerged by the proposed reservoir, when full, will be 2.4 acres, with a maximum depth of water of 6.7 feet; and approximate mean depth of water 1.5 feet.

11. The estimated cost of the proposed work is \$

12. Construction work will begin on or before This is an existing reservoir.

13. Construction work will be completed on or before

BLM - Frank C. Skille (Signature of applicant)

STATE OF OREGON, } ss. County of Marion,

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for CORRECTION

In order to retain its priority, this application must be returned to the State Engineer, with corrections on or before July 17, 1968.

WITNESS my hand this 17th day of May, 1968.

RECEIVED JUL 1 1968 STATE ENGINEER SALEM OREGON

CHRIS L. WHEELER

STATE ENGINEER ASSISTANT (Signature)

Remarks: .....

STATE OF OREGON, }  
County of Marion, } ss.

This is to certify that I have examined the foregoing application and do hereby grant the same, subject to the following limitations and conditions: The right herein granted is limited to the construction of Shumway Reservoir and storage of water from an unnamed stream for livestock, and is subject to the installation and maintenance of an outlet pipe, or to provide other means to evacuate the stored water when determined by the Water Resources Director to be necessary to satisfy prior downstream rights.

The right hereunder shall be limited to the storage of 3.6 acre feet.

The priority date of this permit is April 19, 1968

Actual construction work shall begin on or before June 8, 1979 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1980

WITNESS my hand this 8th day of June, 19 78

*James E. Dixon*

XXXXXXXXXXXXXX  
Water Resources Director

Application No. P-44746

Reservoir Permit No. R 7283

**PERMIT**

To construct a reservoir and store for beneficial use the unappropriated waters of the State of Oregon.

This instrument was first received in the

office of the State Engineer at Salem, Oregon,

on the 19<sup>th</sup> day of April,

1941, at 9:00 o'clock A. M.

Returned to applicant:

Approved:

Recorded in Book No. \_\_\_\_\_ of \_\_\_\_\_

Reservoirs, on Page \_\_\_\_\_

State Engineer

Drainage Basin No. 10 page 12 E

Fees \$20.00