

RECEIVED
NOV 22 1968
STATE ENGINEER
SALEM, OREGON

* Reservoir Permit No. RESR 17479

Application for a Permit to Construct a Reservoir and to Store for Beneficial Use the Unappropriated Waters of the State of Oregon

I, BUREAU OF LAND MANAGEMENT
(Name of Applicant)

of P. O. Box 220 Vale
(Mailing Address)

State of Oregon, do hereby make application for a permit to construct the following described reservoir and to store the unappropriated waters of the State of Oregon, subject to existing rights.

If the applicant is a corporation, give date and place of incorporation

1. The name of the proposed reservoir is Lillie

2. The name of the stream from which the reservoir is to be filled and the appropriation made is Unnamed

tributary of Succor Creek

3. The amount of water to be stored is 4.20 acre feet.

4. The use to be made of the impounded water is Livestock & Wildlife water
(Irrigation, power, domestic supply, etc.)

5. The location of the proposed reservoir will be in Sec. 13
(Give sections or townships to be submerged)

Tp. 25 S., R. 46 E., W.M., in the county of Malheur

(a) State whether situated in channel of running stream and give character of material at outlet

No running stream

(b) If not in channel of running stream, state how it is to be filled. If through a feed canal, give name and dimensions From spring run-off

6. The dam will be located in SE 1/4, Sec. 13
(Smallest legal subdivision)

Tp. 25 S., R. 46 E., W.M. The maximum height will be 13.1 feet above stream bed or ground

surface on center line of dam. The length on top will be 269.2 feet; length on

bottom Triangular feet; width on top 12 feet; slope on front

or water side 3:1; slope on back 2:1; height of dam above water line
(Feet horizontal to 1 vertical)

when full 4 feet.

* A different form of application should be used for the appropriation of stored water to beneficial use. Such forms can be secured without charge, together with instructions, by addressing the State Engineer, Salem, Oregon.

7. The construction of dam, the material of which it is to be built, and method of protection from waves are as follows: A keyway will be excavated and filled with the best impervious material taken from a borrow area. The dam will be built in layers not to exceed six inches and compacted with a cat and carryall.

8. The location of wasteway with dimensions are as follows: Around north end of Dam (State whether over or around the dam)

9. The location of outlet from the proposed reservoir, with character of construction and dimensions, are as follows: None (All dams across natural stream channels must be provided with an outlet conduit, of such capacity and location to pass the normal flow of the stream at any time)

10. The area submerged by the proposed reservoir, when full, will be 0.93 acres, with a maximum depth of water of 9.1 feet; and approximate mean depth of water 4.52 feet.

11. The estimated cost of the proposed work is \$

12. Construction work will begin on or before One year from date of permit

13. Construction work will be completed on or before Two years from date of permit

Signature of applicant: Anthony J. Wieland

STATE OF OREGON, }
County of Marion, } ss.

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for Corrections

In order to retain its priority, this application must be returned to the State Engineer, with corrections on or before March 28th, 1969.

WITNESS my hand this 28th day of January, 1969.

RECEIVED FEB 10 1969 STATE ENGINEER SALEM, OREGON

CHRIS L. WHEELER STATE ENGINEER
By Larry W. Jebousek ASSISTANT

R 7479

Remarks:

STATE OF OREGON, }
County of Marion, } ss.

This is to certify that I have examined the foregoing application and do hereby grant the same, subject to the following limitations and conditions: The right herein granted is limited to the construction of Little Reservoir and storage of water for livestock and wildlife, and is subject to the installation and maintenance of an outlet pipe, or to provide other means to evacuate the stored water when determined by the Water Resources Director to be necessary to satisfy prior downstream rights.

The right hereunder shall be limited to the storage of 4.2 acre feet.

The priority date of this permit is November 22, 1968

Actual construction work shall begin on or before July 11, 1979 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1980.

WITNESS my hand this 11th day of July, 1978.

James E. Seaman
Water Resources Director 216

Application No. R-45602
Reservoir Permit No. R 7179

PERMIT

To construct a reservoir and store for beneficial use the unappropriated waters of the State of Oregon.

This instrument was first received in the office of the State Engineer at Salem, Oregon, on the 22nd day of November, 1928, at 1:00 o'clock P. M.

Returned to applicant:

Approved:

Recorded in Book No. _____ of
Reservoirs, on Page _____

State Engineer

Drainage Basin No. 1 page 234
Fees \$ 20.00