



STATE OF OREGON

DESCHUTES COUNTY

"CERTIFICATE NO. 59048"

PERMIT TO APPROPRIATE THE PUBLIC WATERS

This is to certify that I have examined APPLICATION R-60935 and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to City of Redmond, of 455 South 7th Street, Redmond, Oregon 97756, phone 548-2148, for the construction of the Sewage Effluent Storage Reservoir and storage of effluent from the City of Redmond Wastewater Treatment Plant to be appropriated under Application 61422, Permit 46323, for supplemental irrigation.

The dam will be LOCATED in the: SW 1/4 of Section 19, Township 14 South, Range 13 East, WM, in the County of Deschutes.

The maximum height will be 18.8 feet above the stream bed or ground surface at the centerline. The top width will be 8.0 feet, slope of upstream face 2:1, slope of downstream face 2:1, and height of dam above water line when full 1.3 feet.

The area submerged by the reservoir, when full, will be 34.0 acres, and the maximum depth of water will be 17.5 feet.

The location and dimensions of the spillway are: none.

The location and dimension of the outlet or bypass, and control works are: none. Water removed by pumping.

The structure is out of the channel.

The dam will be earthfill construction with soil cement liner over compacted hard pan or bedrock.

The right hereunder shall be limited to the storage of 286.0 acre-feet.

The PRIORITY DATE of this permit is October 23, 1980.

Actual construction work shall begin on or before March 30, 1983 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1983.

WITNESS my hand this 30th day of March, 1982.

/s/ JAMES E. SEXSON

WATER RESOURCES DIRECTOR