



STATE OF OREGON

YAMHILL COUNTY

PERMIT TO APPROPRIATE THE PUBLIC WATERS

This is to certify that I have examined APPLICATION R-63048 and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to Mitchell and Nelson Associates, Inc., agent for Michelbook Estates, Inc. of 1420 SW Broadway, Portland, Oregon 97201, phone 225-0822, for the construction of North and South Reservoirs and storage of water to be appropriated under Application 63049, Permit 46419, for irrigation and the dams shall be constructed under the supervision of a registered professional engineer.

The dams will be LOCATED in the: SW 1/4 SW 1/4 of Section 17, Township 4 South, Range 4 West, WM, in the County of Yamhill.

The maximum height for the North Dam will be 12.7 feet above the stream bed or ground surface at the centerline and for the South Dam maximum height will be 10.7 feet. The top width for the North Dam will be 40.0 feet, slope of upstream face 3:1, slope of downstream face 3:1, and height of dam above water line when full 2.7 feet. The top width for the South Dam will be 250.0 feet, slope of the upstream face 3:1, slope of downstream face 2%, and height of dam above water line when full 3.2 feet.

The area submerged by the reservoirs, when full, will be 4.5 acres and 0.9 acre, and the maximum depths of water will be 10.0 feet.

The location and dimensions of the spillways are: Over the dams.

The location and dimension of the outlet or bypass, and control works are: South Lake: 280 L.F. - 60-inch corrugated metal pipe (with standpipe at Elevation 139.5), sized to accommodate 50-year storm under existing conditions (rural) or 25-year storm under urbanized (future) conditions. North Lake: 85-foot - 18-inch corrugated metal pipe (with weir/spillway at Elevation 140.0).

The structures are in the channel.

The dams will be earthfill construction.

The right hereunder shall be limited to the storage of 33.25 acre-feet, being 29.75 acre-feet in North Reservoir and 3.5 acre-feet in South Reservoir.

The North Dam shall be constructed under the supervision of a registered professional engineer.

The PRIORITY DATE of this permit is November 17, 1981 for 30.0 acre-feet and March 12, 1982 for 3.25 acre-feet.

Actual construction work shall begin on or before April 12, 1983 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1984.

WITNESS my hand this 12th day of April, 1982.

/s/ JAMES E. SEXSON

WATER RESOURCES DIRECTOR

APPLICATION R-63048

"CERTIFICATE NO. 66134"

PERMIT R 8344