



STATE OF OREGON

DOUGLAS COUNTY

PERMIT TO APPROPRIATE THE PUBLIC WATERS

This is to certify that I have examined APPLICATION R-62121 and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to Darrell Henry Green of Box 30, Weaver Road, Myrtle Creek, Oregon 97457, phone 863-5013, for the construction of two reservoirs and storage of water from two unnamed streams with any deficiency in the available supply from the two unnamed streams to be made up by diversion from South Umpqua River to be appropriated under Application 62122, Permit 46680, for irrigation and stock water.

The dams will be LOCATED in the: NE 1/4 NE 1/4 of Section 6, Township 30 South, Range 5 West, WM, in the County of Douglas.

The maximum height for Reservoir 1 will be 8.0 feet above the stream bed or ground surface at the centerline. The top width will be 18.0 feet, slope of upstream face 3:1, slope of downstream face 2:1, and height of dam above water line when full 2.5 feet. The maximum height for Reservoir 2 will be 9.8 feet above the stream bed or ground surface at the centerline. The top width will be 10.0 feet, slope of upstream face 3:1, slope of downstream face 2:1, and height of dam above water line when full 2.5 feet.

The area submerged by Reservoir 1, when full, will be 0.4 acre, and the maximum depth of water will be 8.0 feet. The area submerged by Reservoir 2, when full, will be 0.2 acre, and the maximum depth of water will be 10.0 feet.

The location and dimensions of the spillways are: None.

The location and dimension of the outlet or bypass, and control works are: 18-inch outlet conduit on north side of dams.

Reservoir 1 is out of the channel, Reservoir 2 is in the channel.

The dams will be earthfill construction.

The right hereunder shall be limited to the storage of 1.3 acre-feet in Reservoir 1 and 1.2 acre-feet in Reservoir 2, being 1.3 acre-feet in Reservoir 1 for irrigation and 1.0 acre-foot in Reservoir 2 for irrigation and 0.2 acre-foot in Reservoir 2 for stock water.

The PRIORITY DATE of this permit is August 5, 1981.

Actual construction work shall begin on or before June 28, 1983 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1984.

WITNESS my hand this 28th day of June, 1982.

/s/ JAMES E. SEXSON

WATER RESOURCES DIRECTOR

APPLICATION R-62121

PERMIT R 8401

ASSIGNED. See Misc. Rec., Vol. By Deed Page

ASSIGNED. See Misc. Rec., Vol. 8 437