



STATE OF OREGON

CLACKAMAS COUNTY

PERMIT TO APPROPRIATE THE PUBLIC WATERS

This is to certify that I have examined APPLICATION R-60177 and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to Jonathan Price Cox of 3990 Sussex Street, West Linn, Oregon 97068, phone 656-9312, for the construction of Misty Meadow Reservoirs 1 and 2 Reservoir and storage of water from Tanner Creek to be appropriated under Application 60178, Permit 46699, for stock water.

The dams will be LOCATED in the: SE 1/4 NW 1/4 of Section 36, Township 2 South, Range 1 East, WM, in the County of Clackamas.

The maximum height for each will be 4.0 feet above the stream bed or ground surface at the centerline. The top width will be 12.0 feet, slope of upstream face 3:1, slope of downstream face 2:1, and height of dam above water line when full 2.0 feet.

The area submerged by each reservoir, when full, will be 0.115 acre, and the maximum depth of water will be 6.0 feet.

The location and dimensions of the spillway are: Around each dam and protected with concrete apron and rip rap. Bottom width of each 10.0 feet; top width of each 15.0 feet, depth of each 2.5 feet.

The location and dimension of the outlet or bypass, and control works are: Conduits will be located in left abutment with a 24-inch diameter by 5-foot long C.M. pipe.

The structures are in the channel.

The dams will be concrete construction.

The right hereunder shall be limited to the storage of 0.09 acre-foot, being 0.045 acre-foot in each reservoir.

The PRIORITY DATE of this permit is June 7, 1982.

Actual construction work shall begin on or before June 30, 1983 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1984.

WITNESS my hand this 30th day of June, 1982.

/s/ JAMES E. SEXSON

WATER RESOURCES DIRECTOR