



## STATE OF OREGON

LINCOLN COUNTY

"CERTIFICATE NO. 56433"

### PERMIT TO APPROPRIATE THE PUBLIC WATERS

This is to certify that I have examined APPLICATION R-63462 and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to John E. Campbell of Route 1, Box 146, Otis, Oregon 97368, phone 994-9365, for the construction of a reservoir and storage of water from an unnamed stream to be appropriated under Application 63463, Permit 46756 for recreation.

The dam will be LOCATED in the: SW 1/4 NW 1/4 of Section 29, Township 6 South, Range 9 West, WM, in the County of Lincoln.

The maximum height will be 5.0 feet above the stream bed or ground surface at the centerline. The top width will be 8.0 feet, slope of upstream face 2:1, slope of downstream face 3:1, and height of dam above water line when full 1.0 foot.

The area submerged by the reservoir, when full, will be 0.03 acre, and the maximum depth of water will be 6.0 feet.

The location and dimensions of the spillway are: Over dam. The bottom width will be 4.0 feet. The top width will be 4.0 feet. The distance between the crest of the dam and the crest of the spillway will be 2.5 feet.

The location and dimension of the outlet or bypass, and control works are: 15-inch culvert within confines of dam at streambed, with lift-gate.

The structure is in the channel.

The dam will be earthfill and concrete construction.

The right hereunder shall be limited to the storage of 0.12 acre-foot.

The PRIORITY DATE of this permit is April 12, 1982.

Actual construction work shall begin on or before July 13, 1983 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1984.

WITNESS my hand this 13th day of July, 1982.

/s/ JAMES E. SEXSON

WATER RESOURCES DIRECTOR