



STATE OF OREGON

WASCO COUNTY

PERMIT TO APPROPRIATE THE PUBLIC WATERS

This is to certify that I have examined APPLICATION R-63102 and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to Rajneesh Neo-Sannyas International Commune of PO Box 12A, Antelope, Oregon 97001, phone 489-3333, for the construction of the Currant Creek Reservoir and storage of water from Currant Creek to be appropriated under Application 63103, Permit 46810, for irrigation and supplemental irrigation. The dam shall be constructed according to the approved plans and specifications under the supervision of a Registered Professional Engineer.

The dam will be LOCATED in the: SE 1/4 SE 1/4 of Section 35, Township 8 South, Range 18 East, WM, in the County of Wasco.

The maximum height will be 82.5 feet above the stream bed or ground surface at the centerline. The top width will be 20.0 feet, slope of upstream face 3:1, slope of downstream face 2:1, and height of dam above water line when full 14.0 feet.

The area submerged by the reservoir, when full, will be 44.0 acres, and the maximum depth of water will be 56.0 feet.

The location and dimensions of the spillway are: Around dam. The bottom width will be 200.0 feet. The top width will be 228.0 feet. The distance between the crest of the dam and the crest of the spillway will be 14.0 feet.

The location and dimension of the outlet or bypass, and control works are: The outlet will welded steel pipe encased in concrete.

The structure is in the channel.

The dam will be earthfill construction.

The right hereunder shall be limited to the storage of 1,020.0 acre-feet.

The PRIORITY DATE of this permit is December 7, 1981.

Actual construction work shall begin on or before July 30, 1983 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1984.

WITNESS my hand this 30th day of July, 1982.

AMENDED by special order

v. 52 pg. 948

WATER RESOURCES DIRECTOR

ASSIGNED. See Misc. Rec., Vol. 8 Page 111

ASSIGNED. See Misc. Rec., Vol.            Page           

APPLICATION R-63102

PERMIT R 8452

ASSIGNED. See Misc. Rec., Vol. By deed Page           

T7886

Permit Modified V52 A103