



STATE OF OREGON

COOS COUNTY

PERMIT TO APPROPRIATE THE PUBLIC WATERS

This is to certify that I have examined APPLICATION R-61527 and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to Coos Bay-North Bend Water Board of PO Box 539, Coos Bay, Oregon 97420, phone 267-3128, for the enlargement of the Upper Pony Creek Reservoir and storage of water from Pony Creek to be appropriated under Application 63237, Permit 47095, for municipal water supply.

The dam shall be constructed under the supervision of a registered professional engineer.

The dam will be LOCATED in the: SW 1/4 SW 1/4 of Section 28, Township 25 South, Range 13 West, WM, in the County of Coos.

The maximum height will be 45.0 feet above the streambed or ground surface at the centerline. The top width will be 15.0 feet, slope of upstream face 3:1, slope of downstream face 2:1, and height of dam above water line when full 6.0 feet.

The area submerged by the reservoir, when full, will be 131.0 acres, and the maximum depth of water will be 39.0 feet.

The location and dimensions of the spillway are: Over flashboards. The bottom width will be 30.0 feet. The top width will be 30.0 feet. The distance between the crest of the dam and the crest of the spillway will be 6.0 feet.

The location and dimension of the outlet or bypass, and control works are: 36-inch extra strength culvert pipe at base of dam.

The structure is in the channel.

The dam will be earthfill and flashboard construction.

During the winter storm season the flashboards shall not be higher than elevation 79.1 feet MSL to allow for adequate spillway capacity to carry storms through the dam. The winter storm season for this purpose shall begin October 1 and end on March 1.

During that portion of the year other than the winter storm season, the flashboards shall not be higher than elevation 82.1 MSL.

The right hereunder shall be limited to the storage of 465.0 acre-feet.

The PRIORITY DATE of this permit is April 13, 1981.

Actual construction work shall begin on or before November 23, 1983 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1984.

WITNESS my hand this 23rd day of November, 1982.

This permit, when issued, is for the beneficial use of water. By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan. It is possible that the land use you propose may not be allowed if it is not in keeping with the goals and the acknowledged plan. Your city or county planning agency can advise you about the land-use plan in your area.

/s/ JAMES E. SEXSON

WATER RESOURCES DIRECTOR

APPLICATION R-61527

PERMIT **R 8518**