



STATE OF OREGON

GRANT COUNTY

PERMIT TO APPROPRIATE THE PUBLIC WATERS

This is to certify that I have examined APPLICATION R-59568 and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to Bureau of Land Management of 74 South Alvord, Burns, Oregon 97720, for the construction of Fawn Creek #1 (15-4983) Reservoir and storage of water from an unnamed stream for livestock, and is subject to the installation and maintenance of an outlet pipe, or to provide other means to evacuate the stored water when determined by the Water Resources Director to be necessary to satisfy prior downstream rights.

The dam will be LOCATED in the: SE 1/4 SE 1/4 of Section 34, Township 10 South, Range 26 East, WM, in the County of Grant.

The maximum height will be 10.0 feet above the streambed or ground surface at the centerline. The top width will be 10.0 feet, slope of upstream face 3:1, slope of downstream face 2:1, and height of dam above water line when full 4.0 feet.

The area submerged by the reservoir, when full, will be 0.25 acre, and the maximum depth of water will be 10.0 feet.

The location and dimensions of the spillway are: Around the dam. The bottom width will be 14.0 feet. The top width will be 18.0 feet. The distance between the crest of the dam and the crest of the spillway will be 4.0 feet.

The location and dimension of the outlet or bypass, and control works are: None.

The structure is out of the channel.

The dam will be earthfill construction.

The right hereunder shall be limited to the storage of 1.0 acre-foot.

The PRIORITY DATE of this permit is October 21, 1982.

Actual construction work shall begin on or before November 30, 1983 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1984.

WITNESS my hand this 30th day of November 1982.

/s/ JAMES E. SEXSON
WATER RESOURCES DIRECTOR