



STATE OF OREGON

County of JACKSON

PERMIT TO APPROPRIATE THE PUBLIC WATERS

This is to certify that I have examined APPLICATION **R-64604** and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to **Jerry and/or Shirley M. Stone** of 5500 Lost Creek Road, Eagle Point, Oregon 97524, phone 826-7213, for the construction of 4 reservoirs and storage of water from Frog Creek, and an unnamed stream, tributaries of South Fork Little Butte Creek, to be appropriated under Application 64605, Permit 47440 for supplemental irrigation.

The dam will be LOCATED in the: **Reservoir 1 - SW 1/4 SW 1/4 of Section 3; Reservoir 2 - NW 1/4 NW 1/4 of Section 10; Reservoir 3 - N 1/2 of NW 1/4 of Section 10; Reservoir 4 - NW 1/4 NW 1/4 of Section 10; all of Township 37 South, Range 2 East, WM, in the County of Jackson.**

The maximum height will be **9.9** feet above the stream bed or ground surface at the centerline. The top width will be **12 feet**, slope of upstream face **3:1**, slope of downstream face **1.5:1**, and height of dam above water line when full **2.5 feet**.

The area submerged by the reservoir, when full, will be * , and the maximum depth of water will be **

* **Reservoir 1 - 1.5 acres; Reservoir 2 - 0.8 acre; Reservoir 3 - 1.3 acres; Reservoir 4 - 0.15 acre**

** **Reservoir 1 - 10 feet; Reservoir 2 - 9 feet; Reservoir 3 - 10 feet; Reservoir 4 - 10 feet.**

*** **in Reservoir 3 from the unnamed stream and 1.4 af stored in Reservoir 4 from the unnamed stream.**

The locations and dimensions of the spillway are: **Reservoir 1 - bottom width 4 feet, top width 9 feet; Reservoir 2 - bottom width 3 feet, top width 6 feet; Reservoir 3 - bottom width 4 feet, top width 12 feet; Reservoir 4 - bottom width 6 feet, top width 12 feet; the distance between the crest of the dam and the crest of the spillway for all reservoirs will be 2.5 feet.**

The location and dimensions of the outlet conduits will be: **Reservoir 1 - 8-inch concrete pipe with cement cutoff collars, 8-inch gate valve on water side; Reservoirs 2 and 3 - 8-inch concrete pipe with valve on water side; Reservoir 4 - no outlet pipe.**

The structures are out of the channel.

The reservoirs will be earthfill construction.

The right hereunder shall be limited to the storage of **25.4 acre-feet**, being **9.0 af** stored in Reservoir 1 from Frog Creek, **6.0 af** stored in Reservoir 2 from the unnamed stream, **9.0 af** stored ***

The PRIORITY DATE of this permit is **December 29, 1982**.

Actual construction work shall begin on or before **May 11, 1984** , and shall thereafter be prosecuted with reasonable diligence and be completed on or before **October 1, 1985** .

Complete application of the water to the proposed use shall be made on or before **October 1, 19 n/a** .

Witness my hand this **11th** day of **May** , 19 **83** .

/s/ **JAMES E. SEXSON**

WATER RESOURCES DIRECTOR

This permit, when issued, is for the beneficial use of water. By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan. It is possible that the land use you propose may not be allowed if it is not in keeping with the goals and the acknowledged plan. Your city or county planning agency can advise you about the land-use plan in your area.

APPLICATION **R-64604**

CERTIFICATE NO. **75239**

PERMIT

R 8610