



STATE OF OREGON

County of DOUGLAS

PERMIT TO APPROPRIATE THE PUBLIC WATERS

This is to certify that I have examined APPLICATION R-59217 and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to Peter B. Serafin of PO Box 2250, Roseburg, Oregon 97470, phone 672-5549, for the construction of a reservoir and storage of water from an unnamed stream, tributary of North Umpqua River to be appropriated under Application 64543, Permit 47456 for recreation and irrigation, and the dam shall be constructed under the supervision of a registered professional engineer

The dam will be LOCATED in the: SW 1/4 SW 1/4 of Section 32, Township 26 South, Range 4 West, WM, in the County of Douglas.

The maximum height will be 16 feet above the stream bed or ground surface at the centerline. The top width will be 12 feet, slope of upstream face 3:1, slope of downstream face 2:1, and height of dam above water line when full 4 feet.

The area submerged by the reservoir, when full, will be 1.9 acres, and the maximum depth of water will be 16 feet.

The locations and dimensions of the spillway are: Bottom width 20 feet, top width 20 feet, the distance between the crest of the dam and the crest of the spillway 4 feet.

The location and dimensions of the outlet conduit will be: 18-inch corrugated metal pipe, Morning Glory discharge at the centerline of the existing channel.

The structure is in the channel.

The dam will be earthfill construction.

The right hereunder shall be limited to the storage of 18.0 acre-feet, being 8.0 af for irrigation and 10.0 af for recreation.

The PRIORITY DATE of this permit is November 19, 1982 for 11.1 af, December 13, 1982 for 6.9 af.

Actual construction work shall begin on or before May 31, 1984, and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1985.

Complete application of the water to the proposed use shall be made on or before October 1, 19 n/a.

Witness my hand this 31st day of May, 1983.

/s/ JAMES E. SEXSON

WATER RESOURCES DIRECTOR

This permit, when issued, is for the beneficial use of water. By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan. It is possible that the land use you propose may not be allowed if it is not in keeping with the goals and the acknowledged plan. Your city or county planning agency can advise you about the land-use plan in your area.