



# STATE OF OREGON

County of MALHEUR

## PERMIT TO APPROPRIATE THE PUBLIC WATERS

This is to certify that I have examined APPLICATION **R-59166** and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to Bureau of Land Management of Box 700, Vale, Oregon 97918, phone (503)-473-3144, for the construction of Duck Butte (0187) Reservoir and storage of water from an unnamed stream, tributary of Dead Man Creek for wildlife and livestock and is subject to the installation and maintenance of an outlet pipe, or to provide other means to evacuate the stored water when determined by the Water Resources Director to be necessary to satisfy prior \*

The dam will be LOCATED in the: SE 1/4 NE 1/4 of Section 4, Township 27 South, Range 37 East, WM, in the County of Malheur.

The maximum height will be **13.9** feet above the stream bed or ground surface at the centerline. The top width will be **12 feet**, slope of upstream face **3:1**, slope of downstream face **2:1**, and height of dam above water line when full **4 feet**.

The area submerged by the reservoir, when full, will be **.42 acres**, and the maximum depth of water will be **9.9 feet**.

\* downstream rights.

The locations and dimensions of the spillway are: Bottom width 24 feet, top width 39.6 feet, the distance between the crest of the dam and the crest of the spillway 4 feet.

The location and dimensions of the outlet conduit will be: none.

The structure is out of the channel.

The dam will be earthfill construction.

The right hereunder shall be limited to the storage of **2.7 acre-feet**.

The PRIORITY DATE of this permit is **August 6, 1979**.

Actual construction work shall begin on or before **June 29, 1984**, and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 19 **85**.

Complete application of the water to the proposed use shall be made on or before October 1, 19 **n/a**.

Witness my hand this **29th** day of **June**, 19 **83**.

/s/ **JAMES E. SEXSON**

WATER RESOURCES DIRECTOR

This permit, when issued, is for the beneficial use of water. By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan. It is possible that the land use you propose may not be allowed if it is not in keeping with the goals and the acknowledged plan. Your city or county planning agency can advise you about the land-use plan in your area.

APPLICATION **R-59166**

ASSIGNED. See Misc. Rec., Vol. **7** Page **2243**

PERMIT

**R 8796**

**44**  
**45**  
**46**