



STATE OF OREGON

County of GRANT

PERMIT to CONSTRUCT a RESERVOIR and to STORE for BENEFICIAL USE the PUBLIC WATERS

This is to certify that I have examined APPLICATION R-64362 and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to United States Malheur National Forest, 139 Northeast Dayton Street, John Day, Oregon 97845, phone 575-1731, for the construction of two reservoirs (Ridge Road Pond and Willow Pond Reservoirs) and storage of water from two unnamed intermittent tributaries of Scotty Creek-Silvies River for livestock, and is subject to the installation and maintenance of outlet pipes, or to provide other means to evacuate the stored water when determined by the*
The dam will be LOCATED in the: Ridge Pond - SW 1/4 NW 1/4, Section 2; Willow Pond - SE 1/4 NE 1/4, Section 3 within Township 17 South, Range 30 East, WM, in the County of Grant.

The maximum height will be each 7.5 feet above the stream bed or ground surface at the centerline. The top width will be 10.0 feet each, slope of upstream face each 3:1, slope of downstream face each 4:1, and height of dam above water line when full each 3.0 feet

The area submerged by the reservoir, when full, will be 0.05 acre each, and the maximum depth of water will be 5.0 feet each

* Water Resources Director to be necessary to satisfy prior downstream rights.

The locations and dimensions of the spillway are: Over the dam, bottom width 6.0 feet, top width 15.0 feet, the distance between the crest of the dams and the crest of the spillways will be 3.0 feet.

The location and dimension of the outlet conduit will be: None.

The structures will be in the channel.

The dams will be earthfill construction.

The right hereunder shall be limited to the storage of 0.4 acre-foot, being 0.20 af stored in each reservoir.

The PRIORITY DATE of this permit is October 4, 1982.

Actual construction work shall begin on or before November 4, 1984, and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1985.

Witness my hand this 4th day of November, 1983.

/s/ WILLIAM H. YOUNG
WATER RESOURCES DIRECTOR

This permit, when issued, is for the beneficial use of water. By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan. It is possible that the land use you propose may not be allowed if it is not in keeping with the goals and the acknowledged plan. Your city or county planning agency can advise you about the land-use plan in your area.