

* Reservoir Permit No. 904

Application for a Permit to Construct a Reservoir and to Store for Beneficial Use the Unappropriated Waters of the State of Oregon

I, GEORGE YOKOM (Name of applicant)

of Mt. Vernon, County of Grant (Post office)

State of Oregon, do hereby make application for a permit to construct the following described reservoir and to store the unappropriated waters of the State of Oregon, subject to existing rights.

If the applicant is a corporation, give date and place of incorporation

1. The name of the proposed reservoir is Yokom Reservoir

2. The name of the stream from which the reservoir is to be filled and the appropriation made is Birch Creek tributary of John Day River

3. The amount of water to be stored is 45 acre feet.

4. The use to be made of the impounded water is irrigation (Irrigation, power, domestic supply, etc.)

5. The location of the proposed reservoir will be in Sec. 15 and 22 (Give sections or townships to be submerged)

(a) State whether situated in channel of running stream and give character of material at outlet
In channel of Birch Creek - concrete spillway, iron pipe outlet into irrigation ditch

(b) If not in channel of running stream, state how it is to be filled. If through a feed canal, give name and dimensions

6. The dam will be located in NW¹/₄NE¹/₄ and NE¹/₄NW¹/₄, Sec. 22, Tp. 13 S., R. 29 E., W. M. It will be 25 feet in height, (No. N. or S.) (No. E. or W.) (Smallest legal subdivision)

* A different form of application should be used for the appropriation of stored water to beneficial use. Such forms can be secured without charge, together with instructions, by addressing the State Engineer, Salem, Oregon.

having a length on top of 600 feet; length on bottom 25 feet; width on top 10 feet slope of front or water side 3 to 1 (Feet horizontal to 1 vertical) slope on back 2 to 1 (Feet horizontal to 1 vertical); height of dam above water line when full 5 feet.

7. The construction of dam, the material of which it is to be built, and method of protection from waves are as follows: Will be constructed by use of catapillar and teams of adjacent earth which is a doby loam with small amount of gravel. The height and slope will furnish ample protection from waves.

8. The location of wasteway with dimensions are as follows: At East end of dam, 40 feet (State whether over or around the dam) wide of concrete with rock apron, allowing waste to run off down natural water way.

9. The location of outlet from the proposed reservoir, with character of construction and dimensions, are as follows: through 12 inch iron pipe emptying into present irrigation ditch (State whether through or around the proposed dam)

10. The area submerged by the proposed reservoir, when full, will be approx 6 acres, with a maximum depth of water of 25 feet; and approximate mean depth of water feet.

11. The estimated cost of the proposed work is \$ 1000.00

12. Construction work will begin on or before November 1, 1938

13. Construction work will be completed on or before March 1, 1939

Duplicate maps of the proposed reservoir and storage works, prepared in accordance with the rules of the State Water Board, accompany this application.

(Sgd) George Yokom (Name of applicant)

Signed in the presence of us as witnesses:

(1) (Sgd) Orval D. Yokom, John Day, Oregon (Name) (Address of witness)

(2) (Sgd) S. E. Lucas, John Day, Oregon (Name) (Address of witness)

Remarks: This storage is for the purpose of augmenting the supply of irrigation water under proofs No. 1500 and 1501.

STATE OF OREGON, }
County of Marion, } ss.

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for correction or completion as follows:

In order to retain its priority, this application must be returned to the State Engineer, with corrections, on or before _____, 19_____.

WITNESS my hand this _____ day of _____, 19_____.

State Engineer

STATE OF OREGON, }
County of Marion, } ss.

This is to certify that I have examined the foregoing application and do hereby grant the same, subject to the following limitations and conditions: The right herein granted is limited to the construction of a reservoir and the storage of water from Birch Creek for irrigation purposes, to be appropriated under Application No. 22943, Permit No. 17902.

The right hereunder shall be limited to the storage of 45.0 acre feet.

The priority date of this permit is September 29, 1938

Actual construction work shall begin on or before December 18, 1948 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1950

WITNESS my hand this 18th day of December, 19 47.

CHAS. E. STRICKLIN

State Engineer

Application No. 17611

Reservoir Permit No. 904

PERMIT

To construct a reservoir and store for beneficial use the unappropriated waters of the State of Oregon.

District No.

This instrument was first received in the office of the State Engineer at Salem, Oregon, on the 29th day of September, 1938, at 8:00 o'clock A. M.

Returned to applicant for correction:

Corrected application received:

Approved:

January 15, 1948

Recorded in Book No. 3 of Reservoirs, on Page R-904

CHAS. E. STRICKLIN

State Engineer

Form 103a-500-7-37

STATE PRINTING DEPT.

6 - 22 A

Fees paid \$10.00