



STATE OF OREGON

County of JACKSON

"CERTIFICATE NO. 577234"

**PERMIT to CONSTRUCT a RESERVOIR and to STORE
for BENEFICIAL USE the PUBLIC WATERS**

ASSIGNED. See Misc. Rec., Vol. 6 Page 1298

This is to certify that I have examined APPLICATION R-67696 and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to Robert L. Johnson and/or Kristin K. Johnson of 7936 Upper Applegate Road, Jacksonville, Oregon 97530, phone 899-8980, for the construction of a reservoir and storage of water from an unnamed spring, a tributary to Applegate River and surface runoff to be appropriated under Application 67697, Permit 48206 for irrigation,

The dam will be LOCATED in the: NW 1/4 NW 1/4 of Section 33, Township 39 South, Range 3 West, WM, in the County of Jackson.

The maximum height will be 8.0 feet above the stream bed or ground surface at the centerline. The top width will be 10.0 feet, slope of upstream face 3:1, slope of downstream face 2:1, and height of dam above water line when full 3.5 feet

The area submerged by the reservoir, when full, will be 0.34 acre, and the maximum depth of water will be 8.0 feet

The location and dimensions of the spillway are: Around the dam, bottom width 3.0 feet, top width 2.5 feet, the distance between the crest of the dam and the crest of the spillway 2.5+ feet.

The location and dimension of the outlet conduit will be: 2 - 12 inch outlets, approximately 2 1/2 to 3 1/2 feet from top of reservoir, with concrete and rock overflow on downhill side of reservoir.

The structure is out of the channel.

The dam will be earthfill construction, packed sand and clay in area.

The right hereunder shall be limited to the storage of 2.7 acre-feet, being 1.35 af from each source

The PRIORITY DATE of this permit is October 13, 1983 .

Actual construction work shall begin on or before February 21, 1985, and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1985 .

Witness my hand this 21st day of February, 1984 .

/s/ WILLIAM H. YOUNG

WATER RESOURCES DIRECTOR

This permit, when issued, is for the beneficial use of water. By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan. It is possible that the land use you propose may not be allowed if it is not in keeping with the goals and the acknowledged plan. Your city or county planning agency can advise you about the land-use plan in your area.

APPLICATION R-67696

PERMIT

R 9308