



STATE OF OREGON

County of WASHINGTON

PERMIT to CONSTRUCT a RESERVOIR and to STORE for BENEFICIAL USE the PUBLIC WATERS

This is to certify that I have examined APPLICATION R-67689 and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to Ted C. Neward of Route 1, Box 206, Banks, Oregon 97106, phone 324-7901, for the construction of two reservoirs (Pond 1 and Pond 2), tributaries of Garrigus Creek, and storage of water from Rock Creek to be appropriated under Application 64595, Permit 48331, for irrigation,

The dam will be LOCATED in the: Reservoir 1 - SE 1/4 NW 1/4 of Section 14; Reservoir 2 - SE 1/4 SW 1/4 of Section 11, both in Township 2 North, Range 4 West, WM, in the County of Washington.

The maximum height will be * feet above the stream bed or ground surface at the centerline. The top width will be 14.0 feet, slope of upstream face 3:1, slope of downstream face 2 1/2:1, and height of dam above water line when full Reservoir 1 - 4.0 feet and Reservoir 2 - 4.3 feet

The area submerged by the reservoir, when full, will be ** , and the maximum depth of water will be Reservoir 1 - 25.0 feet and Reservoir 2 - 30.0 feet

* Reservoir 1 - 20.0 feet and Reservoir 2 - 28.0 feet

** Reservoir 1 - 5.2 acres and Reservoir 2 - 1.5 acres

The location and dimension of the spillway is: Around the dam, the bottom width of the spillway will be 30.0 feet for Reservoir 1 and 20 feet for Reservoir 2, with side slopes of 2:1 and the distance between the crest of the dam and the crest of the spillway will be 3.0 feet for Reservoir 1 and 3.1 feet for Reservoir 2.

The location and dimension of the outlet conduit will be: Reservoir 1 - 12 inch diameter asphalt coated CMP and Reservoir 2 - 8 feet diameter asphalt coated CMP. Both pipes located through base of dam.

The structure is in the channel.

The dam will be earthfill construction

Reservoir 1 was constructed under Permit R-6076; Reservoir 2 was constructed under Permit R-5556. The purpose of the new permit is to allow storage for irrigation, a use not requested nor allowed in the prior permits.

The right hereunder shall be limited to the storage of 26.0 acre-feet, being 20.0 af in Pond 1 and 6.0 af in Pond 2

The PRIORITY DATE of this permit is October 12, 1983 .

Actual construction work shall begin on or before April 19, 1985 , and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 19 86 .

Witness my hand this 19th day of April , 19 84 .

/s/ WILLIAM H. YOUNG

WATER RESOURCES DIRECTOR

This permit, when issued, is for the beneficial use of water. By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan. It is possible that the land use you propose may not be allowed if it is not in keeping with the goals and the acknowledged plan. Your city or county planning agency can advise you about the land-use plan in your area.

APPLICATION R-67689

CERTIFICATE NO. 61460

PERMIT

R 9602