



STATE OF OREGON

County of CLACKAMAS

PERMIT to CONSTRUCT a RESERVOIR and to STORE for BENEFICIAL USE the PUBLIC WATERS

This is to certify that I have examined APPLICATION R-68004 and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to Sandy Farms of 34500 SE Highway 211, Boring, Oregon 97009, phone 668-4525 (office) or 668-6598 (home), for the construction of Sandy Farms 4 Reservoir and storage of water from an unnamed stream, a tributary of Deep Creek, to be appropriated under Application 68005, Permit 48424 for supplemental irrigation. All flashboards to be removed from spillway during the period from *
The dam will be LOCATED in the: NE 1/4 NE 1/4 of Section 27, Township 2 South, Range 4 East, WM, in the County of Clackamas.

The maximum height will be 16.0 feet above the stream bed or ground surface at the centerline. The top width will be **, slope of upstream face 3:1, slope of downstream face 2:1, and height of dam above water line when full 2.0 feet

The area submerged by the reservoir, when full, will be 0.89 acres, and the maximum depth of water will be 14.0 feet

* October 1 to April 1 of each year.

** Earthfill - 10.0 feet; Flashboard - 25.0 feet

The location and dimensions of the spillway are: Around the dam, bottom width 6.0 feet, top width 6.0 feet, the distance between the crest of the dam and the crest of the spillway 16.0 feet.

The location and dimension of the outlet conduit will be: A 12 inch steel outlet conduit is provided through the reinforced concrete flashboard section adjacent to the flashboard channel. The outlet conduit is provided with a shear gate at the upstream end and a blind flange at the downstream end. The conduit serves a dual purpose as an outlet and a pump suction line.

The structure is in channel.

The dam will be earthfill and flashboard construction.

The right hereunder shall be limited to the storage of 4.3 acre-feet

The PRIORITY DATE of this permit is January 25, 1984 .

Actual construction work shall begin on or before May 14, 1985, and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1986 .

Witness my hand this 14th day of May, 1984 .

/s/ WILLIAM H. YOUNG

WATER RESOURCES DIRECTOR

This permit, when issued, is for the beneficial use of water. By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan. It is possible that the land use you propose may not be allowed if it is not in keeping with the goals and the acknowledged plan. Your city or county planning agency can advise you about the land-use plan in your area.

APPLICATION R-68004

"CERTIFICATE NO. 67227"

PERMIT

R 9689