



## STATE OF OREGON

"CERTIFICATE NO. 55825"

County of MARION

**PERMIT to CONSTRUCT a RESERVOIR and to STORE  
for BENEFICIAL USE the PUBLIC WATERS**

This is to certify that I have examined APPLICATION R-68025 and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to Loris C. Harrell of 4023 Judy Avenue, NE, Salem, Oregon 97305, phone 364-8132, for the construction of a reservoir, a tributary of Little Pudding and storage of water from an unnamed creek to be maintained by appropriation under Application 68026, Permit 48425 for esthetic purposes,

The dam will be LOCATED in the: NW 1/4 NE 1/4 of Section 9, Township 7 South, Range 2 West, WM, in the County of Marion.

The maximum height will be 5.0 feet above the stream bed or ground surface at the centerline. The top width will be 10.0 feet, slope of upstream face 3:1, slope of downstream face 2:1, and height of dam above water line when full 3.0 feet

The area submerged by the reservoir, when full, will be 0.5 acre, and the maximum depth of water will be 3.0 feet

The location and dimensions of the spillway are: Around the dam, bottom width 14.0 feet, top width 14.0 feet, the distance between the crest of the dam and the crest of the spillway 39 inches.

The location and dimension of the outlet conduit will be: East side of dam, concrete, 40 feet long, 10 feet wide, 2.5 feet high walls, 10 inch concrete pipe base of dam.

The structure in channel.

The dam will be earthfill construction.

The right hereunder shall be limited to the storage of 1.0 acre-feet

The PRIORITY DATE of this permit is March 5, 1984

Actual construction work shall begin on or before May 14, 1985, and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1986

Witness my hand this 14th day of May, 1984

/s/ WILLIAM H. YOUNG

WATER RESOURCES DIRECTOR

This permit, when issued, is for the beneficial use of water. By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan. It is possible that the land use you propose may not be allowed if it is not in keeping with the goals and the acknowledged plan. Your city or county planning agency can advise you about the land-use plan in your area.