



STATE OF OREGON

County of DOUGLAS

PERMIT to CONSTRUCT a RESERVOIR and to STORE for BENEFICIAL USE the PUBLIC WATERS

This is to certify that I have examined APPLICATION R-68097 and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to Richard Caddock of 1606 Wild River Drive, Roseburg, Oregon 97443, for the construction of the Caddock Recreation Reservoir, and storage of water from an unnamed stream, a tributary of North Umpqua River, to be maintained by appropriation under Application 68142, Permit 48757 for recreation,

The dam will be LOCATED in the: NE 1/4 SE 1/4 of Section 15, Township 26 South, Range 4 West, WM, in the County of Douglas.

The maximum height will be 13.0 feet above the stream bed or ground surface at the centerline. The top width will be 10.0 feet, slope of upstream face 3:1, slope of downstream face 2:1, and height of dam above water line when full 3.0 feet

The area submerged by the reservoir, when full, will be 0.53 acre, and the maximum depth of water will be 11.0 feet

The location and dimension of the spillway are: Around the dam, the bottom width of the spillway will be 12.0 feet.

The location and dimension of the outlet conduit will be: 6 inch PVC conduit with 6 inch gate valve at the lower end. 2-4'x4" concrete seep collars will be constructed as shown on the plans. The PVC conduit will be tested at 50 psig after backfilling.

The structure is in the channel.

The dams will be earthfill construction.

The right hereunder shall be limited to the storage of 1.89 acre-feet

The PRIORITY DATE of this permit is June 4, 1984

Actual construction work shall begin on or before September 27, 1985, and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1985

Witness my hand this 27th day of September, 1984

/s/ WILLIAM H. YOUNG

WATER RESOURCES DIRECTOR

This permit, when issued, is for the beneficial use of water. By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan. It is possible that the land use you propose may not be allowed if it is not in keeping with the goals and the acknowledged plan. Your city or county planning agency can advise you about the land-use plan in your area.

"CERTIFICATE NO. 62029"

APPLICATION R-68097

PERMIT

R 9972