

SUPERSEDED

Permit No. 19116

CERTIFICATE NO. 46557

CERTIFICATE NO. 20207

ASSIGNED, See Misc. Rec. Vol. 3 Page 539-40

* APPLICATION FOR PERMIT

To Appropriate the Public Waters of the State of Oregon

I, R. H. Poole (Name of applicant)
of Jacksonville Star Route 1, Box 79, (Mailing address)
State of Oregon, do hereby make application for a permit to appropriate the following described public waters of the State of Oregon, SUBJECT TO EXISTING RIGHTS:

If the applicant is a corporation, give date and place of incorporation

1. The source of the proposed appropriation is Big Applegate River (Name of stream)

, a tributary of Rogue River

2. The amount of water which the applicant intends to apply to beneficial use is 0.15 cubic feet per second. (If water is to be used from more than one source, give quantity from each)

**3. The use to which the water is to be applied is Irrigation (Irrigation, power, mining, manufacturing, domestic supplies, etc.)

4. The point of diversion is located 1950 ft. S. and 1800 ft. W. from the NE corner of Section 29 (Section or subdivision)

(Pump site location on the Kubli ditch is 1940 feet South & 850 feet East from the N. W. corner of Section 29, Township 38 South, Range 4 West, W.M.)

(If preferable, give distance and bearing to section corner)

(If there is more than one point of diversion, each must be described. Use separate sheet if necessary)

being within the SW 1/4 NE 1/4 of Sec. 29, Tp. 38 S. (Give smallest legal subdivision) (N. or S.)

R. 3 W., W. M., in the county of Jackson (E. or W.)

5. The Kubli ditch to be 1 1/2 miles (Main ditch, canal or pipe line) (Miles or feet)

in length, terminating in the SW 1/4 NW 1/4 of Sec. 23, Tp. 38 S. (Smallest legal subdivision) (N. or S.)

R. 4 W., W. M., the proposed location being shown throughout on the accompanying map. (E. or W.)

DESCRIPTION OF WORKS

Diversion Works—

6. (a) Height of dam 4 feet, length on top 80 feet, length at bottom feet; material to be used and character of construction concrete (Loose rock, concrete, masonry, rock and brush, timber crib, etc., wasteway over or around dam)

(b) Description of headgate 4 x 3 x 16' long (Timber, concrete, etc., number and size of openings)

(c) If water is to be pumped give general description 3" Centr. ifugal pump powered by 2 H.P. electric motor; total lift 15 feet. (Size and type of pump) (Size and type of engine or motor to be used, total head water is to be lifted, etc.)

* A different form of application is provided where storage works are contemplated.

** Application for permits to appropriate water for the generation of electricity, with the exception of municipalities, must be made to the Hydroelectric Commission. Either of the above forms may be secured, without cost, together with instructions by addressing the State Engineer, Salem, Oregon.

Canal System or Pipe Line—

7. (a) Give dimensions at each point of canal where materially changed in size, stating miles from headgate. At headgate: width on top (at water line) 4 feet; width on bottom 3 feet; depth of water 1 feet; grade 2 feet fall per one thousand feet.

(b) At 2 miles from headgate: width on top (at water line) 4 feet; width on bottom 3 feet; depth of water 1 feet; grade 2 feet fall per one thousand feet.

(c) Length of pipe, 1550 ft.; size at intake, 3 in.; size at 650 ft. from intake 2 in.; size at place of use 2 in.; difference in elevation between intake and place of use, 15 ft. Is grade uniform? Yes Estimated capacity, sec. ft. Sprinkler system

8. Location of area to be irrigated, or place of use

Township	Range	Section	Forty-acre Tract	Number Acres To Be Irrigated
38 S	4 W	23	SW 1/4 NW 1/4	12
Property on which water is to be used is a part of that more explicitly described by applicant as follows:				
Joe Markham & Lavon E. Markham				
Property description as copied from Warranty Deed, Volume 310, Page 268, Jackson County Deed Records:				
Government Lots 2 and 3 in Section 23, Township 38 South, of Range 4 West of the Willamette Meridian in Jackson County, Oregon; also, beginning at the Northeast corner of Donation Land Claim No. 38, in Township 38 South of Range 4 West of the Willamette Meridian in Oregon; thence South 15 1/2° West 4 chains and 66 links; thence South 41° West 6 chains; thence South 54 1/2° West 10 chains; thence South 80° West 8 chains to a post near the confluence of Humbug Creek with Applegate Creek; thence South 45 3/4° East along the West bank of Applegate Creek 29 chains and 59 links to the Southeast corner of said D.L.C. 38; thence North along the east boundary line of said D.L.C. 38, 36 chains and 85 links to the place of beginning.				
(If more space required, attach separate sheet)				

(a) Character of soil River loam

(b) Kind of crops raised Alfalfa and hay

Power or Mining Purposes—

9. (a) Total amount of power to be developed theoretical horsepower.

(b) Quantity of water to be used for power sec. ft.

(c) Total fall to be utilized feet.
(Head)

(d) The nature of the works by means of which the power is to be developed

(e) Such works to be located in of Sec.
(Legal Subdivision)

Tp., R., W. M.
(No. N. or S.) (No. E. or W.)

(f) Is water to be returned to any stream?
(Yes or No)

(g) If so, name stream and locate point of return

....., Sec., Tp., R., W. M.
(No. N. or S.) (No. E. or W.)

(h) The use to which power is to be applied is

(i) The nature of the mines to be served

Application No. 21211

Permit No. 19116

PERMIT TO APPROPRIATE THE PUBLIC WATERS OF THE STATE OF OREGON

Division No. District No.

This instrument was first received in the office of the State Engineer at Salem, Oregon, on the 28th day of October 1949, at 1:00 o'clock P. M.

Returned to applicant:

Corrected application received:

Approved:

March 30, 1950

Recorded in book No. 47 of Permits on page 19116

CHAS. E. STRICKLIN

STATE ENGINEER

Drainage Basin No. 15 Page 8 A

Fees Paid \$15.00

PERMIT

STATE OF OREGON, } ss. County of Marion,

This is to certify that I have examined the foregoing application and do hereby grant the same, SUBJECT TO EXISTING RIGHTS and the following limitations and conditions:

The right herein granted is limited to the amount of water which can be applied to beneficial use and shall not exceed 0.15 cubic feet per second measured at the point of diversion from the stream, or its equivalent in case of rotation with other water users, from Big Applegate River.

The use to which this water is to be applied is Irrigation

If for irrigation, this appropriation shall be limited to 1/80th of one cubic foot per second or its equivalent for each acre irrigated and shall be further limited to a diversion of not to exceed 1 1/2 acre feet per acre for each acre irrigated during the irrigation season from April 2, to October 31, of each year,

and shall be subject to such reasonable rotation system as may be ordered by the proper state officer.

The priority date of this permit is October 28, 1949

Actual construction work shall begin on or before March 30, 1951 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1952

Complete application of the water to the proposed use shall be made on or before

October 1, 1953

WITNESS my hand this 30th day of March, 1950

CHAS. E. STRICKLIN

STATE ENGINEER