

Application No. 58414

Permit No. 44236

STATE OF OREGON WATER RESOURCES DEPARTMENT

RECEIVED

MAR 19 1979

Application for Permit to Appropriate Surface Water

WATER RESOURCES DEPT.
SALEM, OREGON

I, Rudolph S. Valente

(Name of Applicant)

of Star Route Box 17

(Mailing Address)

Agness

(City)

State of Oregon

(Zip Code)

97406

Phone No. (503) 247-6162

do hereby

make application for a permit to appropriate the following described waters of the State of Oregon:

Spring Area (POD #1)

Rogue River (POD #3)

1. The source of the proposed appropriation is Unnamed Stream (POD #2) Spring (POD #4)

POD #1 Trib. of unnamed stream

POD #2 " " Rogue River

POD #3 " " Private A.C.F.A.

POD #4 " " Rogue River

2. The point of diversion is to be located (s. c. below) ft. and ft.

(N. or S.)

(E. or W.)

from the N.W. 1/6 corner of NE 1/4 SW 1/4

(Public Land Survey Corner)

POD #1 640' S 460' E

(If there is more than one point of diversion, each must be described)

POD #2 950' S 460' E

POD #3 1320' S 970' E

POD #1 & #2 NE 1/4 of the SW 1/4

POD #4 1420' S 520' E

being within the POD #3 & #4 SE 1/4 of the SW 1/4 of

(see attached map)

Sec. 7 Tp. 35 S R. 11 W, W. M., in the county of Curry

(N. or S.)

(E. or W.)

3. Location of area to be irrigated, or place of use if other than irrigation.

Township	Range	Section	List 1/4 1/4 of Section	List use and/or number of acres to be irrigated
<u>T35S</u>	<u>R 11W</u>	<u>7</u>	<u>NE 1/4 SW 1/4</u>	<u>Domestic use to include up to 0.5 Ac. lawn & garden irr. (POD #1 Spring)</u>
"	"	"	" "	<u>Commercial use from unnamed stream (POD #2) supplemented by Spring area (POD #1)</u>
"	"	"	" "	<u>Irrigation 5.4 Ac. from Rogue River (incl. lawn & garden) (POD #3)</u>
"	"	"	<u>SE 1/4 SW 1/4</u>	<u>Irrigation 4.6 Ac. from Rogue River (incl. lawn & garden) and Restroom Facility</u>
"	"	"	" "	<u>Commercial use from spring (POD #4) Domestic use (incl. lawn & garden) from spring</u>

POD #1 Domestic (L+G) 0.0125 Spring
POD #2 Comm. 0.0025 Unnamed Stream

4. The amount of water which the applicant intends to apply to beneficial use is 0.155
(POD #1 & #2) 0.015 from Spring NE 1/4 of SW 1/4 and Unnamed Stream.
cubic feet per second. being (POD #3) 0.13 from Rogue River; (POD #4) 0.01 from Spring in SE 1/4 of SW 1/4.
(If water is to be used from more than one source, give quantity from each)
Irrigation Dom/Comm.

See Remarks

5. The use to which the water is to be applied is ~~Spring area (POD #1) Domestic use, lawn & garden, supplemental commercial use, Unnamed Stream (POD #2) Commercial, lawn & garden, Rogue River (POD #3) Irrigation lawn & garden and Restroom Facilities, Spring (POD #4) Commercial use and Domestic use (incl. lawn & garden).~~

6. DESCRIPTION OF WORKS

Include dimensions and type of construction of diversion dam and headgate, length and dimensions of supply ditch or pipeline, size and type of pump and motor, type of irrigation system to adequately describe the proposed distribution system.

POD #1 Dam (Spring tank) 12' w x 3' h with 2' x 3' wings. 320' of 1" plastic pipe to POD #2 for supplemental commercial use, lawn & garden. 300' of 1" plastic pipe to future domestic use, lawn & garden (all surface).

POD #2 Concrete tank 7' w x 7 1/2' l x 3' deep. 1600' of 2" plastic galv. pipe (underground & surface) gravity flow to commercial use, lawn & garden.

POD #3 Pump 7/8 H.P. 3 Phase High Pressure w/ G-E motor. 130' of 3" aluminum & plastic pipe (surface & underground). 650' of 2" aluminum pipeline w/ faucets every 20' to attach garden hoses to operate "Rain Bird" sprinklers.

POD #4 382 gal Spring Tank. 100' of 3/4" plastic pipe (surface and underground) to domestic use with tie to 350' of 3/4" line for commercial use.

1545 gal Spring Tank. 25' of 1/4" plastic pipe (surface) to 3/4 h.p. pressure pump w/ 300 gal. pressure tank. 350' of 3/4" underground pipeline (plastic & galv.) to commercial use. 400' of 1 1/2" galv. pipeline (underground) for Restroom Facilities, lawn & garden.

If for domestic use state number of families to be supplied two

7. Construction work will begin on or before Construction has begun.

8. Construction work will be completed on or before 3-15-81

9. The water will be completely applied to the proposed use on or before 3-15-82

Application No. 58414

Permit No. 44236


Remarks: Item 5: The use to which the water is to be applied is

Domestic = 0.0175 cfs (0.0125 + 0.005)

Commercial = 0.0075 " (0.0025 + 0.005)

Irrigation : 0.13
0.155 cfs

Assistance in preparation of application by J.P. Drotet from information submitted by applicant.


Signature of Applicant

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for..... Additional Information.....

In order to retain its priority, this application must be returned to the Water Resources Director with corrections on or before June 25th, 19 79.....

WITNESS my hand this 24th day of April 19 79.....

..... JAMES E. SEXSON Water Resources Director

By 
VESTAL R. GARNER.

This instrument was first received in the office of the Water Resources Director at Salem, Oregon, on the 19th day of March, 19 79, at 8:00 o'clock A.M.

Application No. 58414

Permit No. 44236

RECEIVED
JUN 19 1979
WATER RESOURCES DEPT
SALEM, OREGON

Permit to Appropriate the Public Waters of the State of Oregon

This is to certify that I have examined the foregoing application and do hereby grant the same SUBJECT TO EXISTING RIGHTS INCLUDING THE EXISTING FLOW POLICIES ESTABLISHED BY THE WATER POLICY REVIEW BOARD and the following limitations and conditions:

The right herein granted is limited to the amount of water which can be applied to beneficial use and shall not exceed 0.148 cubic feet per second measured at the point of diversion from the

stream, or its equivalent in case of rotation with other water users, from a spring area, an unnamed spring, an unnamed stream, and the Rogue River; for domestic use for two families including the irrigation of lawn and garden not to exceed 1/2 acre in area for one family only, commercial use, and irrigation; being 0.01 from the unnamed spring area for domestic use for one family including irrigation of lawn and garden not to exceed 1/2 acre in area, 0.003 c.f.s. from the unnamed stream for commercial use with any deficiency to be made up by the unnamed spring area, 0.005 c.f.s. for domestic use for one family from the unnamed spring, and 0.13 c.f.s. from the Rogue River for irrigation.

If for irrigation, this appropriation shall be limited to 1/80th of one cubic foot per second or its equivalent for each acre irrigated and shall be further limited to a diversion of not to exceed 4 1/2 acre feet per acre for each acre irrigated during the irrigation season of each year,

and shall be subject to such reasonable rotation system as may be ordered by the proper state officer.

The priority date of this permit is March 19, 1979

Actual construction work shall begin on or before July 13, 1980 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1981

Complete application of the water to the proposed use shall be made on or before October 1, 1982

WITNESS my hand this 13th day of July, 1979

James E. Pearson
Water Resources Director