

Application No...... **58488**.....

44268

44268

STATE OF OREGON WATER RESOURCES DEPARTMENT

Application for Permit to Appropriate Surface Water APR 3 1979

**WATER RESOURCES DEPT.
SALEM, OREGON**

I, Samuel P. Smith (Name of Applicant) WATER RESOURCE
SALEM, OREG.

of P.O. Box 305 (Name of Applicant)
(Mailing Address) MOSIER (City)

(Mailing Address)
State of Oregon, 97040 Phone No. 478-3363 do hereby
(City)
(Zip Code)

make application for a permit to appropriate the following described waters of the State of Oregon:

→ 1. The source of the proposed appropriation is natural Swale Pond source

2. The point of diversion is to be located 540 ft. N and 1230 ft. E
(N. or S.) (E. or W.)

from the S.W. corner of Sec. 5 (Public Land Survey Corner)

Note - The water source for the Snake pond being SPRINGS
(Public Land Survey Corner)
and SNOW AND RAIN WATER RUN-OFF FROM THE
SURROUNDING HILLS. B.B.
(If there is more than one point of diversion, each must be described)

..... being within the S.W. ¼ of the S.W. ¼ of
Sec. 5 Tp. 2 N. R. 12 E., W.M., in the county of WASH. O.

3. Location of area to be irrigated, or place of use if other than irrigation.

4. The amount of water which the applicant intends to apply to beneficial use is Or. 28
cubic feet per second.....
(If water is to be used from more than one source, give quantity from each)

5. The use to which the water is to be applied isIRRIGATION.....

6.

DESCRIPTION OF WORKS

Include dimensions and type of construction of diversion dam and headgate, length and dimensions of supply ditch or pipeline, size and type of pump and motor, type of irrigation system to adequately describe the proposed distribution system.

4 FT HIGH RETAINING DAM - 150' SEMI CIRCLE
WITH 2 FT CONCRETE SPILLWAY WITH 1 FT WIRE
AND STOP-GATE. (4 ft higher than previous land contours.)
10 hp ELECTRIC MOTOR PUMP WI 4" SUCTION
AND 3" DISCHARGE.

This will feed 5" main in west direction
200 ft. with 3- 3" lateral taps. Then
main line will travel southwesterly direction
300 ft. with 2 lateral taps. laterals
with Be 2" alum sect with SPRINKLER
heads at 40' interval spaces.

Note: The pool formed would serve as a
PUMPING SUMP and would NOT ~~be~~ serve as
a WATER STORAGE FOR FUTURE USE. B.

If for domestic use state number of families to be supplied.....

7. Construction work will begin on or before.....OCT 1 1979


8. Construction work will be completed on or before.....OCT 1 1980

9. The water will be completely applied to the proposed use on or before.....JUNE 30 1981/1982

Application No. 58488.....

RECEIVED
Permit No. 44268.....

Remarks:.....



Signature of Applicant

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for.....completion...and..correction.....

WATER RESOURCES DEPT.
SALEM, OREGON

RECEIVED

MAY 16 1979


WATER RESOURCES DEPT.
SALEM, OREGON

JUN 3 1979
WATER RESOURCES DEPT.
SALEM, OREGON

RECEIVED

In order to retain its priority, this application must be returned to the Water Resources Director with corrections on or before July 2, 1979
July 30, 1979
September 5, 1979

WITNESS my hand this 30th day of April, 1979
29th May, 1979
5th July, 1979
James E. Sexson, Water Resources Director

By 
Ves Garner

This instrument was first received in the office of the Water Resources Director at Salem, Oregon, on the 3rd day of April, 1979, at 11:00 o'clock A.M.

Application No. 58488

Permit No. 44268

Permit to Appropriate the Public Waters of the State of Oregon

This is to certify that I have examined the foregoing application and do hereby grant the same SUBJECT TO EXISTING RIGHTS INCLUDING THE EXISTING FLOW POLICIES ESTABLISHED BY THE WATER POLICY REVIEW BOARD and the following limitations and conditions:

The right herein granted is limited to the amount of water which can be applied to beneficial use and shall not exceed 0.28 cubic feet per second measured at the point of diversion from the stream, or its equivalent in case of rotation with other water users, from a natural swale pond.

The use to which this water is to be applied is irrigation.

If for irrigation, this appropriation shall be limited to 1/60th of one cubic foot per second or its equivalent for each acre irrigated and shall be further limited to a diversion of not to exceed 3 acre feet per acre for each acre irrigated during the irrigation season of each year,

and shall be subject to such reasonable rotation system as may be ordered by the proper state officer.

The priority date of this permit is April 3, 1979

Actual construction work shall begin on or before August 8, 1980 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 19..... 81

Complete application of the water to the proposed use shall be made on or before October 1, 19..... 82

WITNESS my hand this 8th day of August , 19.... 79