

STATE OF OREGON WATER RESOURCES DEPARTMENT

Application for Permit to Appropriate Surface Water

I, U. S. Forest Service, Rogue River National Forest
(Name of Applicant)

of P. O. Box 520 Medford
(Mailing Address) (City)

State of Oregon, 97501 Phone No. 776-3600 do hereby
(Zip Code)

make application for a permit to appropriate the following described waters of the State of Oregon:

1. The source of the proposed appropriation is Rogue River (North Fork)
 a tributary of Pacific Ocean

2. The point of diversion is to be located 2,640 ft. N and 1,425 ft. E
(N. or S.) (E. or W.)
 from the SW corner of Section 35, T. 30 S., R. 3 E., W.M.
(Public Land Survey Corner)

(If there is more than one point of diversion, each must be described)

being within the NE $\frac{1}{4}$ of the SW $\frac{1}{4}$ of
 Sec. 35 Tp. 30 S. R. 3 E., W. M., in the county of Jackson
(N. or S.) (E. or W.)

3. Location of area to be irrigated, or place of use if other than irrigation.

Township	Range	Section	List $\frac{1}{4}$ $\frac{1}{4}$ of Section	List use and/or number of acres to be irrigated
30 S.	3 E.	35	SE $\frac{1}{4}$ NW $\frac{1}{4}$	Domestic
30 S.	3 E.	35	SW $\frac{1}{4}$ NE $\frac{1}{4}$	Domestic
30 S.	3 E.	35	NE $\frac{1}{4}$ SW $\frac{1}{4}$	Domestic
30 S.	3 E.	35	NW $\frac{1}{4}$ SW $\frac{1}{4}$	Domestic
30 S.	3 E.	35	SW $\frac{1}{4}$ SW $\frac{1}{4}$	Domestic

4. The amount of water which the applicant intends to apply to beneficial use is 0.04

cubic feet per second..... North Fork Rogue River.....

(If water is to be used from more than one source, give quantity from each)

5. The use to which the water is to be applied is domestic, potable and for sanitation.....

6.

DESCRIPTION OF WORKS

Include dimensions and type of construction of diversion dam and headgate, length and dimensions of supply ditch or pipeline, size and type of pump and motor, type of irrigation system to adequately describe the proposed distribution system.

A 20 gpm submersible pump pumps raw water from Rogue River into a sand filter.....
treatment plant. The water is filtered and disinfected and then pumped into a large
hydropneumatic storage tank. From there it flows through the distribution lines....
throughout the campground. The pipeline consists of 475 ft. of 4 inch line.....
565 ft. of 3 inch line, 605 ft. of 2½ inch line, 1,520 ft. of 2 inch line.....
505 ft. of 1½ inch line, 490 ft. of 1¼ inch line, 145 ft. of 1 inch line.....
400 ft. of ¾ inch line, and 1,100 ft. of ½ inch line.....

If for domestic use state number of families to be supplied

7. Construction work will begin on or before..... 10/1/80.....

8. Construction work will be completed on or before..... 10/1/81.....

9. The water will be completely applied to the proposed use on or before..... 10/1/82.....

Application No. 59685

Permit No. 44981

44981

Remarks: Farewell Bend Campground was constructed in 1933 by the Civilian Conservation Corps of the U. S. Forest Service. It was reconstructed in 1973 and a new water system installed. The campground is administered by the Rogue River National Forest. It is available for use by the general public on a fee basis regardless of race, color or creed.


Signature of Applicant

DONALD H. SMITH, Forest Supervisor

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for

In order to retain its priority, this application must be returned to the Water Resources Director with corrections on or before, 19.....

WITNESS my hand this day of....., 19.....

..... Water Resources Director

By

This instrument was first received in the office of the Water Resources Director at Salem, Oregon, on the 3rd day of January, 19 80, at 11:00 o'clock A.M.

Application No. 59685

Permit No. 44981

44981

Application No. 59685

Permit No. 44981

Permit to Appropriate the Public Waters of the State of Oregon

This is to certify that I have examined the foregoing application and do hereby grant the same SUBJECT TO EXISTING RIGHTS INCLUDING THE EXISTING FLOW POLICIES ESTABLISHED BY THE WATER POLICY REVIEW BOARD and the following limitations and conditions:

The right herein granted is limited to the amount of water which can be applied to beneficial use and shall not exceed 0.04 cubic feet per second measured at the point of diversion from the stream, or its equivalent in case of rotation with other water users, from North Fork Rogue River

The use to which this water is to be applied is domestic use in Farewell Bend Campground

If for irrigation, this appropriation shall be limited to of one cubic foot per second or its equivalent for each acre irrigated

and shall be subject to such reasonable rotation system as may be ordered by the proper state officer.

The priority date of this permit is January 31, 1980

Actual construction work shall begin on or before August 25, 1981 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1982

Complete application of the water to the proposed use shall be made on or before October 1, 1983

WITNESS my hand this 25th day of August, 1980

James E. Larson
Water Resources Director

RHX A