

\*Permit No. 6193

Corr. Cert. 30907  
5343

APPLICATION FOR A PERMIT

To appropriate the Public Waters of the State of Oregon

I, F. G. Buskuhl (Name of Applicant) of Friend (Postoffice), County of Wasco, State of Oregon, do hereby make application for a permit to appropriate the

following described public waters of the State of Oregon subject to existing rights:

If the applicant is a corporation, give date and place of incorporation

1. The source of the proposed appropriation is Fifteen Mile Creek (Name of stream)

tributary of Columbia River

2. The amount of water which the applicant intends to apply to beneficial use is Four cubic feet per second.

3. The use to which the water is to be applied is Power and domestic use. (Irrigation, power, mining, manufacturing, domestic supplies, etc.)

4. The point of diversion is located S. 18 deg. 24 min. W. 2643 ft. from the section cor. common to Sections 17-18-19-20 T. 2 S R 12 E.V.M. (Give distance and bearing to section corner)

being within the NW 1/4 NE 1/4 of Sec. 19, Tp. 2 S, R. 12 E, W. M., in the county of Wasco (Give smallest legal subdivision) (No. N. or S.)

5. The ditch to be 3400 ft. miles in length, terminating in the NW 1/4 NW 1/4 of Sec. 20, Tp. 2 S, R. 12 E, W. M., the proposed location being shown throughout on the accompanying map. (Main ditch, canal or pipe line) (Smallest legal subdivision) (No. N. or S.)

6. The name of the ditch, canal or other works is Munger Ditch

DESCRIPTION OF WORKS

DIVERSION WORKS—

7. (a) Height of dam 2 feet, length on top 20 feet, length at bottom 20 feet; material to be used and character of construction Logs and brush. (Loose rock, concrete, masonry, rock and brush, timber crib, etc., wasteway over or around dam)

(b) Description of headgate Timber 2 ft. X 3 ft. (Timber, concrete, etc., number and size of openings)

\* A different form of application is provided where storage works are contemplated. These forms can be secured without charge, together with instructions, by addressing the State Engineer, Salem, Oregon.

CANAL SYSTEM—

8. (a) Give dimensions at each point of canal where materially changed in size, stating miles from headgate. At headgate: Width on top (at water line) 5 feet; width on bottom 4.5 feet; depth of water 1.0 feet; grade approx. 2.5 feet fall per one thousand feet.

(b) At 3400 ft. miles from headgate. Width on top (at water line) change to 24 in. wood pipe feet; width on bottom feet; depth of water feet; grade feet fall per one thousand feet.

Wooden forebay 5 ft. X 3 ft. 3 in. leading to 24 inch wood pipe approx.

80 ft. long, Forebay is approx. 3400 ft. from headgate.

FILL IN THE FOLLOWING INFORMATION WHERE THE WATER IS USED FOR:

IRRIGATION—

9. The land to be irrigated has a total area of acres, located in each smallest legal subdivision, as follows:

(Give area of land in each smallest legal subdivision which you intend to irrigate)

(If more space required, attach separate sheet)

POWER, MINING, MANUFACTURING, OR TRANSPORTATION PURPOSES—

10. (a) Total amount of power to be developed 28 theoretical horsepower.

(b) Total fall to be utilized 61.5 feet. (Head)

(c) The nature of the works by means of which the power is to be developed Inward flow turbine built by James Leffel Co.

(d) Such works to be located in NW 1/4 NW 1/4 of Sec. 20, Tp. 2 S, R. 12 E, W. M.

(e) Is water to be returned to any stream? Yes (Yes or No)

(f) If so, name stream and locate point of return Fifteen Mile Creek

NW 1/4 NW 1/4, Sec. 20, Tp. 2 S, R. 12 E, W. M.

(g) The use to which power is to be applied is Running saw mill

(h) The nature of the mines to be served



Application No. 8998

Permit No. 6193

PERMIT TO APPROPRIATE THE PUBLIC WATERS OF THE STATE OF OREGON

District No.

This instrument was first received in the office of the State Engineer at

Salem, Oregon, on the 4 day of June, 1923, at 8:30 o'clock A.M.

Returned to applicant for correction

Corrected application received

Approved: March 12, 1924

Recorded in Book No. 21 of Permits, on Page 6193 RHEA LUPER

1 mar 24 ER State Engineer.

\$15.00

STATE OF OREGON, County of Marion, ss.

This is to certify that I have examined the foregoing application and do hereby grant the same, subject to the following limitations and conditions: If for irrigation, this appropriation shall be limited to one-eightieth of one cubic foot per second, or its equivalent, for each acre irrigated, and shall be subject to such reasonable rotation system as may be ordered by the proper state officer.

The right herein granted is limited to the appropriation of water from Fifteen Mile Creek for development of 28 theoretical horsepower and for domestic purposes. The right acquired for power development under this appropriation shall be, is deemed to be, and is hereby expressly made subsequent in right and time to any appropriations of water which may hereafter be made at points above on fifteen Mile Creek and its tributaries, for irrigation or storage purposes.

The amount of water appropriated shall be limited to the amount which can be applied to beneficial use and not to exceed 4.0 cubic feet per second, or its equivalent in case of rotation. The priority date of this permit is June 4, 1923.

Actual construction work shall begin on or before March 12, 1925 and shall thereafter be prosecuted with reasonable diligence and be completed on or before June 1, 1926.

Complete application of the water to the proposed use shall be made on or before October 1, 1927

WITNESS my hand this 12th day of March, 1924. RHEA LUPER,

State Engineer.

Permits for power development are subject to the limitation of franchise as provided in Section 5728, Oregon Laws, and the payment of annual fees as provided in Section 5803, Oregon Laws.

WAIVER.

The right acquired for the appropriation of water for power development under Application No. 8998 shall be, is deemed to be, and is hereby expressly made subsequent in right and time to any appropriations of water which may hereafter be made at points above on Fifteen Mile Creek, and its tributaries, for irrigation or storage purposes. The State Engineer is hereby authorized to so limit this application in his permit issued thereon

Dated this 26 day of February, 1924.

F. G. Buskuhl, (Signature of applicant.)