

APPLICATION FOR A CHANGE IN PLACE, CHARACTER AND QUANTITY OF USE.

URBAN GROWTH BOUNDARY
CITY OF PILOT ROCK, OREGON

The two wells in the NW1/4 of section 9 were used for industrial purposes by United States Gypsum and Oregon Fibre Products. The City of Pilot Rock has acquired lands and wells from these Companies. The City of Pilot Rock intends to change the nature of the use of the two wells from industrial to municipal. They also plan to increase the use of the well in Certificate 38851 by 1.12 cfs. The place of use will be changed from Section 9 to the urban growth boundary of the City of Pilot Rock.

Certificate 38851 authorizes the use of 2.22 cfs from the northern well. Certificate 24374 authorizes the use of 1.25 cfs from well 2.

The City of Pilot Rock intends to install a 130 horsepower pump on the certificate 38851 well and a 75 horsepower pump on the certificate 24374 well.

The City of Pilot Rock intends to connect these two wells to the existing City reservoir tank and the City distribution system.

Certificate 24374 was issued pursuant to Permit U-471.

Certificate 38851 was issued pursuant to Permit G-3221 (U-516).

Cor. monument
2" iron pipe
at 90° turn
in road

Certificate 38851
Well 280 feet south
and 950 ft east
of NW cor. Sec. 9
2.22 cfs

Applying for
additional 2.23 cfs.

TL
1300
1500

Certificate 24374
UMAT 66
Well 2 located
S22°28'E, 2490 feet
from NW Cor. Sec. 9
1.25 cfs

boundary
between
Tax Lots
1300 & 1500
East-West
centerline of
Section 9

Application G-15586
Permit G-15336
Wells 1 and 2
1.34 cfs

600,000 Gallon
Storage Tank

Well 2 UMAT 89
Certificate 23839
1.00 cfs
N41°12'13"85"W
3155.85' from the
SE Corner of
Section 17

Well 1 UMAT 90
Certificate 28952
1.00 cfs
957.88' South
and 1524' West
from SE corner of
Section 17

1/4 Cor.
RR Spike
centerline
of road

NE cor.
SENE
1/2 IP in
concrete

City of Pilot Rock Water System
4 artesian wells
600,000 gallon storage tank
Ductile Iron Pipe
10" 3000'
8" 3200'
6" 300'
4" 4000'
2" 3000'


Year	Gallons Pumped	Population
93-94	148,229,000	1540
94-95	119,953,000	1560
95-96	130,029,000	1570
96-97	135,409,000	1585
97-98	137,956,000	1640
98-99	143,599,900	1675
99-00	136,519,000	1700

USE RECORD

Use Percent	689 Accounts
Residential	83.1
Commercial	8.1
Industrial	1.9
Public	6.3


Bolt in County
Road 1375

Survey by:
CNRE 300
(renews 6-30-03)
David Haddock
P. O. Box 1574
Pendleton, OR 97801
(541) 276-2174
June - July, 2001



Horizontal Scale: 1" = 1320'

NOTE:
The information shown
on this map is solely for
Water Rights.
The data shown does not
represent ownership
information.



RECEIVED

SEP 28 2005

WATER RESOURCES DEPT
SALEM, OREGON

SURVEY FOR
CITY OF PILOT ROCK
% Mr. Steve Draper
144 Alder Place
Pilot Rock, OR 97868
(541) 443-2811

David L. Haddock,
Surveyor & Engineer

HADDOCK SURVEYING

GPS
AND
TOTAL STATION