

STATE OF OREGON

WATER SUPPLY WELL REPORT

(as required by ORS 537.765 & OAR 690-205-0210)

03-26-2008

WELL LABEL # L 97314

START CARD # 1003085

(1) LAND OWNER

Owner Well I.D. 1455

First Name ERIC

Last Name ERICKSON

Company

Address 2001 NW MCDANIEL RD

City POWELL BUTTE

State OR

Zip 97753

(2) TYPE OF WORK ☒ New Well ☐ Deepening ☐ Conversion☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud☐ Reverse Rotary ☐ Other(4) PROPOSED USE ☒ Domestic ☐ Irrigation ☐ Community☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering☐ Thermal ☐ Injection ☐ Other(5) BORE HOLE CONSTRUCTION Special Standard ☐ (Attach copy)

Depth of Completed Well 660.00 ft.

BORE HOLE

SEAL

sacks/

Dia	From	To	Material	From	To	Amt	lbs
12	0	18.5	Bentonite	0	18.5	11	S
8	18.5	660					

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E☒ Other POURED IN DRY

Backfill placed from ft. to ft. Material

Filter pack from ft. to ft. Material Size

Explosives used: ☐ Yes Type Amount

(6) CASING/LINER

Casing	Liner	Dia	+	From	To	Gauge	Stl	Plstc	Wld	Thrd
☒	☒	8	☒	1.5	18.5	.250	☒	☐	☐	☐
☐	☐	5	☐	10	660	.188	☐	☐	☐	☐
☐	☐		☐				☐	☐	☐	☐
☐	☐		☐				☐	☐	☐	☐

Shoe ☐ Inside ☐ Outside ☐ Other Location of shoe(s)Temp casing ☐ Yes Dia From To

(7) PERFORATIONS/SCREENS

Perforations Method SAW

Screens Type Material

Perf/S	Casing/	Screen							
green	Liner	Dia	From	To	Scrtn/slot	Slot	# of	Tele/	
					width	length	slots	pipe size	
Perf	Liner	5	610	660	.125	7	300		

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min Drawdown Drill stem/Pump depth Duration (hr)

15		660	1

Temperature 61 °F Lab analysis ☐ Yes ByWater quality concerns? ☐ Yes (describe below)

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County Crook Twp 14.00 S N/S Range 15.00 E E/W WM

Sec 31 SE 1/4 of the NW 1/4 Tax Lot 200

Tax Map Number Lot

Lat ° 0 ' " or DMS or DD

Long ° 0 ' " or DMS or DD

☒ Street address of well ☐ Nearest address

2001 NW MCDANIEL RD

POWELL BUTTE

(10) STATIC WATER LEVEL

Date SWL(psi) + SWL(ft)

Existing Well / Predeepening		
Completed Well	03-25-2008	458

Flowing Artesian? ☐ Dry Hole? ☐

WATER BEARING ZONES

Depth water was first found 458

SWL Date	From	To	Est Flow	SWL(psi)	+ SWL(ft)
03-25-2008	458	660	15		458

(11) WELL LOG

Ground Elevation

Material	From	To
SANDY TOP SOIL	0	2
GRAY BASALT	2	230
BROWN SANDSTONE	230	610
BROWN SANDSTONE & GRAVEL	610	625
BROWN SANDSTONE	625	660

RECEIVED BY OWRD

JUN 25 2013

SALEM, OR

Date Started 03-13-2008 Completed 03-25-2008

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 1892 Date 03-26-2008

Electronically Filed

Signed JEFF WILLIAMSON (E-filed)

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 584 Date 03-26-2008

Electronically Filed

Signed DARRELL MAPHET (E-filed)

Contact Info (optional)

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK

Form Version: 0.89

T011626