

RECEIVED

JUL 14 1959

WATER WELL REPORT

STATE ENGINEER STATE OF OREGON

SALEM, OREGON

MAR 1959

4499

6/2w-280

State Well No. 6-1174

State Permit No. 6-1174

File Original and First Copy with the STATE ENGINEER, SALEM, OREGON

(1) OWNER:

Name Don N. Zielinski
Address Rt. 2, Box 438
Salem, Oregon

(2) LOCATION OF WELL:

County Marion Owner's number, if any—
SW 1/4 SE 1/4 Section 28 T. 6S R. 2W W.M.
Bearing and distance from section or subdivision corner
420 ft. N and 10 ft. E from the S 1/4 corner of
Sec. 28

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in item 11.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jettied ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒
8" Diam. from 00 ft. to 52 ft. Gage 32#
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☒ Yes ☐ No
Type of perforator used
SIZE of perforations 10 in. by 1/4 in.
120 perforations from 14 ft. to 29 ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed ☐ Yes ☒ No
Manufacturer's Name
Type Model No.
Slot size Set from ft. to ft.
Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Was well gravel packed? ☒ Yes ☐ No Size of gravel: 1/2" minus
Gravel placed from 10 ft. to 52 ft.
Was a surface seal provided? ☐ Yes ☒ No To what depth? ft.
Material used in seal—
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? Depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level 5 ft. below land surface Date July 6, 1959
Artesian pressure lbs. per square inch Date

Log Accepted by:

[Signed] Don Zielinski Date July 9, 1959
(Owner)

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Owner
Yield: 200 gal./min. with 17 ft. drawdown after 3 hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well 8 inches.
Depth drilled 70 ft. Depth of completed well 52 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Topsoil -Loam	00	6 ft.
Brown clay	06	12
Blue clay	12	27
Course sand & gravel	27	29
Course gravel	29	47
Gravel with sand	47	52

Main vain with water 28 30

RECEIVED

DEC 22 2014

WATER RESOURCES DEPT
SALEM, OREGON

Work started June 20 1959. Completed July 6 1959

(13) PUMP:

Manufacturer's Name John Deere
Type: Centrifical H.P. 18

Well Driller's Statement:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME H.W. Panther (Person, firm, or corporation) (Type or print)

Address Rt. 1 Box 324 Salem, Ore.

Driller's well number 5

[Signed] H.W. Panther (Well Driller)

License No. 249 Date July 9, 1959

(USE ADDITIONAL SHEETS IF NECESSARY)