Revised

TRANSFER APPLICATION MAP "TO" LANDS

FOR

JOY LUCK FARM, LLC

T38S, R1W, Sec. 26 W.M.
JACKSON COUNTY, OREGON
CERTIFICATE # 74512 & #48966

RECEIVED

NOV 06 2018

OWRD

LEGEND

|	
SECTION LINE	
1/4 1/4 LINE	
TAX LOT LINE	
ROAD	
CANAL/CREEK	
PROPOSED PIPE	
SECTION CORNER	$\frac{6\ 5}{7\ 8}$
TAX LOT NUMBER	TL 0000
POD	○
POND	
TOTAL ARCRES IRRIGATED PER 1/4 1/4	2.0 NWSW
IRRIGATED LANDS THIS TRANSFER	
IRRIGATED AREA WITH POD CHANGE ONLY CERTIFICATE 74512 PRIORITY 1852	0.1 SENW
IRRIGATED AREA WITH POD CHANGE ONLY CERTIFICATE 74512 PRIORITY 1864	0.1 SENW
IRRIGATED AREA WITH POD CHANGE ONLY CERTIFICATE 74512 PRIORITY 1854	0.1 SENW
IRRIGATED AREA WITH POD CHANGE ONLY CERTIFICATE 74512 PRIORITY 1854 AND CERTIFICATE 48966 PRIORITY 1854	0.1 SWNE
IRRIGATED AREA WITH CHANGE IN POD AND POU CERTIFICATE 74512 PRIORITY 1854 AND 48966 PRIORITY 1854	0.1 NESW
IRRIGATED AREA WITH CHANGE IN POD, POU AND USE CERTIFICATE 74512 PRIORITY 1852	NWSE 0.4

NOTES

1. THIS MAP WAS PREPARED FROM JACKSON COUNTY TAX MAP T38S, R1W, SEC. 26D.

2. THIS MAP IS FOR THE PURPOSE OF IDENTIFYING THE LOCATION OF THE WATER RIGHT ONLY AND HAS NO INTENT TO PROVIDE DIMENSIONS OR LOCATION OF PROPERTY LINES.

3. AUTHORIZED POD FOR CERTIFICATE 74512 AND 48966; 620 FEET SOUTH AND 900 FEET EAST FROM THE SW CORNER OF SECTION 26.

4. PROPOSED POD FOR CERTIFICATE 74512 AND 48966; 2500 FEET NORTH AND 2450 FEET EAST FROM THE SW CORNER OF SECTION 26.

5. ALL LANDS IDENTIFIED IN THIS TRANSFER ARE LOCATED IN DONATION LAND CLAIM 65.

ADKINS
SINCE 1983

CONSULTING
ENGINEERING, LLP

Engineers ▲ Planners ▲ Surveyors

1435 Esplanade Ave · Klamath Falls, Oregon 97601 · (541) 884-4666 · FAX (541) 884-5335
Oregon · California
TRANSFERMAP.DWG

11/06/2018   3372-01

CERTIFIED WATER RIGHT EXAMINER
#88332CWRE
Daniel B. Scalas
April 23, 2015
STATE OF OREGON
RENEWAL 06/30/20

Map labels

TL 3300 TL 3200 TL 3400 TL 800 TL 301 TL 300 TL 302
TALENT CANAL WAGNER CREEK TL 3700 TL 300
TL 500 TL 202 TL 200 TL 1200 TL 400
0.1 SENW PROPOSED POD 0.2 SWNE NWSE 0.5 TL 305
0.4 NESW 3.6 NESW 2.7 NWSE
3.6 NESW TL 1300
TL 704 TL 703 TL 701 TL 705 TL 706 TL 1500 TL 702
TL 1400 0.5 NWSE TL 1600 TL 1700
TL 803 TL 801 TL 800 TL 1800
TL 500 RAPP DITCH
TL 3900 TL 3901 TL 4000 TL 3300 TL 500
27 26 34 35 TL 690 TL 100
TL 200 TL 100 TL 300 EXISTING POD TL 600