

Groundwater Transfer Review Summary Form

Transfer/PA # T- 13295

GW Reviewer Phil Marcy Date Review Completed: 04/14/2020

Summary of Enlargement (Same Source) Review:

☐ The proposed transfer fails to keep the original place of use from receiving water from the same source.

Summary of Injury Review:

☐ The proposed transfer will result in another, existing water right not receiving previously available water to which it is legally entitled or result in significant interference with a surface water source.

Summary of Similarity Review:

☐ The proposed SW-GW transfer doesn't meet the definition of "similarly" as per OAR 690-380-2130.

This is only a summary. Documentation is attached and should be read thoroughly to understand the basis for determinations.



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem, Oregon 97301-1271
(503) 986-0900
www.wrd.state.or.us

Ground Water Review Form:

- ☐ Water Right Transfer
☐ Permit Amendment
☒ GR Modification
☐ Other

Application: T-13295

Applicant Name: Oregon Department of Corrections

Proposed Changes: ☒ POA ☐ APOA ☐ SW→GW ☐ RA
☒ USE ☒ POU ☐ OTHER

Reviewer(s): Phillip I. Marcy

Date of Review: 04/14/2020

Date Reviewed by GW Mgr. and Returned to WRSD: JTI 4/15/2020

The information provided in the application is insufficient to evaluate whether the proposed transfer may be approved because:

- ☐ The water well reports provided with the application do not correspond to the water rights affected by the transfer.
- ☐ The application does not include water well reports or a description of the well construction details sufficient to establish the ground water body developed or proposed to be developed.
- ☐ Other _____

1. Basic description of the changes proposed in this transfer: The applicant proposes to modify character of use, place of use, and authorized point(s) of appropriation on claim GR-692 from well MARI 9613 (listed as MARI 6913 in the application) to three new wells. There are 5 proposed locations for new POAs, but only three will be constructed. The currently authorized use under GR-692 is domestic, and the applicant wishes to use the proposed POAs for irrigation of 26.4 acres.
2. Will the proposed POA develop the same aquifer (source) as the existing authorized POA?
☒ Yes ☐ No Comments: The proposed POA wells are slated to produce from alluvium from 50-120' below land surface (BLS). There is no information regarding seal depth or existence, or perforated intervals on the well log, however the reported depth is likely to produce from sands and gravels, possibly penetrating the uppermost portions of Grande Ronde basalts in the area. The measured water level within the well suggests it is coincident with both alluvial and basalt wells nearby (see attached hydrograph). Considering available water level data in the area, there is no distinctive, consistent difference in heads between the alluvial system, and the upper portions of the Grande Ronde basalt sequence, suggesting that these units are well connected hydraulically.

3. a) Is there more than one source developed under the right (e.g., basalt and alluvium)?
☐ Yes ☒ No Authorized POA (MARI 9613) produces groundwater from alluvium.
- b) If yes, estimate the portion of the right supplied by each of the sources and describe any limitations that will need to be placed on the proposed change (rate, duty, etc.): NA
4. a) Will this proposed change, at its maximum allowed rate of use, likely result in an increase in interference with **another ground water right**?
☐ Yes ☒ No Comments: The proposed POA well locations are not significantly closer to any neighboring groundwater right.
- b) If yes, would this proposed change, at its maximum allowed rate of use, likely result in another groundwater right not receiving the water to which it is legally entitled?
☐ Yes ☒ No If yes, explain: NA
5. a) Will this proposed change, at its maximum allowed rate of use, likely result in an increase in interference with **another surface water source**?
☐ Yes ☒ No Comments: The proposed POA locations are not significantly closer to any surface water source.
- b) If yes, at its maximum allowed rate of use, what is the expected change in degree of interference with any **surface water sources** resulting from the proposed change?
Stream: NA ☐ Minimal ☐ Significant
Stream: NA ☐ Minimal ☐ Significant
Provide context for minimal/significant impact: _____
6. For SW-GW transfers, will the proposed change in point of diversion affect the surface water source similarly (as per OAR 690-380-2130) to the authorized point of diversion specified in the water use subject to transfer?
☐ Yes ☐ No Comments: NA
7. What conditions or other changes in the application are necessary to address any potential issues identified above: All POA wells are proposed to produce groundwater from alluvium, and if this transfer is approved, it shall be conditioned to ensure that when additional wells are constructed, they shall not produce from basalt.
8. Any additional comments: _____





