

To meet State Land Use Consistency Requirements, you must list all county, city, municipal corporation, or tribal governments within whose jurisdiction water will be diverted, conveyed or used.

ENTITY NAME Clackamas Co. Department of Transportation and Development, Planning Division		ADDRESS 150 Beaver Creek Road	
CITY Oregon City	STATE Oregon	ZIP 97045	

Part 5a of 5d – Water Right

Please use a separate Part 5 for each water right being changed. See instructions on page 6, to copy and paste additional Part 5s, or to add additional rows to tables within the form.

CERTIFICATE # 20351

RECEIVED

DEC 28 2020

Description of Water Delivery System

System capacity: **0.77** cubic feet per second (cfs) **OR**
 _____ gallons per minute (gpm)

OWRD

Describe the current water delivery system or the system that was in place at some time within the last five years. Include information on the pumps, canals, pipelines, and sprinklers used to divert, convey, and apply the water at the authorized place of use. Water is diverted from the point of diversion on the stream to capture the live flow from the stream through an 8-inch-diameter Pump Rite L-250 fish screen submerged within the creek. When water is needed, a gate valve connecting the fish screen to an 8-inch PVC pipe is opened, allowing water to gravity flow through the 8-inch PVC pipe connected to a 10-inch PVC pipe running underground from the creek to the pond, thereby using the reservoir as a bulge in the system. Water is pumped from the reservoir at the re-diversion POD using a centrifugal pump with a fish screen. Water from the reservoir is conveyed through a six-inch buried mainline to the place of use.

Table 1. Location of Authorized and Proposed Point(s) of Diversion (POD) or Appropriation (POA)
 (Note: If the POD/POA name is not specified on the certificate, assign it a name or number here.)

*Revised
12-22-2020
DH*

POD/POA Name or Number	Is this POD/POA Authorized on the Certificate or is it Proposed?	If POA, OWRD Well Log ID# (or Well ID Tag # L-___)	Twp		Rng		Sec	¼ ¼		Tax Lot, DLC or Gov't Lot	Measured Distances (from a recognized survey corner)
POD from an unnamed stream	<input checked="" type="checkbox"/> Authorized <input type="checkbox"/> Proposed	NA	3	S	2	E	27	NW	SE	Lot 2	No coordinates given. Re-described per Certificate 47384: 710 feet south and 510 feet east from the Center ¼ corner, Section 27.
Proposed POD from an unnamed stream	<input type="checkbox"/> Authorized <input checked="" type="checkbox"/> Proposed	NA	3	S	2	E	27	NW	SE	Lot 2	940 feet south and 415 feet east from the Center ¼ corner, Section 27
Proposed point of re-diversion from reservoir	<input type="checkbox"/> Authorized <input checked="" type="checkbox"/> Proposed	NA	3	S	2	E	27	NW	SE	Lot 2	240 feet south and 665 feet east from the Center ¼ corner, Section 27