

APPLICATION FOR A CHANGE IN PLACE, CHARACTER AND QUANTITY OF USE.

URBAN GROWTH BOUNDARY  
CITY OF PILOT ROCK, OREGON

The two wells in the NW1/4 of section 9 were used for industrial purposes by United States Gypsum and Oregon Fibre Products. The City of Pilot Rock has acquired lands and wells from these Companies. The City of Pilot Rock intends to change the nature of the use of the two wells from industrial to municipal. They also plan to increase the use of the well in Certificate 38851 by 1.12 cfs. The place of use will be changed from Section 9 to the urban growth boundary of the City of Pilot Rock. Certificate 38851 authorizes the use of 2.22 cfs from the northern well. Certificate 24374 authorizes the use of 1.25 cfs from well 2. The City of Pilot Rock intends to install a 130 horsepower pump on the certificate 38851 well and a 75 horsepower pump on the certificate 24374 well. The City of Pilot Rock intends to connect these two wells to the existing City reservoir tank and the City distribution system. Certificate 24374 was issued pursuant to Permit U-471. Certificate 38851 was issued pursuant to Permit G-3221(U-516).

Cor. monument  
2" iron pipe  
at 90° turn  
in road

Certificate 38851  
Well 280 feet south  
and 950 ft east  
of NW cor. Sec. 9  
2.22 cfs

Applying for  
additional 2.23 cfs.

Certificate 24374  
UMAT 66  
Well 2 located  
S22°28' E 2490 feet  
from NW Cor. Sec. 9  
1.25 cfs

TL 1300  
TL 1500

boundary  
between  
Tax Lots  
1300 & 1500  
East-West  
centerline of  
Section 9

Application G-15586  
Permit G-15336  
Wells 1 and 2  
1.34 cfs

600,000 Gallon  
Storage Tank

Well 2 UMAT 89  
Certificate 23839  
1.00 cfs  
N41°12'13.85"W  
3155.85' from the  
SE Corner of  
Section 17

Well 1 UMAT 90  
Certificate 28952  
1.00 cfs  
957.88' South  
and 1524' West  
from SE corner of  
Section 17

1/4 Cor.  
RR Spike  
centerline  
of road


NE cor.  
SENE  
1/2 IP in  
concrete

City of Pilot Rock Water System  
4 artesian wells  
600,000 gallon storage tank  
Ductile Iron Pipe  
10" 3000'  
8" 32000'  
6" 300'  
5" 4000'  
3" 3000'

Year	Gallons	Pumped	Population
93-94	148,229,000		1540
94-95	118,053,000		1560
95-96	130,028,000		1570
96-97	135,408,000		1585
97-98	137,000,000		1640
98-99	143,000,000		1675
99-00	136,018,000		1700
Use Percent			688 Accounts
Residential			83.1
Commercial			8.1
Industrial			1.9
Public			6.3


Bolt in County  
Road 1375

Survey by:  
CARE 300  
(renew 6-30-03)  
David Haddock  
P. O. Box 1574  
Pendleton, OR 97801  
(541) 278-2174  
June - July, 2001



Horizontal Scale: 1" = 1320'

NOTE:  
The information shown  
on this map is solely for  
Water Rights.  
The data shown does not  
represent ownership  
information.



RECEIVED

SEP 28 2005

WATER RESOURCES DEPT  
SALEM, OREGON

(renew 6-30-07)

SURVEY FOR

CITY OF PILOT ROCK  
& Mr. Steve Draper  
144 Alder Place  
Pilot Rock, OR 97868  
(541) 443-2811

David L. Haddock,  
Surveyor & Engineer

HADDOCK SURVEYING

GPS



TOTAL STATION

F10012