



May 01, 2023

SHAWN BINGAMAN
PO BOX 143
IMBLER, OR 97841

GW

The Department has reviewed the status of your pump test and any requests for extension(s) or exemption(s) for the following permitted well(s). The results are summarized in the following table:

Application	Water Right	Permitted Well	Pumped Well	Test Date	Request Status	Exemption	Well Name
G 16328	Permit: G 15875 *	UNIO0052147	UNIO0052147	06/17/2021	REJECTED	None	EDVALSON WELL/T-10776 (L)

The test(s) was/were rejected for the following reason(s):

- The discharge rate was not held constant.
- The pump was turned off for a portion of the pumping phase.
- The discharge was not measured at the specified time intervals during the pumping phase of the test.
- Water levels were not measured to an accuracy of 0.1 feet.
- Pre-test static water levels or shut in pressures were not measured at the specified intervals.
- Water levels or shut in pressures were not measured at the specified time intervals during the test.
- Water levels or shut in pressures were not measured during the recovery phase of the test.
- Airline measurements are not allowed if the depth to water is less than or equal to 300 feet.
- Airline or sonic measurements were not verified by an electric tape measurement.
- Test data and the supporting documentation were not reported on the Department's forms.
- A graph indicates that the data is probably corrupt.
- Rising water levels during some or all of the pumping phase of the test indicate that the pumping rate was not held constant or that water-level measurements are inaccurate.

The test was rejected for the following reason(s):

- o Water level measurement intervals greater than a tenth of a foot
- o Discharge varies considerably during the test
- o There are no recovery measurements

The well under permit (UNIO 52147) may be eligible for a multi-well exemption, as a well previously authorized under permit G-15875 (UNIO 51479) had an approved pump test, is within five miles, and produces groundwater from the same aquifer system, provided that the two wells have the same owner.

The following pump test related materials can be found on our web site at:

- Pump test administrative rules: <https://secure.sos.state.or.us/oard/displayDivisionRules.action?selectedDivision=3186>
- A booklet explaining pump tests: https://www.oregon.gov/owrd/WRDFormsPDF/pump_test.pdf
- Pump test data forms: https://www.oregon.gov/owrd/WRDFormsPDF/pump_test_coverF.pdf
- Multiple well exemption request: <https://www.oregon.gov/owrd/WRDFormsPDF/pumptestexemptionform.pdf>
- Unreas. burden exemption request: <https://www.oregon.gov/owrd/WRDFormsPDF/pumptestexemptionunreasburden.pdf>

Without an approved pump test, the Department may not be able to process the Claim of Beneficial Use submitted for this permit. The person or persons conducting the test need to be thoroughly familiar with all the test requirements, which are described in the Water Resources Department's administrative rules OAR 690-217.

Please contact me if you have any questions.

Sincerely,

A handwritten signature in black ink, appearing to read "PM", with a stylized flourish extending from the end.

Phil Marcy
971-301-1033
Groundwater Section

cc: GW Pump Test File
cc: Certificates Section/Application File