

Groundwater Application Review Summary Form

Application # G- 18846

Date Re-Review Completed: 2/17/2023

GW Reviewer Travis Brown

Summary of GW Availability and Injury Review:

☐ Groundwater for the proposed use is either over appropriated, will not likely be available in the amounts requested without injury to prior water rights, OR will not likely be available within the capacity of the groundwater resource per Section B of the attached review form.

Summary of Potential for Substantial Interference Review:

☐ There is the potential for substantial interference per Section C of the attached review form.

Summary of Well Construction Assessment:

☐ The well does not appear to meet current well construction standards per Section D of the attached review form. Route through Well Construction and Compliance Section.

This is only a summary. Documentation is attached and should be read thoroughly to understand the basis for determinations and for conditions that may be necessary for a permit (if one is issued).

WATER RESOURCES DEPARTMENT MEMO

TO: Application G- 18846

2/17/2023

FROM: GW: Travis Brown
(Reviewer's Name)

SUBJECT: Scenic Waterway Interference Evaluation

☐ YES The source of appropriation is hydraulically connected to a State Scenic
☒ NO Waterway or its tributaries

☐ YES Use the Scenic Waterway Condition (Condition 7J)
☒ NO

☐ Per ORS 390.835, the Groundwater Section is **able** to calculate ground water interference with surface water that contributes to a Scenic Waterway. The calculated interference is distributed below

☐ Per ORS 390.835, the Groundwater Section is **unable** to calculate ground water interference with surface water that contributes to a scenic waterway; **therefore, the Department is unable to find that there is a preponderance of evidence that the proposed use will measurably reduce the surface water flows necessary to maintain the free-flowing character of a scenic waterway**

DISTRIBUTION OF INTERFERENCE

Calculate the percentage of consumptive use by month and fill in the table below. If interference cannot be calculated, per criteria in 390.835, do not fill in the table but check the "unable" option above, thus informing Water Rights that the Department is unable to make a Preponderance of Evidence finding.

Exercise of this permit is calculated to reduce monthly flows in [Enter] Scenic Waterway by the following amounts expressed as a proportion of the consumptive use by which surface water flow is reduced.

Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec

PUBLIC INTEREST REVIEW FOR GROUNDWATER APPLICATIONS

TO: Water Rights Section Date 2/17/2023
 FROM: Groundwater Section Travis Brown
 Reviewer's Name
 SUBJECT: Application G- 18846 Supersedes review of 8/3/2020
 Date of Review(s)

PUBLIC INTEREST PRESUMPTION; GROUNDWATER

OAR 690-310-130 (1) *The Department shall presume that a proposed groundwater use will ensure the preservation of the public welfare, safety and health as described in ORS 537.525. Department staff review groundwater applications under OAR 690-310-140 to determine whether the presumption is established. OAR 690-310-140 allows the proposed use be modified or conditioned to meet the presumption criteria. This review is based upon available information and agency policies in place at the time of evaluation.*

A. GENERAL INFORMATION: Applicant's Name: Jason Sheng Huang County: Lane

A1. Applicant(s) seek(s) 0.045 cfs from 1 well(s) in the Willamette Basin,
Coast Fork Willamette subbasin

A2. Proposed use Nursery (25 acres) Seasonality: Year-round

A3. Well and aquifer data (attach and number logs for existing wells; mark proposed wells as such under logid):

Well	Logid	Applicant's Well #	Proposed Aquifer*	Proposed Rate(cfs)	Location (T/R-S QQ-Q)	Location, metes and bounds, e.g. 2250' N, 1200' E fr NW cor S 36
1	LANE0019991	1	Bedrock	0.045	19S/02W-04 SWNE	1650 ft S, 1550 ft W of NE cor S 04
2						
3						

* Alluvium, CRB, Bedrock

Well	Well Elev ft msl	First Water ft bls	SWL ft bls	SWL Date	Well Depth (ft)	Seal Interval (ft)	Casing Intervals (ft)	Liner Intervals (ft)	Perforations Or Screens (ft)	Well Yield (gpm)	Draw Down (ft)	Test Type
1	620	100	35	06/09/1972	115	0-50	0-53	-	-	10		A

Use data from application for proposed wells.

A4. **Comments:** _____

A5. ☒ **Provisions of the** Willamette (OAR 690-502) Basin rules relative to the development, classification and/or management of groundwater hydraulically connected to surface water ☐ **are**, or ☒ **are not**, activated by this application. (Not all basin rules contain such provisions.)
 Comments: _____

A6. ☐ **Well(s) #** _____, _____, _____, _____, _____, tap(s) an aquifer limited by an administrative restriction.
 Name of administrative area: _____
 Comments: _____

B. GROUNDWATER AVAILABILITY CONSIDERATIONS, OAR 690-310-130, 400-010, 410-0070

B1. **Based upon available data**, I have determined that groundwater* for the proposed use:

- a. ☐ is over appropriated, ☒ **is not** over appropriated, or ☐ **cannot be determined to be** over appropriated during any period of the proposed use. * This finding is limited to the groundwater portion of the over-appropriation determination as prescribed in OAR 690-310-130;
- b. ☐ **will not** or ☐ **will** likely be available in the amounts requested without injury to prior water rights. * This finding is limited to the groundwater portion of the injury determination as prescribed in OAR 690-310-130;
- c. ☐ **will not** or ☐ **will** likely to be available within the capacity of the groundwater resource; or
- d. ☒ **will, if properly conditioned**, avoid injury to existing groundwater rights or to the groundwater resource:
 - i. ☒ The permit should contain condition #(s) 7C (7-year SWL); Medium Water-Use Reporting;
 - ii. ☐ The permit should be conditioned as indicated in item 2 below.
 - iii. ☐ The permit should contain special condition(s) as indicated in item 3 below;

- B2.
- a. ☐ **Condition** to allow groundwater production from no deeper than _____ ft. below land surface;
 - b. ☐ **Condition** to allow groundwater production from no shallower than _____ ft. below land surface;
 - c. ☐ **Condition** to allow groundwater production only from the _____ groundwater reservoir between approximately _____ ft. and _____ ft. below land surface;
 - d. ☐ **Well reconstruction** is necessary to accomplish one or more of the above conditions. The problems that are likely to occur with this use and without reconstructing are cited below. Without reconstruction, I recommend withholding issuance of the permit until evidence of well reconstruction is filed with the Department and approved by the Groundwater Section.

Describe injury –as related to water availability– that is likely to occur without well reconstruction (interference w/ senior water rights, not within the capacity of the resource, etc): _____

- B3. **Groundwater availability remarks:** Groundwater level records from nearby wells show a stable long-term trend. Likely, the stable trend is a reflection of the efficient hydraulic connection between groundwater and surface water in the area.

The nearest existing groundwater right is almost 1 mile from the proposed POA and there are few other groundwater POAs in the area. Given the distance and low rate of the proposed POA, it is unlikely that the proposed use will cause injury to existing groundwater rights. However, conditions listed in B1(d) are recommended along with standard interference conditions.

C. GROUNDWATER/SURFACE WATER CONSIDERATIONS, OAR 690-09-040**C1. 690-09-040 (1):** Evaluation of aquifer confinement:

Well	Aquifer or Proposed Aquifer	Confined	Unconfined
1	Clastic Sedimentary rocks of Western Cascades	☒	☐
		☐	☐

Basis for aquifer confinement evaluation: Reported SWL is several feet above where First Water was reported; aquifer zones in this type of fractured bedrock generally exhibit confined conditions at depth

C2. 690-09-040 (2) (3): Evaluation of distance to, and hydraulic connection with, surface water sources. All wells located a horizontal distance less than ¼ mile from a surface water source that produce water from an unconfined aquifer shall be assumed to be hydraulically connected to the surface water source. Include in this table any streams located beyond one mile that are evaluated for PSI.

Well	SW #	Surface Water Name	GW Elev ft msl	SW Elev ft msl	Distance (ft)	Hydraulically Connected?			Potential for Subst. Interfer. Assumed?	
						YES	NO	ASSUMED	YES	NO
1	1	Papenfus Creek*	600-610	560-600	2400	☒	☐	☐	☐	☒
1	2	Bear Creek	600-610	500-520	11400	☒	☐	☐	☐	☒
						☐	☐	☐	☐	☐

Basis for aquifer hydraulic connection evaluation: Groundwater elevations are above surface water elevations implying that groundwater is flowing towards, and discharging to surface water

*Papenfus Creek may not be a naturally-perennial stream but was considered under OAR 690-009 because the application proposes year-round use and because Papenfus Creek flows into the Coast Fork Willamette River, which has a year-round instream right that extends to below the confluence with Papenfus Creek and so the creek will be contributing to those flows.

Water Availability Basin the well(s) are located within: COAST FK WILLAMETTE R > WILLAMETTE R - AT MOUTH

C3a. 690-09-040 (4): Evaluation of stream impacts for each well that has been determined or assumed to be **hydraulically connected and less than 1 mile** from a surface water (SW) source. Limit evaluation to instream rights and minimum stream flows that are pertinent to that SW source, not lower SW sources to which the stream under evaluation is tributary. Compare the requested rate against the 1% of 80% *natural* flow for the pertinent Water Availability Basin (WAB). If Q is not distributed by well, use full rate for each well. Any checked ☒ box indicates the well is assumed to have the potential to cause PSI.

Well	SW #	Well < ¼ mile?	Qw > 5 cfs?	Instream Water Right ID	Instream Water Right Q (cfs)	Qw > 1% ISWR?	80% Natural Flow (cfs)	Qw > 1% of 80% Natural Flow?	Interference @ 30 days (%)	Potential for Subst. Interfer. Assumed?
1	1	☐	☐	NA	NA	☐	65.60	☐	<< 25%	☐
		☐	☐			☐		☐		☐

C3b. 690-09-040 (4): Evaluation of stream impacts by total appropriation for all wells determined or assumed to be **hydraulically connected and less than 1 mile** from a surface water source. **Complete only if Q is distributed among wells.** Otherwise same evaluation and limitations apply as in C3a above.

	SW #		Qw > 5 cfs?	Instream Water Right ID	Instream Water Right Q (cfs)	Qw > 1% ISWR?	80% Natural Flow (cfs)	Qw > 1% of 80% Natural Flow?	Interference @ 30 days (%)	Potential for Subst. Interfer. Assumed?
			☐			☐		☐		☐

Comments: Stream-depletion was estimated using the Hunt-1999 stream-depletion model with hydraulic parameter values in a range of expected values for the local aquifer system, informed by nearby pump-test data.

- C4a. **690-09-040 (5):** Estimated impacts on **hydraulically connected surface water sources greater than one mile** as a percentage of the proposed pumping rate. Limit evaluation to the effects that will occur up to one year after pumping begins. This table encompasses the considerations required by 09-040 (5)(a), (b), (c) and (d), which are not included on this form. Use additional sheets if calculated flows from more than one WAB are required.

Non-Distributed Wells													
Well	SW#	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
1	2	%	%	%	%	%	%	%	%	%	%	%	%
Well Q as CFS		0.045	0.045	0.045	0.045	0.045	0.045	0.045	0.045	0.045	0.045	0.045	0.045
Interference CFS		< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05
Distributed Wells													
Well	SW#	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
		%	%	%	%	%	%	%	%	%	%	%	%
Well Q as CFS													
Interference CFS													
(A) = Total Interf.		< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05
(B) = 80 % Nat. Q		955	1080	1080	928	531	216	108	70.5	65.6	86.4	268	761
(C) = 1 % Nat. Q		9.55	10.8	10.8	9.28	5.31	2.16	1.08	0.71	0.66	0.86	2.68	7.61
(D) = (A) > (C)		✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
(E) = (A / B) x 100		< 1 %	< 1 %	< 1 %	< 1 %	< 1 %	< 1 %	< 1 %	< 1 %	< 1 %	< 1 %	< 1 %	< 1 %

(A) = total interference as CFS; (B) = WAB calculated natural flow at 80% exceed. as CFS; (C) = 1% of calculated natural flow at 80% exceed. as CFS; (D) = highlight the checkmark for each month where (A) is greater than (C); (E) = total interference divided by 80% flow as percentage.

Basis for impact evaluation:

The maximum rate of appropriation (0.045 cfs) is less than 1% of the 80%-exceedance flows for each month for the given WAB.

- C4b. **690-09-040 (5) (b)** The potential to impair or detrimentally affect the public interest is to be determined by the Water Rights Section.

- C5. ☐ **If properly conditioned**, the surface water source(s) can be adequately protected from interference, and/or groundwater use under this permit can be regulated if it is found to substantially interfere with surface water:
- ☐ The permit should contain condition #(s) _____;
 - ☐ The permit should contain special condition(s) as indicated in "Remarks" below;

- C6. **SW / GW Remarks and Conditions:** The applicant's proposed POA would be producing from an aquifer system that has been found to be hydraulically-connected to surface water, specifically Bear Creek and Papenfus Creek; the proposed rate and estimated stream-depletion are below the criteria where Potential for Substantial Interference, per OAR 690-009, must be assumed.

References Used:

Herrera, N. B., Burns, E. R., and T. D. Conlon. 2014. *Simulation of Groundwater Flow and the Interaction of Groundwater and Surface Water in the Willamette Basin and Central Willamette Subbasin*, Oregon. USGS Scientific Investigations Report 2014-5136.

Hunt, B. 1999. *Unsteady Stream Depletion from Ground Water Pumping*. Journal of Hydrologic Engineering, Vol 8(1), pp 12-19

McClaghry, J. D., T. J. Wiley, M. L. Ferns, and I. P. Madin. 2010. *Digital Geologic Map of the Southern Willamette Valley, Benton, Lane, Linn, Marion, and Polk Counties, Oregon*. Oregon Dept. of Geology and Mineral Industries. Open File Report O-10-13.

OWRD Well Log Database – Accessed 07/29/2020


D. WELL CONSTRUCTION, OAR 690-200


- D1. **Well #:** _____ **Logid:** _____
- D2. **THE WELL does not appear to meet current well construction standards based upon:**
- a. ☐ review of the well log;
 - b. ☐ field inspection by _____;
 - c. ☐ report of CWRE _____;
 - d. ☐ other: (specify) _____
- D3. **THE WELL construction deficiency or other comment is described as follows:** _____
- D4. ☐ **Route to the Well Construction and Compliance Section for a review of existing well construction.**

Water Availability Tables

Water Availability Analysis Detailed Reports							
COAST FK WILLAMETTE R > WILLAMETTE R - AT MOUTH WILLAMETTE BASIN							
Watershed ID #: 532 (Map) Date: 8/3/2020							
Water Availability as of 8/3/2020							
Exceedance Level: 80% v Time: 2:29 PM							
Water Availability Calculation		Consumptive Uses and Storages		Instream Flow Requirements		Reservations	
Water Rights		Watershed Characteristics					
Water Availability Calculation Monthly Streamflow in Cubic Feet per Second Annual Volume at 50% Exceedance in Acre-Feet							
Month	Natural Stream Flow	Consumptive Uses and Storages	Expected Stream Flow	Reserved Stream Flow	Instream Flow Requirement	Net Water Available	
JAN	955.00	123.00	832.00	0.00	200.00	632.00	
FEB	1,080.00	297.00	783.00	0.00	200.00	583.00	
MAR	1,080.00	467.00	613.00	0.00	200.00	413.00	
APR	928.00	369.00	559.00	0.00	40.00	519.00	
MAY	531.00	236.00	295.00	0.00	40.00	255.00	
JUN	216.00	28.60	187.00	0.00	40.00	147.00	
JUL	108.00	37.30	70.70	0.00	40.00	30.70	
AUG	70.50	33.10	37.40	0.00	40.00	-2.59	
SEP	65.60	24.80	40.80	0.00	40.00	0.84	
OCT	86.40	8.15	78.20	0.00	40.00	38.20	
NOV	268.00	93.70	174.00	0.00	200.00	-25.70	
DEC	761.00	9.05	752.00	0.00	200.00	552.00	
ANN	754,000.00	104,000.00	651,000.00	0.00	77,000.00	574,000.00	

Well Location Map



Annual High Water-Level Measurements in Nearby Wells

Stream-Depletion Model Results


7% PyHunt stream depletion analysis tool

Application type:	G
Application number:	18846
Well number:	1
Stream Number:	1
Pumping rate (cfs):	0.045
Pumping duration (days):	365
Pumping start month number (3=March)	1

Parameter	Symbol	Scenario 1	Scenario 2	Scenario 3	Units
Distance from well to stream	a	2400	2400	2400	ft
Aquifer transmissivity	T	1800	1800	1800	ft ² /day
Aquifer storativity	S	1e-4	1e-4	1e-4	-
Aquitard vertical hydraulic conductivity	Kva	0.001	0.001	0.001	ft/day
Not used		20.0	20.0	20.0	
Aquitard thickness below stream	babs	10	10	10	ft
Not used		0.2	0.2	0.2	
Stream width	ws	5	5	5	ft

Stream depletion for Scenario 2:

Days	10	30	60	90	120	150	180	210	240	270	300	330	360
Depletion (%)	0	0	0	1	1	1	1	1	1	1	1	1	1
Depletion (cfs)	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00



Approved: 

MEMO

To: Kristopher Byrd, Well Construction and Compliance Section Manager
From: Travis Kelly, Well Construction Program Coordinator
Subject: Review of Water Right Application G-18846
Date: August 5, 2020

The attached application was forwarded to the Well Construction and Compliance Section by the Groundwater Section. Mike Thoma reviewed the application. Please see Mike's Groundwater Review and the Well Report.

Applicant's Well #1 (LANE 19991): Based on a review of the Well Report, Applicant's Well #1 does not appear to comply with current minimum well construction standards (See OAR 690 Division 210). The problem is that according to the Water Supply Well Report, only 6 sacks of cement were used for the well seal. A calculated minimum of 11 sacks of cement should have been used. Also, the Well Report indicates that the well head is flush with land surface. In order to meet minimum well construction standards, the well head must be extended so that it is at least one foot above land surface and the well must be resealed with an approved grout to a minimum depth of 50 feet below land surface.

My recommendation is that the Department **not issue** a permit for Applicant's Well #1 unless it is brought into compliance with current minimum well construction standards or information is provided showing that it is in compliance with current minimum well construction standards.

Bringing Applicant's Well #1 into compliance with minimum well construction standards may not satisfy hydraulic connection issues.

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

JUL 6 - 1972

DATE WELL REPORT LANE

STATE OF OREGON

019991

STATE ENGINEER, SALEM, OREGON

within 30 days from the date

of well completion

(Please type or print)

(Do not write above this line)

State Well No. 195/2W-4 RC

State Permit No.

(1) OWNER:

Name CARL JOINSON
Address RR 8 Box 900
PLEASANT HILL, ORE.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒

6" Diam. from 6.2 ft. to 5.3 ft. Gage 25.0
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Blow test 10 gal./min. with 80 ft. drawdown after 1 hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement

Well sealed from land surface to 50 ft.

Diameter of well bore to bottom of seal 10 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 6 sacks

Number of sacks of bentonite used in well seal sacks

Brand name of bentonite

Number of pounds of bentonite per 100 gallons

of water lbs./100 gals.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Lane Driller's well number
SW 1/4 NE 1/4 Section 4 T. 19S R. 2W W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 100 ft.
Static level 35 ft. below land surface. Date 6/9/72
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 115 ft. Depth of completed well 115 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top Soil	0	4'	
Yellow clay & gravel	4'	10'	
Yellow clay	10'	30'	
Yellow clay & gravel	30'	45'	
Blue shale	45'	60'	
Brown shale	60'	63'	
Blue sandstone	63'	115'	35'

Work started 6/8 1972 Completed 6/9 1972

Date well drilling machine moved off of well 6/9 1972

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Frank J. Wilson Date 6/10, 1972
(Drilling Machine Operator)

Drilling Machine Operator's License No. 404

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name W.W. DRILLING (Type or print)

Address 2320 MAIN STREET, ORE

[Signed] Walt Wilson (Water Well Contractor)

Contractor's License No. 268 Date 6/12, 1972

(USE ADDITIONAL SHEETS IF NECESSARY)

SP-45856-119