

Oregon Water Resources Department

Final Order
Limited License Application LL-1957



Appeal Rights

This is a final order in other than contested case. This order is subject to judicial review under ORS 183.484. Any petition for judicial review must be filed within the 60-day time period specified by ORS 183.484(2). Pursuant to ORS 536.075 and OAR 137-004-0080 you may either petition for judicial review or petition the Director for reconsideration of this order. A petition for reconsideration may be granted or denied by the Director, and if no action is taken within 60 days following the date the petition was filed, the petition shall be deemed denied.

Requested Water Use

Applicant: HILLSBORO LANDFILL INC.

Date Submitted: JUNE 26, 2023

Amount: 165 GALLONS PER MINUTE FROM A COMBINATION OF THREE WELLS (0.368 CUBIC FOOT PER SECOND (CFS)) UP TO 26.5 ACRE-FEET, BEING 85 GPM FROM WELL NW-3 (WASH 1130), 76 GPM FROM WELL NW-5 (WASH 9603) AND 111 GPM FROM WELL NW-6 (WASH 9628/WASH 119)

Source: THREE WELLS

Use: ESTABLISH VEGETATION FOR A WILDLIFE CORRIDOR, VISUAL BUFFER AND MITIGATION AREA AT A SOLID WASTE LANDFILL FACILITY

Duration: MARCH 1 THROUGH OCTOBER 31 OF EACH YEAR; FROM MAY 15, 2023 THROUGH OCTOBER 31, 2028

County: WASHINGTON COUNTY

Well Locations: WELL NW-3 (WASH 1130) 1.00S-2.00W-7 NE SE (DLC 68)
WELL NW-5 (WASH 9603) 1.00S-2.00W-7 NE SE (DLC 68)
WELL NW-6 (WASH 9628/WASH 119) 1.00S-2.00W-8 NW SW (DLC 68)

Authorities

The Department may approve a limited license pursuant to its authority under ORS 537.143, 537.144 and OAR 690-340-0030.

ORS 537.143(2) authorizes the Director to revoke the right to use water under a limited license if it causes injury to any water right or a minimum perennial streamflow.

A limited license will not be issued for more than five consecutive years for the same use, as directed by ORS 537.143(8).

Findings of Fact

1. The forms, fees, and map have been submitted, as required by OAR 690-340-0030(1).

2. On July 11, 2023, the Department provided public notice of the application, as required by OAR 690-340-0030(2).
3. The Department has not received public comment related to the possible issuance of the limited license.
4. This limited license request is limited to an area within a single drainage basin, as required by OAR 690-340-0030(3).
5. As part of its review to determine groundwater availability, the Department has determined that groundwater is not determined to be over appropriated, and is available for the requested use. The proposed use will, if properly conditioned, avoid injury to existing groundwater rights or to the groundwater resource. The Department has stipulated conditions pertaining to measurement and reporting, and decline in static water level. A copy of this review is in the file.
6. The Department has determined that Well NW-3 (WASH 1130) does not appear to comply with current minimum well construction standards under OAR 690-210. According to the Water Supply Well Report, Well NW-3 (WASH 1130) does not appear to comply with current minimum well construction standards (See OAR 690 Division 210). The problem is that according to the Water Supply Well Report, the well was sealed with an unapproved grout. In order to meet minimum construction standards, the well must be resealed with an approved grout to a minimum depth of 32 feet below land surface.
7. The Department has determined that the proposed source has not been withdrawn from further appropriation per ORS 538.
8. The Department may not issue a limited license for the same use for more than five consecutive years. (ORS 537.143)(8).
9. In this location, vegetation establishment does not necessarily require continuing irrigation after establishment. This limited license is issued to establish vegetation. The Department may issue a limited license for irrigation if the sole purpose of the use is to provide water necessary to establish a crop for which no further irrigation will be required after the crop is established. ORS 537.143 (6)(a).
10. Pursuant to OAR 690-340-0030(4) and (5), conditions have been added with regard to notice and water-use measurement.
11. Washington County has indicated that the proposed use is compatible with the applicable acknowledged comprehensive land-use plan. A copy of the land use compatibility statement is in the file.
12. The applicant requested a five-year limited license period beginning in 2023. Due to a substantial delay in the groundwater review, the duration of this license is five years from 2024, as further limited below.

Conclusions of Law

The proposed water use will not impair or be detrimental to the public interest pursuant to OAR 690-340-0030(2), as limited in the order below.

Order

Therefore, pursuant to ORS 537.143, ORS 537.144, and OAR 690-340-0030, Application LL-1957 is approved as conditioned below.

1. The authorized use of water under this limited license is as follows:

Amount: 165 GALLONS PER MINUTE FROM A COMBINATION OF TWO WELLS (0.368 CUBIC FOOT PER SECOND (CFS)) UP TO 26.5 ACRE-FEET, BEING 76 GPM FROM WELL NW-5 (WASH 9603) AND 111 GPM FROM WELL NW-6 (WASH 9628/WASH 119)

Source: TWO WELLS

Use: ESTABLISH VEGETATION FOR A WILDLIFE CORRIDOR, VISUAL BUFFER AND MITIGATION AREA AT A SOLID WASTE LANDFILL FACILITY

Duration: MARCH 1 THROUGH OCTOBER 31 OF EACH YEAR; FROM LIMITED LICENSE ISSUE DATE THROUGH FIVE YEARS

Well Locations: WELL NW-5 (WASH 9603) 1.00S-2.00W-7 NE SE (DLC 68)
WELL NW-6 (WASH 9628/WASH 119) 1.00S-2.00W-8 NW SW (DLC 68)

2. The licensee shall give notice to the Watermaster in the district where use is to occur not less than 15 days or more than 60 days in advance of using the water under the limited license. The notice shall include the location of the diversion, the quantity of water to be diverted, and the intended use and place of use. In the case of this application, this order serves as the notice described above.
3. Before water use may begin under this limited license, the licensee shall install a totalizing flow meter at each point of appropriation. The totalizing flow meter must be installed and maintained in good working order.
4. The licensee shall maintain a record of all water use, including the total number of hours of pumping, the total quantity pumped, and the categories of beneficial use to which the water is applied. During the period of the limited license, the record of use shall be submitted to the Department annually, and shall be submitted to the Watermaster upon request.
5. Static Water Level Measurement:

The Department requires the water user to obtain, from a qualified individual (see below), and report annual static water levels for each well on the limited license. The static water level shall be measured in the month of March. Reports shall be submitted to the Department within 30 days of measurement.

The licensee shall report an initial March static water-level measurement once well construction is complete and annual measurements thereafter. Annual measurements are required whether or not the well is used. The first annual measurement will establish a reference level against which future measurements will be compared. However, the Director may establish the reference level based on an analysis of other water-level data. The Director may require the user to obtain and report additional water levels each year if more data are needed to evaluate the aquifer system.

All measurements shall be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed well constructor or pump installer licensed by the Construction Contractors Board. Measurements shall be submitted on forms provided by, or specified by, the Department. Measurements shall be made with equipment that is accurate to at least the standards specified in OAR 690-217-0045. The Department requires the individual performing the measurement to:

- A. Associate each measurement with an owner's well name or number and a Department well log ID; and
- B. Report water levels to at least the nearest tenth of a foot as depth-to-water below ground surface; and
- C. Specify the method of measurement; and
- D. Certify the accuracy of all measurements and calculations reported to the Department.

The water user shall discontinue use of, or reduce the rate or volume of withdrawal from, the well(s) if any of the following events occur:

- A. Annual water-level measurements reveal an average water-level decline of three or more feet per year for five consecutive years; or
- B. Annual water-level measurements reveal a water-level decline of 15 or more feet in fewer than five consecutive years; or
- C. Annual water-level measurements reveal a water-level decline of 25 or more feet; or
- D. Hydraulic interference leads to a decline of 25 or more feet in any neighboring well.


The period of restricted use shall continue until the water level rises above the decline level which triggered the action or the Department determines, based on the licensee's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or causing substantial interference with water rights. The water user shall not allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this limited license. If more than one well is involved, the water user may submit an alternative measurement and reporting plan for review and approval by the Department.

6. The Director may revoke the right to use water for any reason described in ORS 537.143(2), and OAR 690-340-0030(6). Such revocation may be prompted by field regulatory activities or by any other information.
7. Use of water under a limited license shall not have priority over any water right exercised according to a permit or certificate, and shall be subordinate to all other authorized uses that rely upon the same source.
8. By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

9. A copy of this limited license shall be kept at the place of use, and be made available for inspection by the Watermaster or other state authority.

NOTE: This water-use authorization is temporary. Applicants are advised that issuance of this final order does not guarantee that any permit for the authorized use will be issued in the future; any investments should be made with that in mind.

Issued AUG 02 2024



Katherine Ratcliffe
Water Rights Section Manager, *for*
Ivan Gall, Director
Oregon Water Resources Department

cc: Jacob W. Constans, District 18 Watermaster
Western, ODFW
Lower Willamette, DEQ
Summit Water Resources, LLC, Attn: Theodore Ressler
Surface Water Section
File

If you need further assistance, please contact the Water Rights Section at the address, phone number, or fax number below. When contacting the Department, be sure to reference your limited license number for fastest service.

Remember, this limited license does not provide a secure source of water. Water use can be revoked at any time. Such revocation may be prompted by field regulatory activities or many other reasons.

Water Rights Section
Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem OR 97301-1271
Phone: (503) 979-9895 Fax: (503) 986-0901