



## Water Right Application Initial Review

October 4, 2024

HOMES FOR GOOD  
STEVE OCHS  
100 WEST 13TH AVE  
EUGENE OR 97404

Reference: Application G-19392

This document is to inform you of the preliminary analysis of the water-use permit application and to describe your options. In determining whether an application may be approved, the Water Resources Department (Department) must consider the factors listed below, all of which must be favorable to the proposed use if it is to be allowed. Based on the information supplied, the Department has made the following preliminary determinations:

### **Preliminary Determinations under Oregon Administrative Rule (OAR) 690-310-0080:**

1. Application G-19392 proposes the appropriation of 0.0125 cubic foot per second (CFS), further limited to 2.5 acre-feet (AF) annually, of water from Well 1 (LANE 79123) in McKenzie River Basin for irrigation of 1.0 acre from April 15 through October 15 of each year.
2. The proposed use is not prohibited by law or rule except where otherwise noted below.
3. Irrigation from groundwater is allowed under the Willamette Basin Program (OAR 690-502-0160(2)); however, the Department has determined that Well 1 (LANE 79123) will produce groundwater from unconfined alluvium within a quarter mile of the banks of a surface water source and is presumed to be hydraulically connected to the surface water. Under OAR 690-502-0240 such hydraulically connected groundwater shall be classified the same as the surface water source. Irrigation is **not** a classified use of surface water under OAR 690-502-0080(1)(e) of the Willamette Basin Program; therefore, groundwater for the proposed use is not allowed.

**Please note:** Applications are evaluated using the rules in effect at the time the application is accepted as complete. To view the rules relevant for this application, please visit: <https://secure.sos.state.or.us/oard/displayCompilations> and navigate to Chapter 690 (Water Resources Department).

However, OAR 690-502-0240 also states that notwithstanding such classification, permits may be issued for the use of water from a well in an unconfined aquifer that is hydraulically connected to surface water, within a quarter mile of a stream, provided that surface water impacts are mitigated through storage releases. Please see the **Additional Information Opportunity** section below for details.

4. The proposed groundwater use is not within a designated critical groundwater area. OAR 690-310-0080(1)(a).
5. An assessment of groundwater availability has been completed by the Department. A copy of this assessment is in the file and can be viewed on the Department's website. Groundwater for the proposed use is not over-appropriated. OAR 690-310-0080(1)(b); OAR 690-300-0010(57).
6. The Department has determined that the proposed groundwater use will have the potential for substantial interference (PSI) with McKenzie River, an unnamed western tributary to McKenzie River, and an unnamed middle tributary to McKenzie River. OAR 690-009-0040. Therefore, in accordance with OAR 690-300-0010(57)(a) and OAR 690-400-0010(11)(a)(B), surface water availability must be considered. During the period of use requested, surface water is available (at an 80% exceedance probability) from January 1 through December 31 of each year. Therefore, water is available for the proposed use. OAR 690-310-0080(1)(b); OAR 690-300-0010(57); OAR 690-410-0070.
7. If properly conditioned (and if authorized), the proposed use of groundwater will not injure other water rights.
8. The proposed use is not located within or above any state or federal scenic waterway.
9. Because this application will have an impact on surface water flows where sensitive, threatened, or endangered (STE) fish species may be present, this application will be reviewed by the Oregon Department of Fish and Wildlife and the Oregon Department of Environmental Quality. This review may cause your application to be limited, conditioned, or denied. Depending on the proposed use, you may be required to mitigate for potential impacts identified in the review. See the **Division 33 Review** section below for more information.
10. Documentation has been submitted from the relevant land-use planning jurisdiction that indicates an approved land-use decision has been obtained, and that either no administrative appeals were received, or all such appeals have concluded.

Summary of Preliminary Determinations
<b>The appropriation of 0.0125 CFS, further limited to 2.5 AF annually, of water from Well 1 (LANE 79123) in McKenzie River Basin for irrigation of 1.0 acre from April 15 through October 15 of each year is not allowable.</b>

### **Additional Information Opportunity:**

Based on Preliminary Determination #3 above, it is unlikely that a permit will be issued unless surface water impacts are mitigated through storage releases. If you would like to pursue a permit under this application, a stored water contract may satisfy the mitigation requirement under OAR 690-502-0240. It may be possible to obtain a stored water contract through purchase of water stored in the Willamette River Basin Project reservoirs from the U.S. Bureau of Reclamation (BOR). For more information about contracting with the BOR for release of stored water, please reach out to the BOR Pacific Northwest Regional Office at 208-378-6231 or pninfo@usbr.gov.

If you would like to pursue this opportunity, **please inform the Water Resources Department no later than November 7, 2024**. Due to the length of time it can take to obtain a stored water contract, please consider placing your application on an administrative hold. You may request an administrative hold for up to an additional 180 days. You must submit the request in writing, stating how much more time you will need and why you need additional time. If an administrative hold is granted, your application will not be processed further until the requested information is received or the extended deadline has passed.

If we do not receive the information requested above or a request for an administrative hold by this date, the Department will likely proceed with a Proposed Final Order recommending denial of the application.

### **Public Comment:**

Public interest issues and/or public comments will be addressed as the Department prepares a Proposed Final Order. If significant public interest issues are identified, they could have an impact on the eventual outcome of the application.

### **Division 33 Review:**

The Department's Division 33 administrative rules (OAR 690-033) establish additional procedures and standards to aid the Department in determining whether a proposed use will impair or be detrimental to the public interest with regard to STE fish species. This Initial Review does not address the potential impact that your proposed use may have on these species.

You may be required to mitigate for potential impacts identified in the Division 33 review process. Mitigation is often complicated, time consuming, and expensive, and may include, but is not limited to, actions such as replacing the proposed amount of water within the impacted reach through purchasing or transferring an existing water right. Following the Initial Review, you will be notified if mitigation is required due to impacts to STE fish species.

If you choose to pursue mitigation, you will likely need to place your application on administrative hold in order to explore options. There will be an additional fee of \$790 required with any mitigation proposal submitted.

**At this time, you must decide whether to proceed or to withdraw the application.**

- To Proceed - If you choose to proceed with the application, you do not have to notify the Department. The application will be placed on the Department's Public Notice to allow others the opportunity to comment. After the comment period the Department will complete a public interest review and issue a Proposed Final Order.
- To Withdraw - You may withdraw the application and receive a refund (minus a \$310 processing fee). You must notify the Department **in writing** by **October 18, 2024**. For your convenience you may use the enclosed "STOP PROCESSING" form.

**Although it is unlikely that a permit will be issued, if the Department's findings change and a permit is issued, it will likely include the following conditions:**

1. Construction of the well shall begin within five years of the date of permit issuance. The deadline to begin construction may not be extended. This permit is subject to cancellation proceedings if the construction deadline to begin is missed.
2. If the number, location, source, or construction of any well deviates from that proposed in the permit application or required by permit conditions, this permit may not be valid, unless the Department authorizes the change in writing.
3. **Water Use Measurement, Recording, and Reporting:**
  - A. Before water use may begin under this permit, the permittee shall install a totalizing flow meter at each point of appropriation. The permittee shall maintain the device in good working order.
  - B. The permittee shall allow the watermaster access to the device; provided however, where any device is located within a private structure, the watermaster shall request access upon reasonable notice.
  - C. The Director may require the permittee to keep and maintain a record of the volume of water diverted, and may require the permittee to report water use on a periodic schedule as established by the Director. In addition, the Director may require the permittee to report general water-use information, the periods of water use and the place and nature of use of water under the permit.
  - D. The Director may provide an opportunity for the permittee to submit alternative measuring and reporting procedures for review and approval.

#### 4. Groundwater Level Measurement, Reporting, and Shut-Off Condition:

For each well on this authorization, beginning on the permit signature date for existing wells or in the year well construction is completed for new wells, and each year thereafter, the permit holder must report a static water-level measurement ("measurement") taken in March. The measurement is required whether the well is used or not. If pumping is to commence following completion of the well and prior to the next March, then a measurement must be made at least one week following well completion and before pumping commences.

Measurements must be properly reported within 30 days of measurement using forms specified by the Department. A measurement will be properly reported if the submission includes all required information as listed in the document attached. Measurements must be made with equipment that is accurate to the standards specified in Oregon Administrative Rule (OAR) 690-217-0045.

Measurements must be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed land surveyor, licensed well constructor, pump installer licensed by the Construction Contractors Board, or Department staff. The Department is not responsible for regular measurement of the static water level, but Department staff may measure the well during the normal course of groundwater level monitoring or to confirm the submitted measurement(s).

For each well on this permit, the Department will establish a reference groundwater level using the best available data. The reference level is intended to represent the highest elevation (shallowest depth) static water level that has been measured or can be reasonably estimated to have existed within each well at any time before its reference level is set. If Annual High Water Levels have been increased measurably by human activity, then the Department may set a different reference level using best available information. If the permit holder fails to measure and report the static water level within 12 months of permit issuance, or of completion of the well(s), then Department staff will estimate the static water level using available data, including measurements in surrounding wells. In case the permit is amended or the subsequent certificate is transferred, the Department may establish a new reference level for any new or additional wells under new permits or certificates issued under this right. The reference level for a new or additional well should reflect the highest static water level in that well or, if that measurement occurred after the time represented by the original reference level, then the water level that would have been measured in that well, if the well existed and was measured at the time represented by the original reference level.

All water use authorized under this permit must immediately stop if any of the following occur:

- A. Any annual high elevation static groundwater level in any well on this permit declines 25 or more feet below the reference level for that well, or
- B. Groundwater levels are not measured and properly reported as specified above for any completed well that is authorized on the permit for two consecutive years, or
- C. Hydraulic interference contributes to a decline of 25 or more feet in any neighboring well with senior priority, at any time during the year.

The Department will determine when any of the above conditions have occurred and may order the permit holder to stop all water use under this permit. The permit holder is also responsible for stopping all water use if they become aware that any of the conditions have occurred, even without notice from the Department. Following such a stop, water use under this permit will not be allowed and may only resume once the permit holder receives notice from the Department. If the permit holder fails to stop use, then the Department may take control of the controlling works of any wells authorized under this permit and may reduce the amount of groundwater pumped until the unlawful use is eliminated.

The permit holder acknowledges that that one or more of the conditions requiring stoppage of use may occur prior to any use of any well on this permit.

The Department may allow the permit holder to pause annual water level measurement and reporting requirements from some of the permitted wells if measurements from those wells are redundant with other data being collected by the Department. The permit holder must receive written notification of such an allowance before stopping measurements. If this happens, the Department may reinstate the measurement requirements at any time.

**5. Groundwater production shall be only from the shallow, unconsolidated alluvium groundwater reservoir.**

**6. Well Identification Tag:**

Prior to using water from any well listed on this permit, the permittee shall ensure that the well has been assigned an OWRD Well Identification Number (Well ID tag), which shall be permanently attached to the well. The Well ID shall be used as a reference in any correspondence regarding the well, including any reports of water use, water level, or pump test data.

The water source identified in the application may be affected by an Agricultural Water Quality Management Area Plan. These plans are developed by the Oregon Department of Agriculture (ODA) with the cooperation of local landowners and other interested stakeholders, and help to ensure that current and new appropriations of water are done in a way that does not adversely harm the environment. You are encouraged to explore ODA's website at [www.oregon.gov/ODA](http://www.oregon.gov/ODA) to learn more about the plans and how they may affect the proposed water use.

**For Further Information:**

Feel free to contact me at Lucinda.R.Vranizan@water.oregon.gov or 971-375-2256 if you have any questions regarding the contents of this letter or the application. Please include the application number in all correspondence. General questions about water rights and water use permits should be directed to our customer service staff at 503-986-0900. When corresponding by mail, please use this address: Lucinda Vranizan, Oregon Water Resources Department, 725 Summer St NE Ste A, Salem OR 97301-1266. Our fax number is 503-986-0901.

Sincerely,

*Lucinda Vranizan*

Lucinda Vranizan  
Water Right Application Specialist  
Oregon Water Resources Department

Enclosures:   Application Process Description  
                  Stop Processing Request Form

G-19392  
WAB: 529  
Proposed to Deny

# APPLICATION FACT SHEET

Application File Number: G-19392

Applicant: HOMES FOR GOOD AND STEVE OCHS

County: LANE

Watermaster: LANAYA F. BLAKELY, #2, NWR

Priority Date: SEPTEMBER 18, 2023

Source: WELL 1 (LANE 79123) IN MCKENZIE RIVER BASIN

Use: IRRIGATION OF 1.0 ACRE

Quantity: 0.0125 CUBIC FOOT PER SECOND, FURTHER LIMITED TO 2.5 ACRE-FEET ANNUALLY

Period of Use: APRIL 15 THROUGH OCTOBER 15

Basin Name & Number: WILLAMETTE, #2

WAB: MCKENZIE R > WILLAMETTE R - AB BEAR CR

Well Location(s):

Twp	Rng	Mer	Sec	Q-Q	Measured Distances
16 S	4 E	WM	22	SW SE	388 FEET NORTH AND 1038 FEET EAST FROM S1/4 CORNER, SECTION 22

Places of Use:

Twp	Rng	Mer	Sec	Q-Q	Acres
16 S	4 E	WM	22	SW SE	0.995
16 S	4 E	WM	27	NW NE	0.005

**PUBLIC NOTICE DATE: October 8, 2024**

**14 DAY STOP PROCESSING DEADLINE DATE: October 18, 2024**

**30 DAY COMMENT DEADLINE DATE: November 7, 2024**



## **APPLICATION PROCESS DESCRIPTION FOR GROUNDWATER, SURFACE WATER AND REGULAR RESERVOIR APPLICATIONS**

In order to use the waters of Oregon, an application must be submitted and a permit obtained from the Water Resources Department. The water must be used for beneficial purpose without waste. For more information about water right topics, weekly public notice, forms and fees please visit our website at: [www.oregon.gov/owrd](http://www.oregon.gov/owrd)

### **1. Pre-application considerations**

- Follow instructions in the application packet.
- If you have questions about completing an application or would like to arrange a pre-application conference contact the Department's Water Rights Customer Service Group at (503) 986-0900.

### **2. Application filing**

- Application with fee is received by the Department.
- Department determines completeness of application.
- If use is not allowed by statute (ORS 538), the application and fees are returned to the applicant.
- An incomplete application and fees are returned to the applicant.
- Only a complete application receives a tentative priority date, is assigned a caseworker, and moves forward for processing.

### **3. Initial Review (IR)**

- Caseworker reviews application by considering basin plans, water availability, statutory restrictions, and all other appropriate factors.
- Caseworker sends IR report to Applicant.
- Four days after date of the IR, it is included in Department's weekly Public Notice.
- Public comments must be submitted within 30 days after the Public Notice.

### **4. Proposed Final Order (PFO)**

- Caseworker evaluates application against required criteria and develops draft permit, if appropriate.
- PFO includes instructions for filing of protests.
- Caseworker considers public comments and mails PFO to Applicant.
- The PFO is included in Department's weekly Public Notice.
- Public protests to the PFO must be submitted within 45 days after the Public Notice.

### **5. Final Order (FO)**

- If no protest is filed, Final Order is issued.

#### ***The protest process***

If one or more protests are filed, the process consists of:

- settlement discussion;
- contested case hearing;
- Proposed Order;
- period of time to file exceptions; or
- possible hearing by Water Resources Commission.
- Final Order is issued.

### **Permit holder responsibilities**

- Comply with all water use conditions of the permit.
- Advise Department of address change or assignment to new permit holder.
- If need arises, request extension of time or authorize cancellation of permit.
- Submit timely claim of beneficial use (COBU) to the Department.
- Most permits require COBU to be prepared by a Certified Water Right Examiner.
- Permits may be canceled by the permit holder or by the Department for failure to comply with or one or more permit conditions.

## STOP PROCESSING REQUEST FORM

### FOR GROUNDWATER, SURFACE WATER AND REGULAR RESERVOIR APPLICATIONS

---

- Stop processing deadline is within 14 days of Initial Review.

Applicant notification to withdraw Water Right Application **G-19392**.

After reviewing the Initial Review for my application, I request that processing be stopped, and fees be refunded (minus a \$310 processing fee). I understand that without a valid permit, I may not legally use the water as requested in my application.

Signature \_\_\_\_\_ Date \_\_\_\_\_

Signature \_\_\_\_\_ Date \_\_\_\_\_

Under ORS 537.150(5) and 537.620(5), timely submission of this request authorizes that the water right application process be stopped, and all filing fees (except \$310 processing fee) be returned.

- This notice must be received by the Water Resources Department no later than:

**October 18, 2024**

- Return the notice to:

OWRD, Water Right Services Division  
STOP PROCESSING  
725 Summer Street, NE - Suite A  
Salem, OR 97301-1266

---