



Water Right Application Initial Review

October 18, 2024

RICHARD LAFAVE
CAREY LAFAVE
73946 RIMROCK LANE
IMNAHA OR 97842

Reference: Application G-19267

This document is to inform you of the preliminary analysis of the water-use permit application and to describe your options. In determining whether an application may be approved, the Water Resources Department (Department) must consider the factors listed below, all of which must be favorable to the proposed use if it is to be allowed. Based on the information supplied, the Department has made the following preliminary determinations:

Preliminary Determinations under Oregon Administrative Rule (OAR) 690-310-0080:

1. Application G-19267 proposes the appropriation of 0.05 cubic foot per second (CFS), further limited to 10.0 acre-feet (AF) annually, of water from a well in Imnaha River Basin, being 9.0 AF for irrigation of 3.0 acres, and commercial use from January 1 through December 31 of each year.
2. The proposed use is not prohibited by law or rule except where otherwise noted below.
3. Irrigation and commercial uses are allowed under the Grande Ronde Basin Program (OAR 690-508-0050(1)(a)).
4. The proposed groundwater use is not within a designated critical groundwater area. OAR 690-310-0080(1)(a).

Please note: Applications are evaluated using the rules in effect at the time the application is accepted as complete. To view the rules relevant for this application, please visit: <https://secure.sos.state.or.us/oard/displayCompilations> and navigate to Chapter 690 (Water Resources Department).

5. An assessment of groundwater availability has been completed by the Department. A copy of this assessment is in the file and can be viewed on the Department's website. Groundwater for the proposed use is not over-appropriated. In addition, the Department has determined that the proposed groundwater use will not have the potential for substantial interference (PSI) with surface water. OAR 690-009-0040. Therefore, water is available for the proposed use. OAR 690-310-0080(1)(b); OAR 690-300-0010(57).
6. If properly conditioned (and if authorized), the proposed use of groundwater will not injure other water rights.
7. The proposed use is not located within or above any state or federal scenic waterway.
8. Documentation has been submitted from the relevant land-use planning jurisdiction that indicates the proposed use is allowed outright.
9. The application proposes a diversion rate for irrigation that is in excess of the general basin-wide standard, and the applicant has not submitted information that demonstrates the need for the higher rate for the Department to consider. In the absence of other information, if the application is approved, the rate allowed for irrigation will be limited to 0.0375 CFS (or 1/80th of one CFS per acre).
10. The standard irrigation season in the Imnaha River Basin is limited to April 15 through October 15 of each year. The period of use will be limited to April 15 through October 15 on any permit that may be issued under this application.
11. See **Additional Information Required** section below for deficiencies with the application.

Summary of Preliminary Determinations
The appropriation of 0.05 CFS of water from a well in Imnaha River Basin, further limited to 10.0 AF annually, being 0.0375 CFS further limited to 9.0 AF annually for irrigation of 3.0 acres from April 15 through October 15, and commercial use from January 1 through December 31 of each year, may be allowable. See <u>Additional Information Required</u> section below for more details.

Additional Information Required:

Additional information is required to process your application prior to issuance of any Proposed Final Order that may recommend approval. Please provide the following:

- A. The map submitted does not meet the requirements of OAR 690-310-0050(4)(c). The map submitted did not identify the location of the commercial use. Please provide a map that identifies the location of the proposed commercial use.

Please submit this information no later than November 21, 2024. If you are unable to submit the information listed above by this date, you may request an administrative hold for up to an additional 180 days. You must submit the request in writing, stating how much more time is needed and why you

need additional time. If an administrative hold is granted, your application will not be processed further until the requested information is received or the extended deadline has passed.

If we do not receive the information requested above or a request for an administrative hold by the above date, the Department may reject the application.

Public Comment:

Public interest issues and/or public comments will be addressed as the Department prepares a Proposed Final Order. If significant public interest issues are identified, they could have an impact on the eventual outcome of the application.

At this time, you must decide whether to proceed or to withdraw the application.

- **To Proceed** - If you choose to proceed with the application, you do not have to notify the Department. The application will be placed on the Department's Public Notice to allow others the opportunity to comment. After the comment period the Department will complete a public interest review and issue a Proposed Final Order.
- **To Withdraw** - You may withdraw the application and receive a refund (minus a \$310 processing fee). You must notify the Department **in writing** by **November 1, 2024**. For your convenience you may use the enclosed "STOP PROCESSING" form.

If a permit is issued, it will likely include the following conditions:

1. Construction of the well shall begin within five years of the date of permit issuance. The deadline to begin construction may not be extended. This permit is subject to cancellation proceedings if the construction deadline to begin is missed.
2. If the number, location, source, or construction of any well deviates from that proposed in the permit application or required by permit conditions, this permit may not be valid, unless the Department authorizes the change in writing.
3. **Water Use Measurement, Recording, and Reporting:**
 - A. The Director may require the permittee to install a totalizing flow meter at each point of appropriation. If the Director notifies the permittee to install a measuring device, the permittee shall install such device within the period stated in the notice. Once installed, the permittee shall maintain the device in good working order, and shall allow the watermaster access to the device.
 - B. The Director may require the permittee to keep and maintain a record of the volume of water diverted, and may require the permittee to report water-use on a periodic schedule as established by the Director. In addition, the Director may require the permittee to report

general water-use information, the periods of water use and the place and nature of use of water under the permit.

- C. The Director may provide an opportunity for the permittee to submit alternative measuring and reporting procedures for review and approval.

4. Groundwater Level Measurement, Reporting, and Shut-Off Condition:

For each well on this authorization, beginning on the permit signature date for existing wells or in the year well construction is completed for new wells, and each year thereafter, the permit holder must report a static water-level measurement ("measurement") taken in March. The measurement is required whether the well is used or not. If pumping is to commence following completion of the well and prior to the next March, then a measurement must be made at least one week following well completion and before pumping commences.

Measurements must be properly reported within 30 days of measurement using forms specified by the Department. A measurement will be properly reported if the submission includes all required information as listed in the document attached. Measurements must be made with equipment that is accurate to the standards specified in Oregon Administrative Rule (OAR) 690-217-0045.

Measurements must be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed land surveyor, licensed well constructor, pump installer licensed by the Construction Contractors Board, or Department staff. The Department is not responsible for regular measurement of the static water level, but Department staff may measure the well during the normal course of groundwater level monitoring or to confirm the submitted measurement(s).

For each well on this permit, the Department will establish a reference groundwater level using the best available data. The reference level is intended to represent the highest elevation (shallowest depth) static water level that has been measured or can be reasonably estimated to have existed within each well at any time before its reference level is set. If Annual High Water Levels have been increased measurably by human activity, then the Department may set a different reference level using best available information. If the permit holder fails to measure and report the static water level within 12 months of permit issuance, or of completion of the well(s), then Department staff will estimate the static water level using available data, including measurements in surrounding wells. In case the permit is amended or the subsequent certificate is transferred, the Department may establish a new reference level for any new or additional wells under new permits or certificates issued under this right. The reference level for a new or additional well should reflect the highest static water level in that well or, if that measurement occurred after the time represented by the original reference level, then the water level that would have been measured in that well, if the well existed and was measured at the time represented by the original reference level.

All water use authorized under this permit must immediately stop if any of the following occur:

- A. Any annual high elevation static groundwater level in any well on this permit declines 25 or more feet below the reference level for that well, or

- B. Groundwater levels are not measured and properly reported as specified above for any completed well that is authorized on the permit for two consecutive years, or
- C. Hydraulic interference contributes to a decline of 25 or more feet in any neighboring well with senior priority, at any time during the year.

The Department will determine when any of the above conditions have occurred and may order the permit holder to stop all water use under this permit. The permit holder is also responsible for stopping all water use if they become aware that any of the conditions have occurred, even without notice from the Department. Following such a stop, water use under this permit will not be allowed and may only resume once the permit holder receives notice from the Department. If the permit holder fails to stop use, then the Department may take control of the controlling works of any wells authorized under this permit and may reduce the amount of groundwater pumped until the unlawful use is eliminated.

The permit holder acknowledges that that one or more of the conditions requiring stoppage of use may occur prior to any use of any well on this permit.

The Department may allow the permit holder to pause annual water level measurement and reporting requirements from some of the permitted wells if measurements from those wells are redundant with other data being collected by the Department. The permit holder must receive written notification of such an allowance before stopping measurements. If this happens, the Department may reinstate the measurement requirements at any time.

- 5. **Groundwater production shall be from no shallower than 40 feet below land surface.**
- 6. **Special Condition:**

The proposed well shall be constructed to produce from water-bearing zones below an elevation of 1,765 feet above mean sea level, or 40 feet below land surface to avoid hydraulic connection with the nearby Imnaha River. This will require continuous casing and seal into competent basalt overlying the water-bearing zone.

- 7. **Well Identification Tag:**

Prior to using water from any well listed on this permit, the permittee shall ensure that the well has been assigned an OWRD Well Identification Number (Well ID tag), which shall be permanently attached to the well. The Well ID shall be used as a reference in any correspondence regarding the well, including any reports of water use, water level, or pump test data.

The water source identified in the application may be affected by an Agricultural Water Quality Management Area Plan. These plans are developed by the Oregon Department of Agriculture (ODA) with the cooperation of local landowners and other interested stakeholders, and help to ensure that current and new appropriations of water are done in a way that does not adversely harm the environment. You are encouraged to explore ODA's website at www.oregon.gov/ODA to learn more about the plans and how they may affect the proposed water use.

For Further Information:

Feel free to contact me at Lucinda.R.Vranizan@water.oregon.gov or 971-375-2256 if you have any questions regarding the contents of this letter or the application. Please include the application number in all correspondence. General questions about water rights and water use permits should be directed to our customer service staff at 503-986-0900. When corresponding by mail, please use this address: Lucinda Vranizan, Oregon Water Resources Department, 725 Summer St NE Ste A, Salem OR 97301-1266. Our fax number is 503-986-0901.

Sincerely,

Lucinda Vranizan

Lucinda Vranizan
Water Right Application Specialist
Oregon Water Resources Department

Enclosures: Application Process Description
 Stop Processing Request Form

G-19267
WAB: No PSI
Proposed to Approve

APPLICATION FACT SHEET

Application File Number: G-19267

Applicant: RICHARD LAFAVE AND CAREY LAFAVE

County: WALLOWA

Watermaster: DAVID D. BATES, #7, ER

Priority Date: JUNE 21, 2022

Source: A WELL IN IMNAHA RIVER BASIN

Use: IRRIGATION OF 3.0 ACRES AND COMMERCIAL USE

Quantity: 0.05 CUBIC FOOT PER SECOND, FURTHER LIMITED TO 10.0 ACRE-FEET ANNUALLY

Period of Use: JANUARY 1 THROUGH DECEMBER 31

Basin Name & Number: GRANDE RONDE, #8

Well Location(s):

Twp	Rng	Mer	Sec	Q-Q	Measured Distances
2 N	48 E	WM	20	SW SE	762 FEET NORTH AND 341 FEET EAST FROM S1/4 CORNER, SECTION 20

Places of Use:

Irrigation Use					
Twp	Rng	Mer	Sec	Q-Q	Acres
2 N	48 E	WM	20	SW SE	3.0

Commercial Use				
Twp	Rng	Mer	Sec	Q-Q
2 N	48 E	WM	20	SW SE

PUBLIC NOTICE DATE: October 22, 2024

14 DAY STOP PROCESSING DEADLINE DATE: November 1, 2024

30 DAY COMMENT DEADLINE DATE: November 21, 2024

APPLICATION PROCESS DESCRIPTION FOR GROUNDWATER, SURFACE WATER AND REGULAR RESERVOIR APPLICATIONS

In order to use the waters of Oregon, an application must be submitted and a permit obtained from the Water Resources Department. The water must be used for beneficial purpose without waste. For more information about water right topics, weekly public notice, forms and fees please visit our website at: www.oregon.gov/owrd

1. Pre-application considerations

- Follow instructions in the application packet.
- If you have questions about completing an application or would like to arrange a pre-application conference contact the Department's Water Rights Customer Service Group at (503) 986-0900.

2. Application filing

- Application with fee is received by the Department.
- Department determines completeness of application.
- If use is not allowed by statute (ORS 538), the application and fees are returned to the applicant.
- An incomplete application and fees are returned to the applicant.
- Only a complete application receives a tentative priority date, is assigned a caseworker, and moves forward for processing.

3. Initial Review (IR)

- Caseworker reviews application by considering basin plans, water availability, statutory restrictions, and all other appropriate factors.
- Caseworker sends IR report to Applicant.
- Four days after date of the IR, it is included in Department's weekly Public Notice.
- Public comments must be submitted within 30 days after the Public Notice.

4. Proposed Final Order (PFO)

- Caseworker evaluates application against required criteria and develops draft permit, if appropriate.
- PFO includes instructions for filing of protests.
- Caseworker considers public comments and mails PFO to Applicant.
- The PFO is included in Department's weekly Public Notice.
- Public protests to the PFO must be submitted within 45 days after the Public Notice.

5. Final Order (FO)

- If no protest is filed, Final Order is issued.

The protest process

If one or more protests are filed, the process consists of:

- settlement discussion;
- contested case hearing;
- Proposed Order;
- period of time to file exceptions; or
- possible hearing by Water Resources Commission.
- Final Order is issued.

Permit holder responsibilities

- Comply with all water use conditions of the permit.
- Advise Department of address change or assignment to new permit holder.
- If need arises, request extension of time or authorize cancellation of permit.
- Submit timely claim of beneficial use (COBU) to the Department.
- Most permits require COBU to be prepared by a Certified Water Right Examiner.
- Permits may be canceled by the permit holder or by the Department for failure to comply with or one or more permit conditions.

STOP PROCESSING REQUEST FORM

FOR GROUNDWATER, SURFACE WATER AND REGULAR RESERVOIR APPLICATIONS

- Stop processing deadline is within 14 days of Initial Review.

Applicant notification to withdraw Water Right Application **G-19267**.

After reviewing the Initial Review for my application, I request that processing be stopped, and fees be refunded (minus a \$310 processing fee). I understand that without a valid permit, I may not legally use the water as requested in my application.

Signature _____ Date _____

Signature _____ Date _____

Under ORS 537.150(5) and 537.620(5), timely submission of this request authorizes that the water right application process be stopped, and all filing fees (except \$310 processing fee) be returned.

- This notice must be received by the Water Resources Department no later than:

November 1, 2024

- Return the notice to:

OWRD, Water Right Services Division
STOP PROCESSING
725 Summer Street, NE - Suite A
Salem, OR 97301-1266
