



## Water Right Application Initial Review

March 28, 2025

NEXGEN PLANT SCIENCE CENTER, LLC  
ATTN: KENNETH HIGNIGHT  
33725 COLUMBUS ST SE  
ALBANY OR 97322

Reference: Application G-19352

This document is to inform you of the preliminary analysis of the water-use permit application and to describe your options. In determining whether an application may be approved, the Water Resources Department (Department) must consider the factors listed below, all of which must be favorable to the proposed use if it is to be allowed. Based on the information supplied, the Department has made the following preliminary determinations:

### **Preliminary Determinations under Oregon Administrative Rule (OAR) 690-310-0080:**

1. Application G-19352 proposes the appropriation of 0.31 cubic foot per second (CFS) of water from Well 1 (LINN 10407) and Well 2 in Oak Creek Basin, further limited to 4.5 acre-feet (AF) annually for irrigation of 1.8 acres from March 1 through October 31, and 28.75 AF annually for nursery use on 11.5 acres from January 1 through December 31 of each year.
2. The proposed use is not prohibited by law or rule except where otherwise noted below.
3. Uses included in nursery use are included in irrigation and agriculture use, both of which are allowed under the Willamette Basin Program (OAR 690-502-0160(2)).
4. The proposed groundwater use is not within a designated critical groundwater area. OAR 690-310-0080(1)(a).
5. An assessment of groundwater availability has been completed by the Department. A copy of this assessment is in the file and can be viewed on the Department's website. Groundwater for the

**Please note:** Applications are evaluated using the rules in effect at the time the application is accepted as complete. To view the rules relevant for this application, please visit: <https://secure.sos.state.or.us/oard/displayCompilations> and navigate to Chapter 690 (Water Resources Department).

proposed use is not over-appropriated. In addition, the Department has determined that the proposed groundwater use will not have the potential for substantial interference (PSI) with surface water. OAR 690-009-0040. Therefore, water is available for the proposed use. OAR 690-310-0080(1)(b); OAR 690-300-0010(57).

6. If properly conditioned (and if authorized), the proposed use of groundwater will not injure other water rights.
7. The proposed use is not located within or above any state or federal scenic waterway.
8. The application proposes a diversion rate for irrigation that is in excess of the general basin-wide standard, and the applicant has not submitted information that demonstrates the need for the higher rate for the Department to consider. In the absence of other information, if the application is approved, the rate allowed for irrigation will be limited to 0.023 CFS (or 1/80th of one CFS per acre).
9. Documentation has been submitted from the relevant land-use planning jurisdiction that indicates the proposed use is allowed outright.
10. See **Additional Information Required** section below for deficiencies with the application.

Summary of Preliminary Determinations
<p><b>The appropriation of 0.31 CFS of water from Well 1 (LINN 10407) and Well 2 in Oak Creek Basin, further limited to 0.023 CFS and 4.5 AF annually for irrigation of 1.8 acres from March 1 through October 31, and 28.75 AF annually for nursery use on 11.5 acres from January 1 through December 31 of each year may be allowable. See <u>Additional Information Required</u> section below for more details.</b></p>

**Additional Information Required:**

Additional information is required to process your application prior to issuance of any Proposed Final Order that may recommend approval. Please provide the following:

- A. The map submitted does not meet the requirements of OAR 690-310-0050(4)(b). Please provide a map that shows the location of all main canals, ditches, pipelines, or flumes.

**Please submit this information no later than May 1, 2025.** If you are unable to submit the information listed above by this date, you may request an administrative hold for up to an additional 180 days. You must submit the request in writing, stating how much more time is needed and why you need additional time. If an administrative hold is granted, your application will not be processed further until the requested information is received or the extended deadline has passed.

If we do not receive the information requested above or a request for an administrative hold by the above date, the Department may reject the application.

## **Public Comment:**

Public interest issues and/or public comments will be addressed as the Department prepares a Proposed Final Order. If significant public interest issues are identified, they could have an impact on the eventual outcome of the application.

### **At this time, you must decide whether to proceed or to withdraw the application.**

- **To Proceed** - If you choose to proceed with the application, you do not have to notify the Department. The application will be placed on the Department's Public Notice to allow others the opportunity to comment. After the comment period the Department will complete a public interest review and issue a Proposed Final Order.
- **To Withdraw** - You may withdraw the application and receive a refund (minus a \$310 processing fee). You must notify the Department **in writing** by **April 11, 2025**. For your convenience you may use the enclosed "STOP PROCESSING" form.

### **If a permit is issued, it will likely include the following conditions:**

1. Construction of the well shall begin within five years of the date of permit issuance. The deadline to begin construction may not be extended. This permit is subject to cancellation proceedings if the construction deadline to begin is missed.
2. If the number, location, source, or construction of any well deviates from that proposed in the permit application or required by permit conditions, this permit may not be valid, unless the Department authorizes the change in writing.
3. **Water Use Measurement, Recording, and Reporting:**
  - A. Before water use may begin under this permit, the permittee shall install a totalizing flow meter at each point of appropriation. The permittee shall maintain the device in good working order.
  - B. The permittee shall allow the watermaster access to the device; provided however, where any device is located within a private structure, the watermaster shall request access upon reasonable notice.
  - C. The permittee shall keep a complete record of the volume of water used each month, and shall submit an annual report which includes the recorded water-use measurements to the Department annually, or more frequently as may be required by the Director. Further, the Director may require the permittee to report general water-use information, including the place and nature of use of water under the permit.
  - D. The Director may provide an opportunity for the permittee to submit alternative measuring and reporting procedures for review and approval.

#### 4. Groundwater Level Measurement, Reporting, and Shut-Off Condition:

For each well on this authorization, beginning on the permit signature date for existing wells or in the year well construction is completed for new wells, and each year thereafter, the permit holder must report a static water-level measurement (“measurement”) taken in March. The measurement is required whether the well is used or not. If pumping is to commence following completion of the well and prior to the next March, then a measurement must be made at least one week following well completion and before pumping commences.

Measurements must be properly reported within 30 days of measurement using forms specified by the Department. A measurement will be properly reported if the submission includes all required information as listed in the document attached. Measurements must be made with equipment that is accurate to the standards specified in Oregon Administrative Rule (OAR) 690-217-0045. Measurements must be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed land surveyor, licensed well constructor, pump installer licensed by the Construction Contractors Board, or Department staff. The Department is not responsible for regular measurement of the static water level, but Department staff may measure the well during the normal course of groundwater level monitoring or to confirm the submitted measurement(s).

For each well on this permit, the Department will establish a reference groundwater level using the best available data. The reference level is intended to represent the highest elevation (shallowest depth) static water level that has been measured or can be reasonably estimated to have existed within each well at any time before its reference level is set. If Annual High Water Levels have been increased measurably by human activity, then the Department may set a different reference level using best available information. If the permit holder fails to measure and report the static water level within 12 months of permit issuance, or of completion of the well(s), then Department staff will estimate the static water level using available data, including measurements in surrounding wells. In case the permit is amended or the subsequent certificate is transferred, the Department may establish a new reference level for any new or additional wells under new permits or certificates issued under this right. The reference level for a new or additional well should reflect the highest static water level in that well or, if that measurement occurred after the time represented by the original reference level, then the water level that would have been measured in that well, if the well existed and was measured at the time represented by the original reference level.

All water use authorized under this permit must immediately stop if any of the following occur:

- A. Any annual high elevation static groundwater level in any well on this permit declines 25 or more feet below the reference level for that well, or
- B. Groundwater levels are not measured and properly reported as specified above for any completed well that is authorized on the permit for two consecutive years, or
- C. Hydraulic interference contributes to a decline of 25 or more feet in any neighboring well with senior priority, at any time during the year.

The Department will determine when any of the above conditions have occurred and may order the permit holder to stop all water use under this permit. The permit holder is also responsible for stopping all water use if they become aware that any of the conditions have occurred, even without notice from the Department. Following such a stop, water use under this permit will not be allowed and may only resume once the permit holder receives notice from the Department. If the permit holder fails to stop use, then the Department may take control of the controlling works of any wells authorized under this permit and may reduce the amount of groundwater pumped until the unlawful use is eliminated.

The permit holder acknowledges that one or more of the conditions requiring stoppage of use may occur prior to any use of any well on this permit.

The Department may allow the permit holder to pause annual water level measurement and reporting requirements from some of the permitted wells if measurements from those wells are redundant with other data being collected by the Department. The permit holder must receive written notification of such an allowance before stopping measurements. If this happens, the Department may reinstate the measurement requirements at any time.

#### **5. Well Identification Tag:**

Prior to using water from any well listed on this permit, the permittee shall ensure that the well has been assigned an OWRD Well Identification Number (Well ID tag), which shall be permanently attached to the well. The Well ID shall be used as a reference in any correspondence regarding the well, including any reports of water use, water level, or pump test data.

The water source identified in the application may be affected by an Agricultural Water Quality Management Area Plan. These plans are developed by the Oregon Department of Agriculture (ODA) with the cooperation of local landowners and other interested stakeholders, and help to ensure that current and new appropriations of water are done in a way that does not adversely harm the environment. You are encouraged to explore ODA's website at [www.oregon.gov/ODA](http://www.oregon.gov/ODA) to learn more about the plans and how they may affect the proposed water use.

**For Further Information:**

Feel free to contact me at [Amanda.L.Mather@water.oregon.gov](mailto:Amanda.L.Mather@water.oregon.gov) or 971-718-7937 if you have any questions regarding the contents of this letter or the application. Please include the application number in all correspondence. General questions about water rights and water use permits should be directed to our customer service staff at 503-986-0900. When corresponding by mail, please use this address: Amanda Mather, Oregon Water Resources Department, 725 Summer St NE Ste A, Salem OR 97301-1266. Our fax number is 503-986-0901.

Sincerely,

*Amanda Mather*

Amanda Mather  
Water Rights Program Analyst  
Oregon Water Resources Department

Enclosures: Application Process Description  
Stop Processing Request Form

G-19352  
WAB: No PSI  
Proposed to Approve

# APPLICATION FACT SHEET

Application File Number: G-19352

Applicant: NEXGEN PLANT SCIENCE CENTER, LLC

County: LINN

Watermaster: LANAYA F. BLAKELY, #2, NWR

Priority Date: FEBRUARY 21, 2023

Source: WELL 1 (LINN 10407) AND WELL 2 IN OAK CREEK BASIN

Use: IRRIGATION OF 1.8 ACRES AND NURSERY USE ON 11.5 ACRES

Quantity: 0.31 CUBIC FOOT PER SECOND, FURTHER LIMITED TO 4.5 ACRE-FEET ANNUALLY FOR IRRIGATION AND 28.75 ACRE-FEE ANNUALLY FOR NURSERY USE

Period of Use: IRRIGATION – MARCH 1 THROUGH OCTOBER 31  
NURSERY USE – JANUARY 1 THROUGH DECEMBER 31

Basin Name & Number: WILLAMETTE, #2

Well Location(s):

POA Name	Twp	Rng	Mer	Sec	Q-Q	Measured Distances
WELL 1 (LINN 10407)	12 S	3 W	WM	5	NW NE	10 FEET SOUTH AND 2210 FEET WEST FROM NE CORNER, SECTION 5
WELL 2	12 S	3 W	WM	5	NW NE	10 FEET SOUTH AND 1940 FEET WEST FROM NE CORNER, SECTION 5

Place of Use:

IRRIGATION USE					
Twp	Rng	Mer	Sec	Q-Q	Acres
12 S	3 W	WM	5	NW NE	1.8

NURSERY USE					
Twp	Rng	Mer	Sec	Q-Q	Acres
12 S	3 W	WM	5	NE NE	6.6
12 S	3 W	WM	5	NW NE	4.9

**PUBLIC NOTICE DATE: April 1, 2025**

**14 DAY STOP PROCESSING DEADLINE DATE: April 11, 2025**

**30 DAY COMMENT DEADLINE DATE: May 1, 2025**

## **APPLICATION PROCESS DESCRIPTION FOR GROUNDWATER, SURFACE WATER AND REGULAR RESERVOIR APPLICATIONS**

In order to use the waters of Oregon, an application must be submitted and a permit obtained from the Water Resources Department. The water must be used for beneficial purpose without waste. For more information about water right topics, weekly public notice, forms and fees please visit our website at: [www.oregon.gov/owrd](http://www.oregon.gov/owrd)

### **1. Pre-application considerations**

- Follow instructions in the application packet.
- If you have questions about completing an application or would like to arrange a pre-application conference contact the Department's Water Rights Customer Service Group at (503) 986-0900.

### **2. Application filing**

- Application with fee is received by the Department.
- Department determines completeness of application.
- If use is not allowed by statute (ORS 538), the application and fees are returned to the applicant.
- An incomplete application and fees are returned to the applicant.
- Only a complete application receives a tentative priority date, is assigned a caseworker, and moves forward for processing.

### **3. Initial Review (IR)**

- Caseworker reviews application by considering basin plans, water availability, statutory restrictions, and all other appropriate factors.
- Caseworker sends IR report to Applicant.
- Four days after date of the IR, it is included in Department's weekly Public Notice.
- Public comments must be submitted within 30 days after the Public Notice.

### **4. Proposed Final Order (PFO)**

- Caseworker evaluates application against required criteria and develops draft permit, if appropriate.
- PFO includes instructions for filing of protests.
- Caseworker considers public comments and mails PFO to Applicant.
- The PFO is included in Department's weekly Public Notice.
- Public protests to the PFO must be submitted within 45 days after the Public Notice.

### **5. Final Order (FO)**

- If no protest is filed, Final Order is issued.

#### ***The protest process***

If one or more protests are filed, the process consists of:

- settlement discussion;
- contested case hearing;
- Proposed Order;
- period of time to file exceptions; or
- possible hearing by Water Resources Commission.
- Final Order is issued.

#### ***Permit holder responsibilities***

- Comply with all water use conditions of the permit.
- Advise Department of address change or assignment to new permit holder.
- If need arises, request extension of time or authorize cancellation of permit.
- Submit timely claim of beneficial use (COBU) to the Department.
- Most permits require COBU to be prepared by a Certified Water Right Examiner.
- Permits may be canceled by the permit holder or by the Department for failure to comply with or one or more permit conditions.



**STOP PROCESSING REQUEST FORM**

**FOR GROUNDWATER, SURFACE WATER AND REGULAR RESERVOIR APPLICATIONS**

---

- Stop processing deadline is within 14 days of Initial Review.

Applicant notification to withdraw Water Right Application **G-19352**.

After reviewing the Initial Review for my application, I request that processing be stopped, and fees be refunded (minus a \$310 processing fee). I understand that without a valid permit, I may not legally use the water as requested in my application.

Signature \_\_\_\_\_ Date \_\_\_\_\_

Signature \_\_\_\_\_ Date \_\_\_\_\_

Under ORS 537.150(5) and 537.620(5), timely submission of this request authorizes that the water right application process be stopped, and all filing fees (except \$310 processing fee) be returned.

- This notice must be received by the Water Resources Department no later than:

**April 11, 2025**

- Return the notice to:

OWRD, Water Right Services Division  
STOP PROCESSING  
725 Summer Street, NE - Suite A  
Salem, OR 97301-1266

---